

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 292 / 2025

सिस्टम टेंडर नं.172476

कोरबा दिनांक 22.07.2025

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि - 20.08.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 20.08.2025 सायंकाल 4.00 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	घरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 36 अंतर्गत प्रा.शाला सतनाम नगर रिस्दी में अहाता निर्माण कार्य (जि.ख.न्या.मद)	13.00	9750/-	03 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	20.08.2025 से

शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पैन नम्बर, वैध जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाइन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं घरोहर राशि FDR/TDR, शपथपत्र का स्कैन काफी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात् का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता/Form- 5A) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में पलाई एश ग्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कड़िका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संवध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।

प्रतिलिपि:-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		22.07.2025	15.30	22.07.2025	15.30	Release Tender
2		Bid Submission	22.07.2025	15.30	18.08.2025	17.30	
3		Physical Document Submission	22.07.2025	15.30	20.08.2025	15.00	
4	Tender Open		18.08.2025	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Name of Work : **CONSTRUCTION OF BOUNDARY WALL IN P.S. SATNAM NAGAR RISHDI AT WARD NO-31**
 As per SOR : **SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]**

S.N REF ITEM DESCRIPTION

UNIT

QTY

RATE

AMOUNT

1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	136.15	185.00	25,187.75
2	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	25.25	65.00	1,641.25
3	1.19	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	30	242.00	7,260.00
4	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	178.52	139.00	24,814.28
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	93	297.00	27,621.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	46.04	235.00	10,819.40
	1.8	Beams, lintels, cantilevers & walls	sqm	29.54	202.00	5,967.08
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	23.77	2659.00	63,204.43
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	0.75	4073.00	3,054.75
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	70.22	4163.00	292,325.86
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	2.1	Thermo-Mechanically treated bars FE 415	kg	5617.6	54.50	306,159.20
8	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)				
9	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	67.76	3263.00	221,100.88
10	9.3	Steel work in tubular (round, square or rectangular hollow tubes etc.)	cum	48.96	121.00	5,924.16

S.N	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.				
	3.1 Electric resistance or induction butt welded tubes Grade-250	kg	250	88.50	22,125.00
11	11.1 Providing and making 6mm thick cement plaster of mix:				
	1.2 In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	42.9	87.00	3,732.30
12	11.2 Providing and making 12mm thick cement plaster of mix:				
	2.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	395	91.50	36,142.50
13	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	380.6	107.00	40,724.20
14	12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.				
	3.1 Size 600x600mm	sqm	93.24	1151.00	107,319.24
15	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	280.55	94.50	26,511.98
16	14.11 Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade.				
	1.1 On new work (two or more coats)	sqm	205	52.50	10,762.50
17	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	5.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	638	56.00	35,728.00
18	14.5 White washing with lime to give an even shade.				
	5.1 On new work (Three or more coats)	sqm	540	9.40	5,076.00
19	14.22 Painting on new work (two or more coats) to give an even shade with:				
	2.1 Satin synthetic enamel paint	sqm	27.36	55.00	1,504.80

As per Estimate Amount Rs. 1,284,706.56
 Extra for Internal Electrification Add Above 1.2 % 15,416.48
 00.0 1,300,123.04
 Say Rs.


 Sub Engineer
 Nagar Palik Nigam,
 Korba


 Asst. Engineer
 Nagar Palik Nigam,
 Korba

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of Work : CONSTRUCTION OF BOUNDRY WALL IN P.S. SATNAM NAGAR RISHDI AT WARD NO-31
As per SOR SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
		-COL.	6	1.50	1.50	1.50	20.25			
			2	6.00	0.50	0.50	3.00			
			2	5.00	0.50	0.50	2.50			
			1	150.00	0.40	0.40	24.00			
			50	1.20	1.20	1.20	86.40			
						Total	136.15	cum	185.00	25,187.75
2	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
							25.25			
						Total	25.25	cum	65.00	1,641.25
3	1.19	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		ramming and watering, including dressing etc. complete.								
			1	6.00	5.00	1.00	30.00			
						Total	30.00	cum	242.00	7,260.00
4	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
		-F2	6X4	1.00		0.40	9.60			
		-F3	6X4	0.60		0.30	4.32			
		-COL. B.P.L.	6	1.00		0.90	5.40			
		-P.B.	2X2	6.00		0.30	7.20			
			2X2	5.00		0.30	6.00			
		-BOUNDARY COL	50	0.80		0.40	16.00			
			50	1.00		0.80	40.00			
		-P.B.	1X2	150.00		0.30	90.00			
						Total	178.52	sqm	139.00	24,814.28
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape								
			6	1.00		3.00	18.00			
			50	1.00		1.50	75.00			
						Total	93.00	sqm	297.00	27,621.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
			1	6.60	6.50		42.90			
		-SIDE	1	24.20		0.13	3.14			
						Total	46.04	sqm	235.00	10,819.40
	1.8	Beams, lintels, cantilevers & walls								
		-L.B	2X2	5.00		0.20	4.00			
			2X2	6.00		0.20	4.80			

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		-CHHJJA	1	4.40	0.60		2.64			
		-WINDOW	2	1.50	0.60		1.80			
		-S.B.	2X2	6.00		0.30	7.20			
			2X1	6.50		0.30	3.90			
		-SUS BEAM	1x2	6.50		0.40	5.20			
						Total	29.54	sqm	202.00	5,967.08
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								
			6	1.50	1.50	0.10	1.35			
		-WALL	2	5.00	0.40	0.10	0.40			
			2	6.00	0.40	0.10	0.48			
		-FLOOR	1	6.00	5.00	0.10	3.00			
			1	4.40	1.00	0.10	0.44			
			50	1.20	1.20	0.10	7.20			
			1	150.00	0.40	0.10	6.00			
			1	7.00	7.00	0.10	4.90			
						Total	23.77	cum	2659.00	63,204.43
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		-p.protection	2	6.00	0.20	0.15	0.36			
			2	6.50	0.20	0.15	0.39			
						Total	0.75	cum	4073.00	3,054.75
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		-F1	6	1.50	1.50	0.30	4.05			

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		-F2	6	1.00	1.00	0.40	2.40			
		-F2	6	0.60	0.60	0.30	0.64			
		-COL. B.P.L.	6	0.20	0.30	0.90	0.32			
		-P.B.	2	6.00	0.20	0.30	0.72			
			2	5.00	0.20	0.30	0.60			
		-COL	6	0.20	0.30	3.20	1.15			
		-L.B	2	6.00	0.20	0.20	0.48			
			2	5.00	0.20	0.20	0.40			
		-CHHAJJA	1	6.00	0.60	0.10	0.36			
		-S.B	2	6.00	0.20	0.40	0.96			
			2	6.50	0.20	0.40	1.04			
		-SUS BEAM	1	6.50	0.30	0.50	0.97			
		-Slab	1	6.80	6.60	0.13	5.83			
		-BOUNDRY	50	1.20	1.20	0.30	21.60			
		-F2	50	0.80	0.80	0.40	12.80			
		-COL BPL	50	0.20	0.30	0.80	2.40			
		-P.B.	1	150.00	0.20	0.30	9.00			
		-COL	50	0.20	0.30	1.50	4.50			
						Total	70.22	cum	4163.00	292,325.86
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	12.1	Thermo-Mechanically treated bars FE 415								
			70.22	80.00			5617.60			
						Total	5617.60	kg	54.50	306,159.20
8	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
		-below plinth	2	6.00	0.20	1.00	2.40			
			2	5.00	0.20	1.00	2.00			
		-above plinth	1	6.00	0.20	3.30	3.96			
		-stair	2	2.00	1.20	0.20	0.96			
			2	2.00	0.90	0.20	0.72			


SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
			2	2.00	0.60	0.20	0.48			
			2	2.00	0.30	0.20	0.24			
		-BOUNDARY WALL BPL	1	150.00	0.20	0.40	12.00			
			1	150.00	0.20	1.50	45.00			
						Total	67.76	cum	3263.00	221,100.88
9	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								
							3.96			
							45.00			
						Total	48.96	cum	121.00	5,924.16
10	9.3	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.								
	3.1	Electric resistance or induction butt welded tubes Grade-250								
		-MAIN GATE					250.00			
						Total	250.00	kg	88.50	22,125.00
11	11.1	Providing and making 6mm thick cement plaster of mix:								
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)								
			1	6.60	6.50		42.90			

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
12	11.2	Providing and making 12mm thick cement plaster of mix:				Total	42.90	sqm	87.00	3,732.30
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
			1	6.00		4.50	27.00			
			1	150.00		1.80	270.00			
			2	7.00		3.50	49.00			
			2	7.00		3.50	49.00			
						Total	395.00	sqm	91.50	36,142.50
13	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
			1	6.00		3.50	21.00			
			1	150.00		1.80	270.00			
			4	7.00		3.20	89.60			
						Total	380.60	sqm	107.00	40,724.20
14	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.								
	13.1	Size 600x600mm								
			1	6.20	5.20		32.24			
			2	2.00	3.00		12.00			
			1	7.00	7.00		49.00			
						Total	93.24	sqm	1151.00	107,319.24
15	14.13	Providing and applying 2mm thick ready mix								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even:								
			2	6.00		3.60	43.20			
			4	1.00		3.50	14.00			
			1	6.50	5.50		35.75			
			4	7.00		3.50	98.00			
			4	7.00		3.20	89.60			
						Total	280.55	sqm	94.50	26,511.98
16	14.11	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade.								
	11.1	On new work (two or more coats)								
							115.00			
							90.00			
						Total	205.00	sqm	52.50	10,762.50
17	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
			2	150.00		1.80	540.00			
							98.00			
						Total	638.00	sqm	56.00	35,728.00
18	14.5	White washing with lime to give an even shade.								
	5.1	On new work (Three or more coats)								
			2	150.00		1.80	540.00			

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
19	14.22	Painting on new work (two or more coats) to give an even shade with:				Total	540.00	sqm	9.40	5,076.00
	22.1	Satin synthetic enamel paint								
			1.5	4.00		1.80	10.80			
			2	1.20		2.10	5.04			
			4X2	1.20		1.20	11.52			
						Total	27.36	sqm	55.00	1,504.80

As per Estimate Amount Rs. 1284706.56
 Extra for Internal Electrification Add Above 1.2% 15416.48
 00.0 1,300,123.04
 Say Rs.


 Sub Engineer
 Nagar Palik Nigam,
 Korba


 Asst. Engineer
 Nagar Palik Nigam,
 Korba