



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - सफ़ेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

कोसाबाड़ी जोन

फा.क्र./8609/8610/कोसाबाड़ी जोन/2020

कोरबा, दिनांक 27.11.2020

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 22.12.2020 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 22.12.2020 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 29 पोड़ीबहार अंतर्गत सत्यनारायण मंदिर के पास सार्वजनिक सांस्कृतिक शेड का निर्माण कार्य। (महापौर मद 2020-21)	5,00,000/-	5,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	22.12.2020
2	वार्ड क्र. 12 न्यू अमरैयापारा में सी.सी. रोड एवं आर.सी.सी. नाली का निर्माण कार्य। (महापौर मद 2020-21)	8,00,000/-	8,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	22.12.2020

निविदा की शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
6. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्रि नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।



8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
 9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
 10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
 11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
 12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
 13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
 14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
 15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
 16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष हेतु साथ ही 05 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
 23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि को निविदा संबंधी कार्यवाही मानी जावेगी।
- नोट:-
1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
 2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


Abstract


Name of Work :- Construction of Sarwajanik Sanskritik Shed Near Satyanarayan Mandir at Podibahar Ward No. 29

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	In all types of soil	23.74	Cum	185.00	4391.16
2	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	23.74	Cum	65.00	1543.10
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	17.73	Cum	371.00	6577.09
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.				
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	11.168	Cum	2659.00	29695.71
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.00	Cum	4073.00	16292.00
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.				
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	29.32	Cum	4163.00	122061.24
6	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	18.44	Cum	97.50	1797.90
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:				
	Thermo-Mechanically treated bars	2932.00	kg	54.50	159794.00
8	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	Foundations, footings, base of columns and plinth beam in any shape and size.	50.4	Sqm	139.00	7005.60
	Columns, Pillars, Piers and likes- rectangular or square in shape	72.00	Sqm	297.00	21384.00
	Beams, lintels, cantilevers & walls	60.30	Sqm	202.00	12180.60
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	94.71	Sqm	235.00	22256.85
	Weather shade, chhajja, Cornices and mouldings	2.34	Sqm	294.00	687.96
9	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in:				
	Cement Mortar 1:5 (1 cement : 5 coarse sand)	14.40	Cum	3350.00	48240.00
10	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	6.60	Cum	121.00	798.60
11	Providing and making 6mm thick cement plaster of mix:				
	In Cement mortar 1:4 (1 cement : 4 fine sand)	92.85	Sqm	87.00	8077.95

Sno	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
12	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	37.44	Sqm	96.50	3612.96
13	15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)	43.68	Sqm	113.00	4935.84
14	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	200.00	Sqm	94.50	18900.00
15	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	12.60	Sqm	55.00	693.00
16	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 110 mm dia pipe.	5.00	Mtr.	267.00	1335.00
17	14.9 Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	100.00	Sqm	38.00	3800.00
18	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade. On new work (Two or more coats applied @ 3.84 kg/10 sqm)	105.00	Sqm	38.00	3990.00
As per SOR Total Estimate Amount Rs.					500050.56
Say Amount Rs.					500000.00


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE


Name of Work :- Construction of Sarwajanik Sanskritik Shed Near Satyanarayan Mandir at Podibahar Ward No. 29


As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	In all types of soil								
		12	1.20	1.20	1.20	20.74			
	Long Wall	2	7.10	0.40	0.30	1.70			
	Short Wall	2	5.40	0.40	0.30	1.30			
						23.74	Cum	185.00	4391.16
2	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M.					23.74	Cum	65.00	1543.10
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		12	1.20	1.20	0.10	1.73			
		1	10.00	8.00	0.20	16.00			
						17.73	Cum	371.00	6577.09
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm)								
		12	1.20	1.20	0.10	1.73			
		2	10.00	0.40	0.10	0.80			
		2	8.00	0.40	0.10	0.64			
		1	10.00	8.00	0.10	8.00			
						11.17	Cum	2659.00	29695.71
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		1	10.00	8.00	0.05	4.00			
						4.00	Cum	4073.00	16292.00
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form								
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	1 Footing	12	1.20	1.20	0.40	6.91			
	Column Below Plinth	12	0.30	0.20	0.80	0.58			
	Plinth Beam	2	10.00	0.20	0.30	1.20			
		4	8.00	0.20	0.30	1.92			
	Column	12	0.30	0.20	3.00	2.16			

Sno	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
	S/B	2	10.50	0.30	0.30	1.89			
		4	8.50	0.30	0.30	3.06			
	Slab	1	10.50	8.50	0.13	11.60			
						29.32	Cum	4163.00	122061.24
6	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					18.44	Cum	97.50	1797.90
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:								
	Thermo-Mechanically treated bars					2932.00	kg	54.50	159794.00
8	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	Foundations, footings, base of columns and plinth beam in any shape and size.								
		12x4	0.30		0.80	11.52			
		12x4	0.20		0.80	7.68			
		2x2	10.00		0.30	12.00			
		4x2	8.00		0.30	19.20			
						50.40	Sqm	139.00	7005.60
	Columns, Pillars, Piers and likes- rectangular or square in shape								
		12x4	0.30		3.00	43.20			
		12x4	0.20		3.00	28.80			
						72.00	Sqm	297.00	21384.00
	Beams, lintels, cantilevers & walls								
	L/B	2x2	10.00		0.30	12.00			
		2x2	8.50		0.30	10.20			
	S/B	3x2	10.50		0.30	18.90			
		4x2	8.00		0.30	19.20			
						60.30	Sqm	202.00	12180.60
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in								
		1	10.50		8.50	89.25			
		1	42.00		0.13	5.46			
						94.71	Sqm	235.00	22256.85
	Weather shade, chhajja, Cornices and mouldings								
		2	1.50		0.60	1.80			
		2	2.70		0.10	0.54			
						2.34	Sqm	294.00	687.96
9	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in: Cement Mortar 1:5 (1 cement : 5 coarse sand)								
		2	10.00	0.30	0.50	3.00			
		4	8.00	0.30	0.50	4.80			
		1	10.00	0.20	3.30	6.60			
						14.40	Cum	3350.00	48240.00
10	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					6.60	Cum	121.00	798.60

Sno	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
11	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)								
		1	10.50		8.50	89.25			
		12	1.00		0.30	3.60			
						92.85	Sqm	87.00	8077.95
12	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)								
		1	10.40		3.60	37.44			
						37.44	Sqm	96.50	3612.96
13	15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:5 (1 cement : 5 fine sand)								
		1	10.40		4.20	43.68			
						43.68	Sqm	113.00	4935.84
14	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					200.00	Sqm	94.50	18900.00
15	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	2x2	1.50		2.10	12.60			
						12.60	Sqm	55.00	693.00
16	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 110 mm dia pipe.					5.00	Mtr.	267.00	1335.00
17	14.9 Distemping with acrylic washable distemper to give an even shade. On new work (Two or more coats)					100.00	Sqm	38.00	3800.00
18	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade. On new work (Two or more coats applied @					105.00	Sqm	38.00	3990.00
As per SOR Total Estimate Amount Rs.									500050.56
Say Amount Rs.									500000.00


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)