

# कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

क्र.सं. 135/2624

रिस्टम टेंडर नं. 157167

कोरबा दिनांक 05.08.2024

## तृतीय ई-निविदा आमंत्रण सूचना

नगरपालिका नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पञ्जीयन प्रणाली अंतर्गत सक्षम श्रेणी में पञ्जीकृत ठेकेदारों से प्रमुख नगरीय लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 एव विपुत (01.06.2020) से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक) नामित शीटों के साथ प्रेषित अनुसार प्रतिशत दर पर ई-प्रोक्चरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रण की जाती है-

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	घरोहर राशि (FDR/FDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	साईड के 29 पोडीवहार में वडा समाज के सामुदायिक भवन के पास न.पानि कोरबा द्वारा निर्मित सामुदायिक भवन के उपर छत निर्माण (विभागीय मद)	25.00	18800/-	4 माह	750/-	वर्ग डी एव पत्र श्रेणी	20.08.2024 से

शर्तें-

- निविदा दरें प्रस्तुत की एसआर से कम या अधिक प्रतिशत दरों पर दिया जावे की एसआर के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पञ्जीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीडी) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अगले की जानकारी, विगत 3 वर्षों का आयकर बुकता प्रमाण पत्र/पैन नम्बर, जी एस टी पञ्जीयन प्रमाण पत्र एव अमानत राशि के FDR/FDR की प्रति ऑनलाइन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्र नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पञ्जीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड अप्ट एव घरोहर राशि FDR/FDR, शपथपत्र का रकने कापी ऑन लाईन रिस्टम पर अपलोड करना अनिवार्य होगा।
  - अमानत राशि का वैध FDR/FDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल रपीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई चौक रायपुर कोसावाडी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
  - निविदाकार को प्रत्येक निविदा में पञ्जीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभाग में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
  - अमानत राशि का FDR/FDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एव मरम्मत एव सधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पञ्जीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छग भवन और अन्य सन्निर्माण कर्मकार (नियोजन एव सेवा शर्तों का विनियमन) अधिनियम 1996 एव तदंतर्गत निर्धारित नियमों के तहत पञ्जीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का विल एव टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का विल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एसओआर एव निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफडीआर, पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एनएससी जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तातरणीय होगा एवं शर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा प्रपत्र फार्म -ए की कड़िका 11 अनुसार एस्कलेशन देय नहीं होगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सार्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
- ठेकेदारों को निर्माण कार्य के दौरान निर्माण एव अपशिष्ट प्रबंधन नियम 2016 में किये गये प्रावधानों का पालन करना होगा।
- ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान बजट आवंटन और राशि उपलब्ध होने पर किया जाएगा।

प्रतिलिपि-

प्रोग्रामर, सचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

कार्यपालक (अभिमत)  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)

### Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		05 08 2024	12.00	05 08 2024	12.00	Release Tender
2		Bid Submission	05 08 2024	12.00	16 08 2024	17.30	
3		Physical Document Submission	05 08 2024	12.00	20 08 2024	15.00	
4	Tender Open		20 08 2024	16.00	--	--	

  
**EXECUTIVE ENGINEER**  
**KORBA (CG)**  
 For, Commissioner Korba (C.G.)

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)**

**DETAILED ESTIMATE**

Name of Work : CONSTRUCTION OF HALL ABOVE COMMUNITY BUILDING NEAR THE COMMUNITY BUILDING OF CHANDRA SAMAJ BUILT BY N.P.N. KORBA IN WARD NO-29 PODI BAHAR  
 As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
		-stage	6	1.50	1.50	2.00	27.00			
		-for dome	2x6	1.20	1.20	1.20	20.73			
		-p.b	2	19.00	0.40	0.40	6.08			
			2	12.00	0.40	0.40	3.84			
		-for beam	12	1.20	1.20	1.20	20.73			
			2	19.00	0.50	0.50	9.50			
			2	12.00	0.50	0.50	6.00			
		-for gate	3	1.50	1.50	1.50	10.12			
							<b>Total</b>	104.00	cum	185.00
2	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.								
	3.3	In cement mortar.								
			6	1.50	0.20	1.00	1.80			
							<b>Total</b>	1.80	cum	263.00
3	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1.1	Foundations, footings, bases of columns plinth beam,								

N	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		curtain wall in any shape and size and all type of wall below plinth level.								
		-f2	6x4	1.20		0.30	8.64			
		-f3	6x4	0.80		0.40	7.68			
		-col b.pl.	6	1.00		9.00	54.00			
		-p.b	2x2	11.70		0.30	14.04			
			2x2	4.50		0.30	5.40			
		-for i beam	12x4	0.80		0.80	30.72			
			2x2	19.00		0.30	22.80			
			2x2	13.00		0.30	15.60			
		-for gate	3x4	1.20		0.40	5.76			
		-f3	3	1.60		0.40	1.92			
		-p.b.	2x1	6.00		0.30	3.60			
						<b>Total</b>	170.16	sqm	139.00	23652.24
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape								
		-for stage	5	1.00		3.50	17.50			
		-col. for gate	3	1.60		4.00	19.20			
						<b>Total</b>	36.70	sqm	297.00	10899.90
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
			1	12.50	5.10		63.75			
						<b>Total</b>	63.75	sqm	235.00	14981.25
	1.8	Beams, lintels, cantilevers & walls								
			2x2	4.50		0.30	5.40			
		-back	1x2	11.70		0.30	7.02			
		-front	1x2	11.70		0.50	11.70			
		-tie beam	1x2	4.50		0.50	4.50			
		-for gate	1x2	6.00		0.30	3.60			
			1	6.00	0.30		1.80			
						<b>Total</b>	34.02	sqm	202.00	6872.04
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								

REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		6	1.50	1.50	0.10	1.35			
		1	11.70	4.50	0.10	5.26			
					<b>Total</b>	6.61	cum	2659.00	17575.99
1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		1	6.00	3.00	0.15	2.70			
					<b>Total</b>	2.70	cum	4073.00	10997.10
5	3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	-f1	6	1.50	1.50	0.30	4.05			
	-f2	6	1.20	1.20	0.40	3.45			
	-f3	6	0.80	0.80	0.40	1.53			
	-col. b.p.l	6	0.20	0.30	0.90	0.32			
	-p.b.	2	11.70	0.20	0.30	1.40			
		2	4.50	0.20	0.30	0.54			
	-col. above plinth	5	0.30	0.20	3.00	0.90			
	-s.b	1	11.70	0.20	0.30	0.70			
		1	11.70	0.20	0.50	1.17			
		2	4.50	0.20	0.30	0.54			
	-sus beam	1	4.50	0.20	0.50	0.45			
	-slab beam	1	12.30	5.10	0.13	8.15			
	-for I-beam f1	12	1.20	1.20	0.60	10.36			
	-f2	12	0.60	0.60	0.60	2.59			
	-beam	2	19.00	0.20	0.30	2.28			
		2	12.00	0.20	0.30	1.44			
	-for gate f1	3	1.50	1.50	0.30	2.02			
	-f2	3	1.20	1.20	0.40	1.72			
	-col. b.p.l.	3	0.40	0.40	0.40	0.19			
	-p.b.	1	6.00	0.40	0.40	0.96			
	-col.	3	0.40	0.40	3.00	1.44			
	-beam	1	6.00	0.20	0.30	0.36			
					<b>Total</b>	46.56	cum	4163.00	193829.28
6	3.12 Providing and placing in position reinforcement for								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
		R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:									
	12.1	Thermo-Mechanically treated bars FE 415									
			46.56	90.00			4190.40				
							<b>Total</b>	4190.40	kg	54.50	228376.80
7	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:									
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)									
			1	11.70	0.20	3.00	7.02				
		-stair step	2	1.50	1.20	0.15	0.54				
			2	1.50	0.90	0.15	0.40				
			2	1.50	0.60	0.15	0.27				
			2	1.50	0.30	0.15	0.13				
			1	6.00	0.20	0.50	0.60				
							<b>Total</b>	8.96	cum	3263.00	29236.48
8	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:									
							7.72				
							0.60				
							<b>Total</b>	8.32	cum	121.00	1006.72
9	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.									
		-I-Beam 200x100=25kg/mtr	12	6.00	25.00		1800.00				




SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
							<b>Total</b>	63.75	sqm	87.00	5546.25
12	11.2	Providing and making 12mm thick cement plaster of mix:									
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)									
			1	11.70		3.50	40.95				
			2	11.70		1.00	23.40				
			2	4.50		1.00	9.00				
		-stage col.	2	1.00		4.00	8.00				
		gate col.	3	1.60		4.00	19.20				
							<b>Total</b>	100.55	sqm	91.50	9200.32
13	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:									
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)									
			1	11.70		3.50	40.95				
							<b>Total</b>	40.95	sqm	107.00	4381.65
14	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.									
	13.1	Size 600x600mm									
			1	11.70	4.60		53.82				
							<b>Total</b>	53.82	sqm	1151.00	61946.82
15	9.1	Structural steel work in single section including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.									



REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
						400.00			
					Total	400.00	kg	61.50	24600.00
16 14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					400.00			
					Total	400.00	sqm	94.50	37800.00
17 14.12	Applying one coat of cement primer on wall surface (applied @ 0.80 ltrs/10 sqm) complete.					400.00			
					Total	400.00	sqm	23.00	9200.00
18 14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)					400.00			
					Total	400.00	sqm	56.00	22400.00

As per Estimate Amount Rs. 1022568.24  
Say Rs.

  
Sub Engineer  
Nagar Palik Nigam,  
Korba


  
Astt. Engineer  
Nagar Palik Nigam,  
Korba


**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)  
DETAILED ESTIMATE**

Name of Work :- वार्ड क्र. 29 पोड़ीबहार में नगर पालिक निगम, कोरबा द्वारा निर्मित चंद्रा समाज के सामुदायिक भवन के पास सामुदायिक भवन के ऊपर हॉल निर्माण।

As per Sor :- Item Rate

Sno.	ITEM DESCRIPTION	Unit	Qty	Rate	Amount
1	Excavation of Works Contract for self supporting roof on your following building of dimensions as mentioned below shed : (a) Span : 12.00 MTR (Actual) (b) Arch Rise : 1.50 MTR (c) Length : 19.00 MTR (With Projection) (d) Arch Length : 13.40 Mtr (e) No of Bays : 1 No. (f) Area Per Bay : 10 Mtr (g) Building Height : 5.00 Mtr Material Specification : Imported Color Coated Galvalume Sheet : BMT : 1.10 mm APT : 1.15 mm Tolerance : +/- 0.02 mm Coil width : 912 mm Tolerance : +/- 4mm ALZ 150 GMS, 350 Tensile strength Original Embossing of lable with make.	SQM	254.72		

  
Sub-Engineer  
Municipal Corporation  
Korba (C.G.)

  
Asst. Engineer  
Municipal Corporation  
Korba (C.G.)

Executive Engineer  
Municipal Corporation  
Korba (C.G.)