



नगर पालिक निगम, कोरबा (छत्तीसगढ़)

कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

फ़ोन : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

वेबसाइट : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क./42/निर्माण (कोसा.)/2019

कोरबा, दिनांक 29.07.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्रमांक 21 अंतर्गत स्थित पंडित मुकुटधर पाण्डेय साहित्य भवन में शौचालय का निर्माण कार्य । (निगम मद)	1,98,774/-	2000/-	300/-	02 माह	सक्षम श्रेणी	19.08.2019	21.08.2019	27.08.2019

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रायपुर, कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखि तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
3. निविदा प्रपत्र स्वीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जावेगी।
4. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
5. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन का प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र धरोहर राशि निविदा प्रपत्र प्राप्त करने के अंतिम तिथि के 3.00 बजे सायं तक अधोहस्ताक्षरकर्ता के सक्षम आवेदन प्रस्तुत करना अनिवार्य होगा।
6. निविदा प्रपत्र उन्हीं ठेकेदारों को दिया जायेगा, जिन्हें इस प्रकार के कार्य का अनुभव होगा।
7. पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके सक्षम खोले जावेगे।
8. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं मरम्मत एवं संधारण मद के कार्य को छोड़कर 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
9. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
10. ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन काराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।



कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

11. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र देना अनिवार्य होगा।
12. ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
13. निविदा दसों असाप्तमान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एच.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो नांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समादाधि में जमा न करने की दशा में निविदा स्वभाव निरस्त मानी जावेगी।।
14. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
15. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
16. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
17. निविदा प्रपत्र कय कर अथवा वेबसाईट से सीधे डाउनलोड कर निविदा प्रपत्र हेतु निर्धारित राशि की अतिरिक्त डिमॉंड ड्राफ्ट सहित अपनी भरी हुई निविदा नगर पालिक निगम में रजिस्टर्ड/स्वीड पोस्ट द्वारा अमानत राशि के साथ प्रस्तुत करें।

नोट-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समयएवं स्थान माना जावे।

कार्यपालन अभियन्ता

नगर पालिक निगम

कोरबा (छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
ABSTRACT


Name of Work **CONSTRUCTION OF TOILET FOR PT. MUKUTDHAR PANDEY SAHITYA BHAWAN, WARD NO. 21(2)**
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	18.55	185.00	3,431.75
2	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	18.55	65.00	1,205.75
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	2.15	371.00	797.65
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	2.15	2659.00	5,716.85
5	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	6.19	4163.00	25,768.97
6	3.4	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	3.59	97.50	350.02
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	372	54.50	20,274.00
8	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	14.68	139.00	2,040.52
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	11.6	297.00	3,445.20
	1.8	Beams, lintels, cantilevers & walls	sqm	12.16	202.00	2,456.32
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	13.64	235.00	3,205.40
9	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	4.02	3263.00	13,117.26

S.N	RF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
10	7.5	Half brick thick (9cm) brick masonry with modular well burnt clay bricks of crushing strength not less than 35 kg/sqcm and water absorption not more than 20% upto plinth level:				
	9.2	Cement Mortar 1:4 (1 cement : 4 coarse sand)	sqm	1.56	435.00	678.60
11	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	8.80	121.00	1,064.80
12	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	9.1	Size 300x300mm	sqm	9	692.00	6,228.00
13	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.1	Size upto 200x300mm	sqm	50.4	587.00	29,584.80
14	9.16	Providing and fixing M.S. frames of doors, windows, ventilators and cupboards joints mitred and welded with 15x3 mm lugs 10cm long embedded in cement concrete blocks 15x10x10cm of grade M-10 or with wooden plugs and screws or with dash fastener or rawl plugs and screws or with fixing clips or with bolts and nuts as required including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.				
	16.2	Angle-iron frames	kg	60.00	73.50	4,410.00
15	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	160.00	75.00	12,000.00
16	11.1	Providing and making 6mm thick cement plaster of mix:				
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	13.64	87.00	1,186.68
17	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	75.4	96.50	7,276.10
18	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	45.6	113.00	5,152.80
19	14.22	Painting on new work (two or more coats) to give an even shade with:				
	22.1	Satin synthetic enamel paint	sqm	6.3	55.00	346.50
20	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	1.1	White Long pattern W.C. pan of size 580 mm	each	4.00	2459.00	9,836.00
21	18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				
	17.1	White Size 550x450 mm	each	2.00	1430.00	2,860.00

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
22	18.70	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.				
	76.2	110 mm dia pipe.	metre	20.00	267.00	5,340.00
23	19.5	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. CONCEALED WORK including cutting chases and making good the walls etc.,				
	5.1	15 mm nominal outer dia .Pipes.	metre	15.00	133.00	1,995.00
	5.2	20 mm nominal outer dia .Pipes.	metre	30.00	167.00	5,010.00
	5.3	25 mm nominal outer dia .Pipes.	metre	20.00	213.00	4,260.00
24	19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:				
	14.1	Bib cock (400 grams)	each	6.00	382.00	2,292.00
	14.6	Stop cock (concealed) (600 grams)	each	2.00	494.00	988.00
25	19.15	Providing and fixing stainless steel drain jali of approved make/quality.	each	6.00	51.00	306.00
26	19.42	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	Ltr	1000.00	7.30	7,300.00
27	19.18	Providing and fixing gun metal non- return valve (horizontal type) of approved quality (screwed end) :				
	18.1	25 mm nominal bore	each	2.00	413.00	826.00
28	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	0.68	4073.00	2,769.64
29	14.9	Distemping with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)	sqm	89.04	38.00	3,383.52
30	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	45.60	41.00	1,869.60

As per Estimate Amount Rs. 198773.73


Sub Engineer
Nagar Palik Nigam


Asst. Engineer
Nagar palik Nigam

Excutive. Engineer
Nagar palik Nigam