

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

37/निर्माण /2021

सिस्टम टेन्डर नं. 90516

कोरबा, दिनांक 10.01.2022

द्वितीय ई-निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा शासकीय एवं अर्धशासकीय विभागों में व्यवसाय से संबंधित अनुमती ठेकेदारों/ प्रदायकर्ताओं से निविदा लिखित कार्य हेतु शेड्यूल/एस.ओ.आर. अनुसार कम या अधिक प्रतिशत दर पर ई-प्रोक्चुरमेंट (E-Tendring) के माध्यम से निविदाएं आमंत्रित की जाती हैं :-

क्र.	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रु में	कार्यावधि	निविदा खुलने की तिथि
1	नगर पालिक निगम कोरबा क्षेत्रांतर्गत विभिन्न स्थानों पर उर्जा नगरी कोरबा एल.ई.डी. बोर्ड प्रदाय स्थापना एवं संचालन कार्य	37.08	28000.00	4 माह	28.01.2022 से

शर्त :-


1. निविदा ई-प्रोक्चुरमेंट (E-Tendring) के माध्यम से ही स्वीकार किये जाएंगे। निर्धारित तिथि को सायं 5.30 बजे तक ही निविदा डाली जा सकती है।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. निविदा प्राप्त करने के इच्छुक ठेकेदारों को प्रोपाईटरशीप, यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, आयकर प्रमाण पत्र/पैन नं. एवं जी.एस.टी. प्रमाण पत्र, आई.एस.ओ. 9001 सर्टिफिकेट, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र तथा जी.एस.टी. चालान एवं ऑनलाईन जमा किये गये अमानत राशि की स्कैनकापी बेवसाइट पर अपलोड करना अनिवार्य होगा।
4. निविदाकार के पास उद्यम/एम.एस.एम.ई. का रजिस्ट्रेशन सर्टिफिकेट होना अनिवार्य है। उक्त रजिस्ट्रेशन सर्टिफिकेट ऑन लाईन अपलोड करना अनिवार्य होगा।
5. इच्छुक निविदाकार को स्थल निरीक्षण कर स्थल निरीक्षण प्रतिवेदन स्वयं के लेटर हेड में बनाकर कार्यपालन अभियंता, नगर पालिक निगम कोरबा से सत्यापित कराकर ऑनलाईन अपलोड करना अनिवार्य होगा।
6. निविदाकार को उक्त प्रकार के समान कार्यों का विगत 3 वर्षों अंतर्गत किसी भी 1 वर्ष में उक्त लागत का 25 प्रतिशत कार्य का अनुभव प्रमाण पत्र न्यूनतम कार्यपालन अभियंता या उससे ऊपर श्रेणी के सक्षम अधिकारी से जारी अनुभव प्रमाण पत्र संलग्न करना अनिवार्य होगा।
7. उक्त कार्य में "उर्जा नगरी कोरबा" लोगो का ड्राइंग-डिजाइन निविदाकार को ही करवाना होगा एवं उक्त ड्राइंग -डिजाइन का अनुमोदन अधीक्षण अभियंता, न.पा.नि. कोरबा से लिये जाने के पश्चात ही कार्य प्रारंभ किया जावेगा।
8. उक्त कार्य में प्रयुक्त होने वाले मटेरियल का स्पेशिफिकेशन का अनुमोदन अधीक्षण अभियंता से लिया जाना अनिवार्य होगा।
9. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी, जिसमें निविदाकार को 3 साल तक समस्त मरम्मत एवं संधारण कार्य करना अनिवार्य होगा।
10. निविदा अहस्तांतरणीय होगी एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. बिना कारण बताए स्वीकृत/अस्वीकृत या पूर्ण रूप से अमान्य करने का अधिकार सक्षम अधिकारी को रहेगा।
12. किसी भी तरह की विवाद की स्थिति में अंतिम निर्णय लेने का अधिकार सक्षम अधिकारी के पास सुरक्षित रहेगा।
13. उपरोक्त निर्धारित तिथियों में कोई शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम कोरबा की वेब साइट www.korbamunicipal.in पर भी यह टेन्डर उपलब्ध है।
15. अन्य सूचनाएं नगर पालिक निगम साकेत भवन रामपुर कोरबा कार्यालय से प्राप्त की जा सकती हैं।

अधीक्षण अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

Date-Time Detail(s)

Nigam Stage	Contractor Stage	Start		Expiry		Remarks
		Date	Time	Date	Time	
Release Tender		10.01.22	19.30	10.01.22	19.30	Release Tender
	Bid Submission	10.01.22	19.30	27.01.22	17.30	
Tender Open		28.01.22	10.30	--	--	


 SUPERINTENDING ENGINEER
 KORBA (CG)
 For, Commissioner Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT


NG, INSTALLATION, FIXING & COMMISSIONING OF PROPOSED "URJANAGARI KORBA" LED LOGO GLOW SIGN BOARD OF SIZE 20FT X 10FT AT VARIOUS PLACE IN MUNICIPAL CORPORATION, KORBA (C.G.)

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECTRICAL-01.06.2020]

S.N	REF	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	6.58	Supplying, installation, testing and commissioning of Acrylic LED light (a) Specification of Acrylic 3 mm thick x 3 " width x 4 " depth *(imbose) (b) Specification of LED modules :- Each Moduel should have 6 Nos LED of 1 watt				
			200.00	SQFT	2312.00	462400.00
2	6.59	Supply and installation of timer including relay and contactor set complete as required.				
			5.00	Each	3929.00	19645.00
3	6.60	Supplying and installation of SMPS (water proof) for power supply AC input 110/220 V 50/60HZ DC output 12V 30A				
			10.00	Each	5229.00	52290.00
4	6.61	Fabrication and installation of angle iron including angle size 50 mm x 5 mm thick with labour charges including materials as per specification				
			500.00	KG	66.00	33000.00
5	6.62	Providing and fixing aluminium composite panels in approved panel sizes, thickness and shape on aluminium frame work				
	62.1	4 mm thick	18.58	SQM	2404.00	44667.82
6	6.63	Designing providing and fixing aluminium frame work made of special aluminium section on building face with M.S. angle iron brackets fixed on RCC structure with S.S. hold fasteners, including providing and fixing two sided structural adhesive tape of appropriate grade on aluminium section for fixing aluminium/glass panel, sealing on perihphery of frame work by providing EPDM gasket, silicon weather sealant between aluminium frame and building structure.				
		Design, Fixing & Grouting on RCC Structure	100.00	KG	545.00	54500.00
			GROSS TOTAL			666502.82
			TOTAL NUMBER OF SITE = 3			1999508.47
			SAY RS:			1999500.00


Sub. Engg.
Municipal Corporation
Korba (C.G.)


Asst. Engg.
Municipal Corporation
Korba (C.G.)


Exe. Engg.
Municipal Corporation
Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT


PROVIDING, INSTALLATION, FIXING & COMMISSIONING OF PROPOSED "URJANAGARI KORBA" LED LOGO GLOW SIGN BOARD OF SIZE 15FT X 7.50FT AT VARIOUS PLACE IN MUNICIPAL CORPORATION, KORBA (C.G.)

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECTRICAL-01.06.2020]

S.N	REF	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	6.58	Supplying, installation, testing and commissioning of Acrylic LED light (a) Specification of Acrylic 3 mm thick x 3 " width x 4 " depth *(imbose) (b) Specification of LED modules :- Each Moduel should have 6 Nos LED of 1 watt	112.50	SQFT	2312.00	260100.00
2	6.59	Supply and installation of timer including relay and contactor set complete as required.	3.00	Each	3929.00	11787.00
3	6.60	Supplying and installation of SMPS (water proof) for power supply AC input 110/220 V 50/60HZ DC output 12V 30A	6.00	Each	5229.00	31374.00
4	6.61	Fabrication and installation of angle iron including angle size 50 mm x 5 mm thick with labour charges including materials as per specification	281.25	KG	66.00	18562.50
5	6.62	Providing and fixing aluminium composite panels in approved panel sizes, thickness and shape on aluminium frame work 62.1 4 mm thick	10.45	SQM	2404.00	25125.65
6	6.63	Designing providing and fixing aluminium frame work made of special aluminium section on building face with M.S. angle iron brackets fixed on RCC structure with S.S. hold fasteners, including providing and fixing two sided structural adhesive tape of appropriate grade on aluminium section for fixing aluminium/glass panel, sealing on perihphery of frame work by providing EPDM gasket, silicon weather sealant between aluminium frame and building structure. Design, Fixing & Grouting on RCC Structure	56.25	KG	545.00	30656.25
GROSS TOTAL						377605.40
TOTAL NUMBER OF SITE = 3						1132816.20
SAY RS:						1133000.00


Sub. Engg.
Municipal Corporation
Korba (C.G.)


Asst. Engg.
Municipal Corporation
Korba (C.G.)


Exe. Engg.
Municipal Corporation
Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


ABSTRACT


PROVIDING, INSTALLATION, FIXING & COMMISSIONING OF PROPOSED "URJANAGARI KORBA" LED LOGO GLOW SIGN BOARD OF SIZE 10FT X 5.0FT AT VARIOUS PLACE IN MUNICIPAL CORPORATION, KORBA (C.G.)

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ELECTRICAL-01.06.2020]

S.N	REF	ITEM DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	6.58	Supplying, installation, testing and commissioning of Acrylic LED light (a) Specification of Acrylic 3 mm thick x 3 " width x 4 " depth *(imbose) (b) Specification of LED modules :- Each Moduel should have 6 Nos LED of 1 watt	50.00	SQFT	2312.00	115600.00
2	6.59	Supply and installation of timer including relay and contactor set complete as required.	3.00	Each	3929.00	11787.00
3	6.60	Supplying and installation of SMPS (water proof) for power supply AC input 110/220 V 50/60HZ DC output 12V 30A	6.00	Each	5229.00	31374.00
4	6.61	Fabrication and installation of angle iron including angle size 50 mm x 5 mm thick with labour charges including materials as per specification	125.00	KG	66.00	8250.00
5	6.62	Providing and fixing aluminium composite panels in approved panel sizes, thickness and shape on aluminium frame work	4.65	SQM	2404.00	11166.96
	6.63	Designing providing and fixing aluminium frame work made of special aluminium section on building face with M.S. angle iron brackets fixed on RCC structure with S.S. hold fasteners, including providing and fixing two sided structural adhesive tape of appropriate grade on aluminium section for fixing aluminium/glass panel, sealing on perihphery of frame work by providing EPDM gasket, silicon weather sealant between aluminium frame and building structure.	25.00	KG	545.00	13625.00
		Design, Fixing & Grouting on RCC Structure				
					GROSS TOTAL	191802.96
					TOTAL NUMBER OF SITE = 3	575408.87
					SAY RS:	575400.00


Sub. Engg.
Municipal Corporation
Korba (C.G.)


Astt. Engg.
Municipal Corporation
Korba (C.G.)


Exe. Engg.
Municipal Corporation
Korba (C.G.)