

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क्र./22, 23, 24, 25, 32, 33, 34 एवं 35/निर्माण (कोसा.)/2019

कोरबा, दिनांक 18.07.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्रमांक 19 अंतर्गत दुर्गा पण्डाल का मरम्मत एवं विस्तार कार्य (मरम्मत एवं संधारण मद)	3,07,700/-	3077 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019
2	वार्ड क्रमांक 19 के विभिन्न सामुदायिक भवन गंव में पोतार्ड पेंटिंग कार्य।(मरम्मत एवं संधारण मद)	3,17,000 /-	3170 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019
3	वार्ड क्रमांक 18 पथरीपारा में नाली का मरम्मत एवं रख-रखाव कार्य। (मरम्मत एवं संधारण मद)	3,99,681 /-	4000 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019
4	वार्ड क्र. 18 पथरीपारा अंतर्गत सामुदायिक भवन का मरम्मत एवं रख-रखाव कार्य। (मरम्मत एवं संधारण मद)	4,00,000 /-	4000 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019
5	वार्ड क्र. 25 में आर.सी.सी. नाली एवं सी.सी. पेविंग का रख-रखाव एवं मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,99,445 /-	4000 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019
6	वार्ड क्र. 27 रामनगर में नाली एवं रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000 /-	4000 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019
7	वार्ड क्र. 27 गायत्री नगर में नाली एवं रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000 /-	4000 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019
8	वार्ड क्र. 28 राजेन्द्र प्रसाद नगर फेस-1 अंतर्गत विभिन्न स्थानों पर नाली का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000 /-	4000 /-	750 /-	02 माह	सक्षम श्रेणी	05.08.2019	07.08.2019	14.08.2019

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरगाव : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आइटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखित तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
3. निविदा प्रपत्र स्वीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेंगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
4. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
5. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमल की जानकारी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन का प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र धरोहर राशि निविदा प्रपत्र प्राप्त करने के अंतिम तिथि के 3.00 बजे सायं तक अधोहस्ताक्षरकर्ता के सगक्ष आवेदन प्रस्तुत करना अनिवार्य होगा।
6. निविदा प्रपत्र उन्हीं ठेकेदारों को दिया जायेगा, जिन्हें इस प्रकार के कार्य का अनुभव होगा।
7. पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहें तो उनके सगक्ष खोले जावेंगे।
8. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं मरम्मत एवं संधारण मद के कार्य को छोड़कर 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मस सिक्यूरिटी के रूप में रोकी जावेगी।
9. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
10. ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी गविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
11. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र देना अनिवार्य होगा।
12. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
13. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयवधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
14. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सरत निविदाओं पर विचार नहीं किया जावेगा।
15. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
16. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
17. निविदा प्रपत्र कय कर अथवा वेबसाईट से सीधे डाउनलोड कर निविदा प्रपत्र हेतु निर्धारित राशि की अतिरिक्त डिमांड ड्राफ्ट सहित अपनी भरी हुई निविदा नगर पालिक निगम में रजिस्टर्ड/स्वीड पोस्ट द्वारा अमानत राशि के साथ प्रस्तुत करें।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

कार्यपालन अभियन्ता

नगर पालिक निगम

कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


ABSTRACT


Name of Work :- Repair & Maintenance Work at Samudayik Bhawan Patharripara, Ward No. 18

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno.	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
1	16.37 Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50	241.60	Sqm	11.00	2657.60
2	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	1.55	Cum	768.00	1190.40
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and				
	In all types of soils	15.90	Cum	185.00	2941.50
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm	1.50	Cum	2659.00	3988.50
5	3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding				
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal	12.05	Cum	4163.00	50164.15
6	3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete				
	Thermo-Mechanically treated bars FE 415	950.00	Kg	54.50	51775.00
7	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels,				
	Foundations, footings, bases of columns plinth beam, curtain wall in any shape	13.32	Sqm	139.00	1851.48
	Columns, Pillars, Piers and likes- rectangular or square in shape	16.00	Sqm	297.00	4752.00
	Beams, lintels, cantilevers & walls	13.80	Sqm	202.00	2787.60
	Weather shade, chhajja, Cornices and mouldings	23.16	Sqm	294.00	6809.04
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves	17.85	Sqm	235.00	4194.75
8	7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in				
	Cement Mortar 1:6 (1 cement : 6 coarse sand)	6.45	Cum	3263.00	21046.35
9	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	5.10	Cum	121.00	617.10
10	Providing and making 6mm thick cement plaster of mix:				
	In Cement mortar 1:4 (1 cement : 4 fine sand)	29.75	Sqm	87.00	2588.25
11	11.2 Providing and making 12mm thick cement plaster of mix:				
	In Cement Mortar 1:5 (1 cement : 5 fine sand)	25.50	Sqm	96.50	2460.75
12	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix				
	In Cement Mortar 1:5 (1 cement : 5 fine sand)	275.60	Sqm	113.00	31142.80
13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	330.85	Sqm	94.50	31265.33
14	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with				
	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	275.60	Sqm	56.00	15433.60

	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
	Painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade				
	On new work (two or more coats)	346.85	Sqm	52.50	18209.63
16	14.22 Painting on new work (two or more coats) to give an even shade with				
	Satin synthetic enamel paint	17.42	Sqm	55.00	958.32
17	14.23 Painting on old work (one or more coats) to give an even shade with:				
	Satin synthetic enamel paint	45.67	Sqm	52.50	2397.78
18	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	161.46	Sqm	22.50	3632.85
19	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed				
	Size 300x300mm	23.76	Sqm	22.50	534.60
20	9.13 Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including	200.00	Kg	75.00	15000.00
21	12.65 Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including				
	Pigment Coloured (rubber mould) precast interlock concrete blocks	161.46	Sqm	632.00	102042.72
22	4.13 Grading roof for water proofing treatment with:				
	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	5.04	Cum	3817.00	19237.68
23	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	10.00	Kg	43.50	435.00
As per SOR Total Estimate Amount Rs.					400114.77
Say amount Rs.					400000.00


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)