



कार्यालय नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. / 133,134,136 / सर्वमंगल जोन / 2019-20 /

कोरबा दिनांक 04.02.2020

निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग (भवन/रोड़), रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरो पर तथा शेड्यूल अनुसार आईटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेब साईड से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है।

- 01 निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 24.02.2020 सायंकाल 3:00 बजे तक
- 02 निविदा खुलने की अंतिम तिथि - 24.02.2020 सायंकाल 4:00 बजे तक

क.	कार्य का नाम	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क्र.54 सर्वमंगला नगर एस.जी.पी. कॉलोनी बरमपुर में मंच के पास रिटर्निंग वॉल निर्माण कार्य। (प्रमारी मंत्री मद)	5,00,000/-	5,000/-	750/-	Form-A	04 माह	सक्षम श्रेणी	24-02-2020
2	वार्ड क्र.61 आदर्श नगर कुसमुड़ा में सामुदायिक भवन निर्माण कार्य। (विधायक मद)	10,00,000/-	7,500/-	750/-	Form-A	05 माह	सक्षम श्रेणी	24-02-2020
3	वार्ड क्र.58 में ईमलीछापर सामुदायिक भवन मदरसा के पास सीमेंट कांक्रीट रोड़ निर्माण एवं लक्ष्मण नाला घाट में कांक्रीटिंग कार्य। (पार्षद मद 2019-20)	7,00,000/-	5,250/-	750/-	Form-A	04 माह	सक्षम श्रेणी	24-02-2020

निविदा की शर्त :-


- निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक प्रतिशत दरों पर दिया जावें, सी.एस.आर. के अंतर्गत के आईटमो पर पृथक से आईटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथो - हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमो यथा कोरियर, सर्विस,साधारण डाक इंतयादि से प्राप्त अथवा समयावधि के पश्चात प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा प्रपत्र आयुक्त नगर पालिक निगम, साकेत भवन आई.टी.आई.चौक कोरबा, जिला - कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम,कोरबा के वेबसाईट WWW.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form- A/B/ABC (जारी दिनांक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि- लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा :-
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र,आयकर चुकता प्रमाण पत्र,निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर.जो कि आयुक्त नगर पालिक निगम,कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा निविदा प्रपत्र होगा।
(स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम,(साड़ा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साड़ा) के हित के विरुद्ध कार्य किया गया हो उनहे निविदा भरने की प्रात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनर शीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर प्रमाण पत्र/पेन नम्बर जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र,कर्मचारी भविष्य निधि संगठन,कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एन.आई.टी.) हस्ताक्षर युक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र.04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मोंक,निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
- निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
- निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वभेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
- निर्धारित प्रारूप में निविदा प्रपत्र,निविदा प्रपत्र शुल्क,अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाये जाने पर ही निविदा दर संबंधित लिफाफा खोला जावेगा,अन्यथा निविदा निरस्त कर दी जावेगी।
- ठेकेदार को अपनी दरें संबद्ध एवं अंको में लिखना अनिवार्य होगा।
- शासन के विभिन्न विभागों जैसे :- खनिज विभाग,श्रम विभाग,समाज कल्याण विभाग,इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों /आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
- ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्राक्धान के अंतर्गत कार्यवाही की जावेगी।

कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई. सी.द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी संपूर्ण जवाबदारी ठेकेदार की होगी।

5. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जब की निविदा की दरों में काफी कमी हो जैसे निविदा दाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदा दाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर.आफिस टाईम डिपॉजिट अथवा एन.एस.सी.जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम से देय होगा,जो माग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष के लिए परफार्मेंस सिक्यूरिटी के रूप में तथा परफार्मेंस सिक्यूरिटी राशि 03 वर्ष के लिए रोकी जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 01 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथ पत्र कंडिया क्र.- 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईंट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तातरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम,कोरबा के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर अगामी तिथि को निविदा संबंधित कार्यवाही मानी जावेगी।

नोट :-

01. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगर जमा रसीद पृथक से लिफाफे में स्वीकार किये जायेगे जो आयुक्त नगर पालिक निगम,कोरबा के नाम से देय हो।
02. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा(छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (U.G.)

ABSTRACT

: CONSTRUCTION OF COMMUNITY CENTER AT ADRAS NAGAR KUSMUNDA UNDER MLA FUND WARD NO 61

SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SOR N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	42.27	185.00	7,819.95
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	26.82	371.00	9,950.22
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	15.39	2970.00	45,708.30
4	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	52.44	139.00	7,289.16
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	39.6	297.00	11,761.20
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	127.66	235.00	30,000.10
	1.8	Beams, lintels, cantilevers & walls	sqm	35.34	202.00	7,138.68
5	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	33.54	4163.00	139,627.02
6	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	2.2	Thermo-Mechanically treated bars FE 500D	kg	3354	54.50	182,793.00
7	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	38.32	3263.00	125,038.16
8	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	28.87	121.00	3,493.27
9	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	150.00	68.00	10,200.00
10	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete	kg	300.00	75.00	22,500.00


	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	including applying a priming coat of red oxide zinc chromate primer.				
	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	200.00	67.50	13,500.00
12	11.1 Providing and making 6mm thick cement plaster of mix:				
	1.2 In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	112.52	87.00	9,789.24
13	11.2 Providing and making 12mm thick cement plaster of mix:				
	2.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	248.15	91.50	22,705.72
14	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	245.7	107.00	26,289.90
15	12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.2 Size above 200x300mm	sqm	21.6	646.00	13,953.60
16	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	9.1 Size 300x300mm	sqm	4.68	692.00	3,238.56
17	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	586.37	94.50	55,411.96
18	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade.				
	4.1 On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	310.00	41.00	12,710.00
19	14.9 Distempering with acrylic washable distemper to give an even shade.				
	9.1 On new work (Two or more coats)	sqm	276.35	38.00	10,501.30
20	14.22 Painting on new work (two or more coats) to give an even shade with:				
	2.2 Premium synthetic enamel paint	sqm	58.08	47.00	2,729.76
21	1.17 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	42.27	65.00	2,747.55
22	9.11 Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.	sqm	7.56	3330.00	25,174.80
23	18.1 Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	1.3 White Orissa pattern W.C. pan of size 580x440 mm	each	1.00	2899.00	2,899.00
24	18.17 Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				


	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	White Size 550x450 mm	each	1.00	1430.00	1,430.00
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & cross threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. INTERNAL WORK - EXPOSED ON WALL				
4.1	15 mm nominal outer dia .Pipes.	metre	15.00	110.00	1,650.00
4.3	25 mm nominal outer dia .Pipes.	metre	25.00	199.00	4,975.00
4.4	32 mm nominal outer dia .Pipes.	metre	17.00	271.00	4,607.00
26	19.13 Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:				
3.1	Bib cock (250 grams)	each	4.00	185.00	740.00
3.3	Stop cock (350 grams)	each	4.00	237.00	948.00
27	19.42 Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	NO	1000.00	7.25	7,250.00
28	12.12 Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	sqm	90.58	963.00	87,228.54
29	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	3.81	4073.00	15,518.13

As per Estimate Amount Rs. 929,317.12
ADD ENTENAL ELECTRIFICITION Add Above 7.5 % 69,698.78
Grand Total Rs. 999,015.90
%
Grand Total Rs. 999,015.90
Say Rs. 999,015.90

Nine Lacs Ninety Nine Thousand One Hundred

999100 = 0


Sub Engineer
Nagar Palik Nigam
Korba (C.G.)


Asst. Engineer
Nagar Palik Nigam
Korba (C.G.)


E.E. Engineer
Nagar Palik Nigam
Korba (C.G.)