

# कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

359/  
फा.क./ निर्माण/2018

सिस्टम टेंडर नं. 52681  
पंचम ई-निविदा आमंत्रण सूचना

कोरबा दिनांक 02.07.2019

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत रक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती हैं :-

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 25 विश्वकर्मा मंदिर कुआ भट्टा के समीप सामुदायिक भवन निर्माण कार्य	5.00	5000/-	03 माह	वर्ग डी एवं प्रवर श्रेणी	18.07.2019 से .....


शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड ) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्रि नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)

**Date-Time Detail(s)**

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		02.07.19	18.00	02.07.19	18.00	Release Tender
2		Bid Submission	02.07.19	18.00	17.07.19	17.30	
3	Tender Open		18.07.19	10.30	--	--	

  
**EXECUTIVE ENGINEER**  
**KORBA (CG)**  
 For, Commissioner Korba (C.G.)

(15)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)  
ABSTRACT


Name of Work :- Const. of Community Building Near Vishwakarma Mandir Kuan Bhattha Ward No.- 25  
As per Sor :- Schedule of Rates Public Works Department [ PWD BUILDING 01-01-2015]

	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing In all types of soil	41.25	Cum	185.00	7631.25
2	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift	40.40	Cum	65.00	2626.00
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	2.25	Cum	371.00	834.75
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal	9.15	cum	2659.00	24329.85
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, Foundations, footings, base of columns and plinth beam in any shape and size. Columns, Pillars, Piers and likes- rectangular or square in shape Beams, lintels, cantilevers & walls Suspended floors, roofs, access platform, balconies (plain surfaces) and Weather shade, chhajja, Cornices and mouldings	32.00	sqm	139.00	4448.00
		34.00	sqm	297.00	10098.00
		33.60	sqm	202.00	6787.20
		61.75	sqm	235.00	14511.25
		5.46	sqm	294.00	1605.24
6	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal	23.61	cum	4163.00	98288.43
7	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	13.28	cum	97.50	1294.80
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	2370.00	kg	54.50	129165.00
9	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	22.50	cum	3263.00	73417.50
10	Extra for brick work in superstructure: Above plinth and upto floor five level.	19.80	cum	121.00	2395.80
11	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including	250.00	Kg	75.00	18750.00
12	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including	220.00	Kg	67.50	14850.00
13	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	77.47	Sqm	87.00	6739.89
14	Providing and making 12mm thick cement plaster of mix: Cement Mortar 1:6 (1 cement : 6 fine sand)	132.44	sqm	91.50	12118.26

15

ITEM DESCRIPTION	Qty	Unit	Rate	Amount
5mm thick cement plaster on the rough side of single or half brick wall of mix:				
1:6 cement Mortar (1 cement : 6 fine sand)	110.96	sqm	107.00	11872.72
Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	301.00	sqm	94.50	28444.50
17 Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.				
50 mm thick	55.51	Cum	254.00	14099.54
18 Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.				
On new work (two or more coats)	320.87	Cum	44.50	14278.72
19 Painting on new work (two or more coats) to give an even shade with:				
Satin synthetic enamel paint	25.08	Sqm	55.00	1379.40
<b>Total amount as per SOR Rs.</b>				<b>499966.10</b>
<b>Say amount Rs.</b>				<b>500000.00</b>

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Asst. Engineer  
 Municipal Corporation  
 Korba (C.G.)