

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2019

सिस्टम टेन्डर नं. 53212
ई-निविदा आमंत्रण सूचना


कोरबा, दिनांक 16/07/2019

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015ए (सड़क) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरो पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

| क्र. | कार्य का नाम | प्राक्कलन राशि में | धरोहर राशि रु में | कार्यावधि | ठेकेदार का वर्ग | निविदा खुलने की अंतिम तिथि |
|------|---|--------------------|-------------------|-----------|--------------------------|----------------------------|
| 1 | वार्ड क 09 में मिलाई खुर्द क. 01 में मानीकपुर कलवर्ट तक सीमेंट कांकीट सड़क एवं आर.सी. सी. कलवर्ट का निर्माण कार्य | 38.31 | 288000/- | 06 माह | वर्ग डी एवं प्रवर श्रेणी | 06.08.2019 से |


शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जायेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में पैन शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

| Seq. No. | Nagar Nigam Stage | Contractor Stage | Start | | Expiry | | Remarks |
|-------------|-------------------|------------------|----------|-------|----------|-------|----------------|
| | | | Date | Time | Date | Time | |
| 1 | Release Tender | | 16.07.19 | 20.30 | 16.07.19 | 12.30 | Release Tender |
| 2 | | Bid Submission | 16.07.19 | 12.30 | 05.08.19 | 17.30 | |
| 3 | Tender Open | | 06.08.19 | 10.30 | — | — | |


EXECUTIVE ENGINEER
KORBA (CG)
 For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE (PART A)

Construction of Cement Concrete Road from Bhalai Khurd Kramank 1 to Manikpur Culvert at Ward No. 9

Schedule of rates public works department [PWD ROAD - 01-01-2015]

| S. N. | SOR Ref. | DESCRIPTION | NO | L | B | D/H | QTY | UNIT | RATE | AMOUNT |
|---------|----------|---|----|--------|------|--------|--------|------|---------|------------|
| 1 | 2.6 | Dismantling of cement concrete pavement i/c breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead upto 1000 meters, stacking serviceable and unserviceable materials separately and as per relevant clauses of section-200. | | | | | | | | |
| | | | 1 | 980.00 | 2.20 | 0.08 | 172.48 | | | |
| | | | | | | Total= | 172.48 | Cum | 1104.00 | 190417.92 |
| 2 | 3.2 | Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300. | | | | | | | | |
| | | | 1 | 980.00 | 1.20 | 0.20 | 235.20 | | | |
| | | | | | | Total= | 235.20 | Cum | 95.00 | 22344.00 |
| 3 | 6.6 | Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) | | | | | | | | |
| | 1 | P.C.C. M-10 | | | | | | | | |
| | | | 1 | 440.00 | 3.40 | 0.10 | 149.60 | | | |
| | | | | | | Total= | 149.60 | Cum | 2789.00 | 417234.40 |
| 4 | 6.7 | Providing and laying unreinforced cement concrete without dowel bar including form work and expansion, contraction and longitudinal joint as per design or as per IRC- 62-2014 over a prepared base as per approved mix design and finishing to lines and grade as per Drawings for pavement thickness less than 200mm in low volume Roads. | | | | | | | | |
| | (i) | Plain Cement Concrete Grade M-30 and minimum Cement Content @375 kg/cum | | | | | | | | |
| | | | 1 | 980.00 | 3.40 | 0.20 | 666.40 | | | |
| | | | | | | Total= | 666.40 | Cum | 4391.00 | 2926162.40 |
| TOTAL = | | | | | | | | | | 3556158.72 |

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

Sub Engineer
Municipal Corporation
Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


DETAILED ESTIMATE (PART B)


Construction of R.C.C. Culvert Between Road Bhalai Khurd Kramank 1 to Manikpur
Culvert at Ward No. 9

Schedule of rates public works department [PWD BUILDING-01-01-2015]

| S. N. | SOR Ref. | DESCRIPTION | NO | L | B | D/H | QTY | UNIT | RATE | AMOUNT |
|-------|----------|--|----|-------|------|--------|-------|------|---------|----------|
| 1 | 16.4 | Demolishing cement concrete including disposal of material within 50 metre lead. | | | | | | | | |
| | 2 | 1:3:6 or richer mix | | | | | | | | |
| | | | 2 | 2.50 | 2.50 | 0.30 | 3.75 | | | |
| | | | | | | Total= | 3.75 | Cum | 549.00 | 2058.75 |
| 2 | 1.1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. | | | | | | | | |
| | 1 | In all types of soil | | | | | | | | |
| | | | 2 | 6.00 | 2.20 | 1.50 | 39.60 | | | |
| | | | | | | Total= | 39.60 | Cum | 185.00 | 7326.00 |
| 3 | 2.1 | Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: | | | | | | | | |
| | 1 | Foundations, footings, base of columns and plinth beam in any shape and size. | | | | | | | | |
| | | | 8 | 6.00 | | 0.40 | 19.20 | | | |
| | | | 8 | 2.20 | | 0.40 | 7.04 | | | |
| | | | 2 | 6.00 | | 0.25 | 3.00 | | | |
| | | | 8 | 6.00 | | 1.00 | 48.00 | | | |
| | | | | | | Total= | 77.24 | Sqm | 139.00 | 10736.36 |
| | 7 | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ) | | | | | | | | |
| | | | 2 | 6.00 | 1.00 | | 12.00 | | | |
| | | | 2 | 15.60 | | 0.25 | 7.80 | | | |
| | | | | | | Total= | 19.80 | Sqm | 235.00 | 4653.00 |
| 4 | 3.1 | Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. | | | | | | | | |
| | 3 | 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size). | | | | | | | | |
| | | | 2 | 6.00 | 2.20 | 0.10 | 2.64 | | | |
| | | | | | | Total= | 2.64 | Cum | 2970.00 | 7840.80 |
| 5 | 3.2 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. | | | | | | | | |
| | 1 | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | | | | | | | | |
| | | | 2 | 6.00 | 2.20 | 0.30 | 7.92 | | | |
| | | | 4 | 6.00 | 0.40 | 1.00 | 9.60 | | | |
| | | | 2 | 6.00 | 1.80 | 0.25 | 5.40 | | | |
| | | | 4 | 6.00 | 1.20 | 0.25 | 7.20 | | | |
| | | | | | | Total= | 30.12 | Cum | 1100.00 | 40500.00 |

| | | | | | | | | | | |
|---------|------|--|--|--|--|--------|---------|-----|-------|-----------|
| 6 | 3.12 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of welding wire in foundation and plinth all complete: | | | | | | | | |
| | 1 | Thermo-Mechanically treated bars FE 415 | | | | Total= | 2096.00 | Kg | 54.50 | 114232.00 |
| 7 | 1.17 | Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M. | | | | | 39.60 | Cum | 65.00 | 2574.00 |
| TOTAL = | | | | | | | | | | 274810.47 |


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)