



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

जल प्रदाय

फा.क्र./1433/जल प्रदाय/2025/

कोरबा, दिनांक 24.03.2025

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु CG PHED SOR Amendment 07/2022-23 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 16.04.2025 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 16.04.2025 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	छ.ग ईस्ट वेस्ट रेल कॉरिडोर परियोजना गोवरा रोड से पेण्डारोड अंतर्गत रेल ब्रिज No. 04 Near Gurudwara at Guddeva पाईप लाईन शिफ्टिंग कार्य। (प्रथम निविदा) (डिपॉजिट वर्क 2024-25)	7,72,195/-	5,800 /-	750/-	Form-A	02 माह	सक्षम श्रेणी	16.04.2025

निविदा की शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
 - प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी, निविदाओं में निविदाकार को फिजिकल दस्तावेज के साथ निविदा सूचना जारी होने के पश्चात् दिनांक का शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्य की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
- निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकरी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाणपत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के अनुरूप लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।

क्रमशः.....02

8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लेवें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. ठेकेदार द्वारा संपादित किये गये कार्य के देयको का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जायेगा।
10. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गये प्रावधानों का पालन करना अनिवार्य होगा।
11. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
12. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर का लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
13. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
14. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
15. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
16. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
17. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
18. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा निधि मद में राशि रनिंग देयकों से 01 वर्ष की अविध हेतु साथ ही 05 प्रतिशत पृथक से 03 वर्ष की गारन्टी के लिए परफार्मेंस सिक्क्यूरिटी के रूप में रोकी जावेगी।
19. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
20. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथ पत्र राशि रु. 100/- नॉन ज्यूडिशियल स्टॉम्प पेपर पर कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
21. ईंट से संबंधित निर्माण कार्यों में प्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
22. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
23. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
24. निविदा प्रपत्र **Form-A** के क्लॉज नम्बर-13 अनुसार एस्केलेशन देय नहीं होगा।
25. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
26. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हों।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Municipal Corporation Korba

Name of work:- Shifting of pipe line due to railway track near Gurudwara at Guddeva


Estimate based on CG PHED SOR 2020 & Amendment 07/2022-23

ABSTRACT

Sr. No.	Item Description	Qty	Unit	Rate	Amount
1	Earth work in excavation for pipe trench in ordinary soil areas including dressing, watering, ramming and disposal of excavated earth lead up to 50m and lift up to 1.5m, disposal earth to be Qty of Soft Soil @ 70% of total Quantity (CG PHED SOR Amendment 07/2022-23, It.No. 18.15,	162.75	Cum	201.00	32712.75
2	Earth work in excavation for pipe trench in Hard soil areas including dressing, watering, ramming and disposal of excavated earth lead up to 50m and lift up to 1.5m, disposal earth to be levelled, neatly dressed Hard Soil Qty of Hard Soil @ 20% of total Quantity (CG PHED SOR Amendment 07/2022-23, It.No. 18.19.1,	46.50	Cum	266.00	12369.00
3	Earth work in excavation for pipe trench in all kinds of rocks in areas including dressing, stacking of useful material and disposal of unservice able material up to lead up to 50m and lift up to Soft rock with or without blasting or bituminous pavement / cement concrete road. Qty of rocks @ 10% of total Quantity (CG PHED SOR Amendment 07/2022-23, It.No. 18.19.1,	23.25	Cum	465.00	10811.25
4	Pumping out water caused by springs, tides or river seepage, broken water mains or drains or well or the like. (CG PHED SOR Amendment 07/2022-23, It.No.18.21,	100.00	KL	71	7100.00
5	Providing, laying & jointing including testing following socket & spigot centrifugally cast (spun) Ductile iron pressure pipes with inside cement lining (class K-7) conforming to IS 8329/2000 with suitable Rubber Gasket (Push on) joint as per IS : 300 mm dia. DI K-7 150 mm dia. DI K-7 (CG PHED SOR Amendment 07/2022-23, It.No.4.1, Pg.No.02)	50.00 50.00	Mtr Mtr	3774.00 1804.00	188700.00 90200.00
6	Supply & Filling moorum/river sand for pipe bedding or over the pipe (including supply) (CG PHED SOR Amendment 07/2022-23, It.No.18.24,	6.51	Cum	864.00	5627.07
7	Filling available excavated earth in trenches, lead up to 50m and lift up to 1.5m in all kind of soil excluding Watering and (CG PHED SOR Amendment 07/2022-23, It.No.18.23,	221.57	Cum	62.00	13737.44
8	Providing and Laying including testing ductile iron PN 16 type flanged sockets conforming to IS: 9523/2000 having dimension as per table 23 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS:9523/2000. 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.4.7, Pg.No.04)	1.00 1.00	Each Each	5298.00 2005.00	5298.00 2005.00


No.	Item Description	Qty	Unit	Rate	Amount
9	Providing and Laying including testing ductile PN 16 type iron flanged spigot conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement mortar lining with finishing as per clause 13 of IS: 9523/2000. 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.4.9, Pg.No.05)	1.00	Each	6015.00	6015.00
		1.00	Each	2291.00	2291.00
10	Providing and Laying including testing Ductile iron Mechanical joint collar with follower glands conforming to IS: 9523/2000 having dimension as per table 24 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen and 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.4.11, Pg.No.06)	2.00	Each	8901.00	17802.00
		2.00	Each	3896.00	7792.00
11	Providing and Laying including testing Ductile Iron Double Socket 90° Bends conforming to IS: 9523/2000 having dimension as per table 15 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.4.13, Pg.No.07)	1.00	Each	8439.00	8439.00
		1.00	Each	2595.00	2595.00
12	Providing and Laying including testing Ductile Iron Double Socket 45° Bends conforming to IS: 9523/2000 having dimension as per table 16 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal cement 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.4.15, Pg.No.07-)	1.00	Each	6361.00	6361.00
		1.00	Each	2078.00	2078.00
13	Providing and Laying including testing Ductile Iron Double Socket 22.5° Bends conforming to IS: 9523/2000 having dimension as per table 17 of IS: 9523/2000 in the following nominal diameter/sizes with external bitumen coating and internal 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.4.17, Pg.No.08)	1.00	Each	5322.00	5322.00
		1.00	Each	1817.00	1817.00
14	Providing and Laying including testing Ductile Iron Double Socket 11.25° bends conforming to IS:9523/2000 having dimension as per table 18 of IS:9523/2000 in the following nominal diameter/ sizes with external bitumen coating and 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.4.19, Pg.No.09)	1.00	Each	4804.00	4804.00
		1.00	Each	1687.00	1687.00
15	Providing and laying mechanically mixed cement concrete with crushed stone aggregate excluding centering and shuttering (with 40mm nominal size graded stone aggregate) For Road restoration (M-10)	2.40	Cum	5029.00	12069.60

No.	Item Description	Qty	Unit	Rate	Amount
	(CG PHED SOR Amendment 07/2022-23, It.No.18.40.1.3,				
16	Providing & laying mechanically mixed cement concrete 20mm nominal size graded crushed stone excluding cost of centering & shuttering. For Road restoration (M-20) (CG PHED SOR Amendment 07/2022-23, It.No.18.41.1.3,	4.80	Cum	6545.00	31416.00
17	Providing & laying mechanically mixed R.C.C. excluding centering & shuttering and reinforcement in foundation/plinth For thrust block & pipe encasing (CG PHED SOR Amendment 07/2022-23, It.No.18.42.1,	4.88	Cum	6025.00	29377.98
18	Providing and placing in position cold twisted steel and hot rolled deformed steel reinforcement for R.C.C. work i/c cutting, bending, binding etc. complete i/c cost of binding wire and qty as per item no.18 (80 kg/cum) (CG PHED SOR Amendment 07/2022-23, It.No.18.44,	540.00	Kg	70.00	37800.00
19	Labour only for cutting following Ductile Iron pipes of any type 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.19.4, Pg.No.60)	4.00 4.00	Per Cut Per Cut	269.00 135.00	1076.00 540.00
20	Chamfering of CI/DI pipes of all type sand classes to make suitable for tyton joints. 300 mm dia. 150 mm dia. (CG PHED SOR Amendment 07/2022-23, It.No.19.6, Pg.No.61)	8.00 8.00	Each Each	1681.00 1079.00	13448.00 8632.00
21	Manufacturing, Supplying at site & laying, jointing of following M.S. pipes as per IS specifications, duly testing for usage in Drinking water inclusive of all materials, inspection charges, transit insurance, loading/unloading, FOR site and stacking etc. complete as per direction of Engineer-in-Charge. (Excluding 500 mm dia. (I.D.) M.S. Pipe 8 mm Thk 300 mm dia. (I.D.) M.S. Pipe 6 mm Thk (CG PHED SOR 2020, Item No 10.1.9(iii) & 10.1.5(ii), Page no-	20.00 20.00	Mtr. Mtr.	6712.00 3022.00	134240.00 60440.00
22	Providing & applying 400 micron epoxy coating as per relevant IS specification on out side face of pipe including testing. Outside surface (CG PHED SOR 2020, Item No 10.10, Page no-147)	52.00	Sqm	146.00	7591.77
				Total Amount (In Rs.) =	772194.85
				Previlling Market Rate (25%) =	
				(A) Total (In Rs.) =	
				Add 3% Contingency =	
				Add 18% of GST on (A) =	
				Grtrand Total (In Rs.) =	



Sub Engineer
Municipal Corporation
Korba (C.G.)

Say Rs.



Assistant Engineer
Municipal Corporation
Korba (C.G.)