कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र. / 1287 / ज.प्र.स. / 2023 /

SYSTEM TENDER NO: **119007**

कोरबा, दिनांक 02.01.2023

द्वितीय निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारो से निम्नलिखित कार्य हेतु "पार्ट ए," प्रमुख अभियंता, लोक स्वास्थ्य यांत्रिक विभाग रायपुर PHED- SOR Amendment 7-2022-23 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम, अधिक या समान प्रतिशत दरों पर एवं पार्ट "बी" हेतु शेड्यूल अनुसार आईटम दर पर ई–प्रोक्युरमेंट (E-Tendring) के माध्यम से निविदा आमंत्रित की जाती है।

क्र	कार्य का नाम	प्राक्कलन राशि	अमानत राशि	ठेकेदार का वर्ग	कार्यावधि	निविदा खुलने की तिथि
1	रेलकारिडोर उरगा–कुसमुण्डा (गेवरा–पेंड्रा) में सर्वमेंगला मंदिर के पीछे पाईप लाईन कासिंग का कार्य।	33.23 लाख	25,000 / –	वर्ग डी एवं प्रवर श्रेणी	02 माह	25.01. 2023 से ......

शर्ते :–

1. निविदा दरें प्रचलित सी.एस.आर. से कम / अधिक / समान प्रतिशत दरों पर दिया जावें। सी.एस.आर. के अंतर्गत आईटमों पर पृथक से आइटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा प्रपत्र की ई–प्रोक्युरमेंट (E-Tendring) के माध्यम से ही स्वीकार किये जाएंगे।
3. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
4. निविदा प्राप्त करने के इच्छुक ठेकेदारों को आवेदन के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि ऑनरशीप यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों का अनुभव प्रमाण पत्र, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र / पेन नं. एवं जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑन लाईन जमा करना अनिवार्य होगा। प्रतिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन का कोड एवं धरोहर राशि स्केन कॉपी आन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
5. उक्त प्रकृति के कार्य किये गये ठेकेदार ही निविदा में भाग लिया जा सकेगा।
6. ईंट से संबंधित निर्माण कार्य में फ्लाई एशब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
7. निविदा प्रपत्र अहस्तांतरणीय होगी एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा ।
8. किसी भी तरह की विवाद की स्थिति में अंतिम निर्णय लेने का अधिकार सक्षम अधिकारी के पास सुरक्षित रहेगा।
9. आवेदन के साथ 10.00 लाख या उससे अधिक लागत के निर्माण कार्यो की निविदा में भाग लेने वाले ठेकेदारों को छ.ग.भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तो का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 01 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
10. उपरोक्त कार्य में उपयोग किया जाने वाला पाईप एवं पाईप फिटिंग आई.एस.आई. मार्क द्वारा प्रमाणित होना चाहिए।
11. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में शपथ पत्र देना अनिवार्य होगा।
12. निविदा दरे एस.ओ.आर. से कम होने पर एस.ओ.आर. एव निविदा दर की अंतर की राशि ठेकेदार से अमानत राशि के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर. / पोस्ट आफिस टाईम डिपाजिट / एन.एस.सी. जो कि आयुक्त नगर पालिक के नाम से देय होगा,तत्काल जमा कराई जावेगीं। उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम कोरबा की वेब साइट www.Korbamunicipal.in पर भी यह टेन्डर उपलब्ध है।
13. अन्य सूचनाएं नगर पालिक निगम साकेत भवन रामपुर कोरबा कार्यालय से प्राप्त की जा सकती है।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि – प्रोग्रामर, संचालनालय, नगरीय प्रशासन विकास विभाग रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		02.01.2023	16.30	02.01.2023	16.30	Release Tender
2		Bid Submission	02.01.2023	16.30	24.01.2023	17.30	
3	Tender Open		25.01.2023	10.30	--	--	

EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

KORBA MUNICIPAL CORPORATION , KORBA - CHATTISGARH.

Name of Work :- Railway crossing of 500 mm Dia. MS Casing Pipe & 200mm Dia. MS Carring pipe BELOW Railway track for at ward No - 54 behind Sawamangala Temple.

ABSTRACT SHEET

RS. 4153900 (GROSS)

Particulars of Item	Quantity	Rate	Unit	Amount	Remarks
Item No. 1: Excavation for foundation / pipe trenches in all type of strata including removing the excavated material up to a distance of 50 m and lift as below, stacking and spreading as directed, normal dewatering, preparing the bed for foundation and exluding back filling, etc complete.					
(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No-18.15; Page no-51) **Lift 0 to 1.50 m**	45.00	201	M3	9045.00	
Item No. 2: Excavation for foundation / pipe trenches in all type of strata including removing the excavated material up to a distance of 50 m and lift as below, stacking and spreading as directed, normal dewatering, preparing the bed for foundation and exluding back filling, etc complete.					
(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No 18.15 & 18.19.1; Page no-51 & 52) **Lift 1.50 m TO 3.0 M**	45.00	268	M3	12060.00	
Item No. 3: Excavation for foundation / pipe trenches in all type of strata including removing the excavated material up to a distance of 50 m and lift as below, stacking and spreading as directed, normal dewatering, preparing the bed for foundation and exluding back filling, etc complete.					
(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No 18.15 & 18.19.1; Page no-51 & 52) **Lift 3.0 m TO 4.50 M**	39.00	335	M3	13065	
Item No. 4: Pumping out water caused by springs, tides or river seepage, broken water mains or drains or well or the like.	1500.00	71	KL	106500	
(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No 18.21; Page no- 52)					
Item No. 5 :- Manufacturing, Supplying at site & laying, jointing of following M.S. pipes as per IS specifications, duly testing for usage in Drinking water inclusive of all materials, inspection charges, transit insurance, loading/unloading, FOR site and stacking etc. complete as per direction of Engineer-in-Charge. (Excluding protective coating)					
(Basic rate as per CG PHED SOR 2020 / Item No 10.1.9; Page no-140)					
FOR CASING PIPES					
a) 500 mm Dia MS Pipes / 12 mm Thickness	60.00	10189	Rmt.	611340.00	
b) 200 mm Dia MS Pipes / 8 mm Thickness	90.00	2748	Rmt.	247320.00	

Particulars of Item	Quantity	Rate	Unit	Amount	Remarks
Item No. 6 :- Fabrication of M.S. pipes & specials fromsteel plates as per relevant IS specifications inclusive of cost of all materials, for any thickness as per design, inspection charges, testing, transit insurance, loading/ unloading, FOR site and stacking etc. complete as per direction of the Engineer in charge. fabricating of pipes and specials fromsteel plates.					
(Basic rate as per CG PHED SOR 2020 / Item No 10.2; Page no-143)					
FOR CARRYING PIPES (length = 40m)					
a) 200 mm Dia MS Pipes / 8 mm Thickness	1640.64	74	Kg.	121407.17	
ITEM NO. 7 :- Providing and laying PCC In Grade M-150 for bedding / levelling course ---- etc complete. (As per Rate analysis attached) *(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No 18.40.1.4; Page no-53)*	4.50	5910.00	Cum	26595.00	
ITEM NO. 8 :- Providing , laying and casting in Situ RCC in Grade M-250 for Thrust wall with metal of type Granite / gniss etc complete. *(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No 18.42; Page no-54)*	2.41	6025.00	Cum	14505.19	
ITEM NO. 9 :- Providing , cutting , Bending and placing in position Steel reinforcement for RCC Work. Etc complete. *(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No 18.44; Page no-54)*	0.30	70000.00	MT	21065.63	
Item No. 10 :- Pushing of M.S. Pipe of following Dia. For road crossing and Railway crossing by Push Through method in all types of Strata by using hydraullic jack and drilling machine of required diameter , below 3.0 m depth including lowering , laying , jointing of M.S. casing pipe including cost of labour , fuel and material , required welding machinery , tripod , chain pulley block , crane , blower etc. tracsportation and dewatering etc. complete as directed by Engineer - In- Charge but excluding cost of M.S. Pipes.					
(Basic rate as per MJP CSR 2021-22/ Item No-14b; Page no-63)					
For Casing pipe of 500 mm Dia. MS Pipes					
For 500 mm Dia. M.S. Casing Pipe.	60.00	31384	Rmt	1883040.00	
Item No. 11 :- Providing and applying external and internal coating for steel structure with elastomeric (450% elongation o, thermoplastic, fire retardant, coatin, skin tensile strength 18 to 21 kg. sqcm, micron DFT or self bonding grade with steel 50 micron DFT of liner coat and 50 micron DFT of top coat. *(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No 20.20; Page no-75)*	312.19	798	Sqm.	249126.92	

Particulars of Item	Quantity	Rate	Unit	Amount	Remarks
Item No. 12 :- Refilling the trenches with available excavated stuff with soft material first over pipeline and then hard material in 15 cms layers with all leads and lifts including consolidation, surcharging, etc. complete. (BASIC RATE AS PER PHED SOR 2020, ITEM NO.18.23 PAGE NO. 227) *(Basic rate as per CG PHED SOR Amendment No-07/2022; Item No-18.23; Page no-52)*	129.00	62.00	Cum	7998.00	
NET COST	TOTAL		RS.	3323067.90	
ADD CONTINGENCY 5 % **ADD SUPERVISION CHARGES 2 %** **ADD 18 % GST**			RS. RS. RS.	166153.40 66461.36 598152.22	
	TOTAL		RS.	4153834.88	
GROSS COST			SAY RS.	4153900.00	

Sub Engineer
Municipal Corporation Korba
District : Korba(C.G)

Assistant Engineer
Municipal Corporation Korba
Korba(C.G)

Executive Engineer
Municipal Corporation Korba
Korba(C.G)