



कार्यालय नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क./284,285,286,287,288/दर्री जोन/2018-19/

कोरबा दिनांक 25.07.2019

निविदा आमंत्रण सूचना

लोक निर्माण विभाग द्वारा एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित निर्माण कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग (भवन), रायपुर द्वारा 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरो पर दरों पर मैनुअल/ऑन लाईन निविदा वेब साईड से डाउनलोड कर आमंत्रित की जाती है।

क.	कार्य का नाम	प्राक्कलन राशि	घरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने हेतु आवेदन जमा करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की तिथि
1	वार्ड क्र. 53 दर्रीखार क्र.-02 में रोड़ नाली व भवन का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,91,000/-	4,000/-	750/-	02 माह	वर्ग "डी" एवं उपर की श्रेणी	07-08-19	16-08-19	23-08-19
2	वार्ड क 51 सरदार वल्लभ भाई पटेल नगर में रोड़,नाली भवन का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,87,000/-	4,000/-	750/-	02 माह	वर्ग "डी" एवं उपर की श्रेणी	07-08-19	16-08-19	23-08-19
3	वार्ड क्र. 55 बल्गी में रोड़ नाली व भवन का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,95,000/-	4,000/-	750/-	02 माह	वर्ग "डी" एवं उपर की श्रेणी	07-08-19	16-08-19	23-08-19
4	वार्ड क्र. 52 दर्रीखार क्र.-01 में रोड़ नाली व भवन का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,98,000/-	4,000/-	750/-	02 माह	वर्ग "डी" एवं उपर की श्रेणी	07-08-19	16-08-19	23-08-19
5	वार्ड क्र.51 अंतर्गत विभिन्न स्थानों पर रोड़ का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,94,000/-	4,000/-	750/-	02 माह	वर्ग "डी" एवं उपर की श्रेणी	07-08-19	16-08-19	23-08-19


शर्त

- निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक प्रतिशत दरों पर दिया जावे, सी.एस.आर. के अंतर्गत के आईटमों पर पृथक से आईटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियों नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सम्मुख अंकित राशि नगद जमा कर उपर लिखे तिथि को साँय 5.30 बजे तक अवकाश के दिन को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा भेजना हो तो रु. 50.00 अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी। साथ ही निविदा प्रपत्र निगम के वेब साईड से डाउनलोड करने पर निविदा प्रपत्र के साथ में (अ) घरोहर राशि एवं निविदा प्रपत्र शुल्क (ब) अर्हता संबंधित समस्त दस्तावेज एवं (स) निविदा प्रपत्र के साथ प्रस्तुत दर-तीन पृथक- पृथक लिफाफे में दी जावे, शुल्क एवं दस्तावेज परीक्षण उपरांत सही पाये जाने पर ही निविदा दर खोली जावेगी।
- निविदा प्रपत्र केवल स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किये जावेगे। निर्धारित तिथि को साँय 3.00 बजे के पश्चात प्राप्त निविदाओं पर विचार नहीं किया जावेगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो, उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने के इच्छुक ठेकेदारों को आवेदन के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनर शीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर प्रमाण पत्र/पैन नम्बर एवं छत्तीसगढ़ वाणिज्यिक पंजीयन प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, अमानत राशि का एफ.डी.आर./टी.डी.आर./नगद जमा की रसीद एवं निविदा प्रपत्र वेब साईड से डाउनलोड करने पर निविदा प्रपत्र शुल्क के रूप में डिमांड ड्राफ्ट अथवा नगद जमा रसीद संलग्न करना अनिवार्य होगा, अन्यथा प्रस्तुत निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र उन्ही ठेकेदारों को दिया जावेगा जिन्हें इस प्रकार के कार्यों का अनुभव हो।
- पूर्ण रूप से भरे निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है। और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहें तो उनके समक्ष खोली
- सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफॉरमेंस सिक्यूरिटी के रूप में रोकी जावेगी।
- आवेदन के साथ रु 10.00 लाख या उससे अधिक लागत के निर्माण कार्यों की निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं शेवा शर्तों का विनमय) अधिनियम 1996 एवं तदुत्तरगत निर्धारित नियमों के तहत पंजीयन करना आवश्यक होगा। तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- निविदा उन्ही ठेकेदारों को प्रदाय किये जावेगे जो कि कर्मचारी भविष्यनिधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- ईट से संबंधित निर्माण कार्यों में फ्लाइ एस ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
- कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेन्ट की खरीदी ठेकेदारों को स्वयं करनी होगी।
- निविदा प्रपत्र अहस्तान्तरणीय होगी एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।

- दरें एस.ओ.आर.से असामान्य होने पर सफल निविदाकार से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य कारमेन्स गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर. पोस्ट ऑफिस का टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
15. निविदा के संबंध में किसी भी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
 16. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम, कोरबा के पास सुरक्षित रहेगा।
 17. ठेकेदारों को उपरोक्त कार्य हेतु लगे श्रमिकों का भुगतान बैंक के माध्यम से किया जाना अनिवार्य होगा।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में शपथ पत्र देना अनिवार्य होगा।
 19. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा की वेब साइट www.korbamunicipal.in एवं साकेत भवन स्थित सूचना पटल एवं निर्माण शाखा (दर्री जोन) पर भी यह टेन्डर उपलब्ध है।

बोट :-

1. उपरोक्त निविदा तिथियों में कोई शासकीय अथवा स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय /स्थान माना जावे।
2. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर./अथवा नगद जमा राशि की रसीद आवेदन के साथ ही स्वीकार किये जावेंगे। जो कि आयुक्त नगर पालिक निगम कोरबा के नाम पर देय होगा।


कार्यपालन अधिकारी
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Name of Work **W. NO. 55 BALGIKHAAR ME ROAD, NALI VA BHAWAN KA MARAMMAT KARY (MARAMMAT SANDHAARAN MAD)**
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	22.56	185.00	4,173.60
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	5.64	371.00	2,092.44
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	5.52	2970.00	16,394.40
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	5.72	4073.00	23,297.56
5	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	6.60	4163.00	27,475.80
6	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	450.00	54.50	24,525.00
7	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	kg	5.00	43.50	217.50
8	3.16	Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.	sqm	60	273.00	16,380.00
9	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	21.91	139.00	3,045.49
10	4.13	Grading roof for water proofing treatment with:				
	13.1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone	cum	5.73	3817.00	21,871.41

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		aggregate 20 mm nominal size)				
	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	cum	5.7	3350.00	19,095.00
12	8.13	Providing and fixing flush door shutters, conforming to IS 2202 (Part 1), interior grade, commercial type, core of block board construction with frame of first class hard wood and well matched commercial ply veneering with vertical grains, cross bands and face veneers on both faces of shutters excluding hinges.				
	13.2	35 mm. thick (single leaf)	sqm	4.20	1370.00	5,754.00
13	8.52	Providing, and fixing M.S. round and square bars with MS flat of required pattern in wooden frames for windows & clerestory windows including applying a priming coat of red oxide zinc chromate primer, welding etc complete				
	52.1	Plain grill	kg	72.00	68.00	4,896.00
14	8.96	Providing and fixing M.S. bright finished or black enameled Double spring hinges with iron screws:				
	36.2	125 mm	each	15.00	286.00	4,290.00
15	8.97	Providing and fixing M.S. bright finished or black enameled Piano hinges 1mm thick with 35mm wide flange including necessary iron screws.				
16	8.99	Providing and fixing M.S. bright finished or black enameled sliding door bolts with bolts, nuts and necessary iron screws:				
	39.1	300x16mm	each	10.00	77.50	775.00
17	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	50.00	68.00	3,400.00
18	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	150.00	75.00	11,250.00
19	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	57.00	96.50	5,500.50
20	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	57.00	113.00	6,441.00
21	12.51	Extra for nosing in steps and treads of Kota stone slab.	metre		69.50	
22	14.9	Distempering with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)	sqm	700.00	38.00	26,600.00
	9.2	On old work (one or more coats)	sqm		17.50	
23	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	1033.00	94.50	97,618.50
24	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	500.00	41.00	20,500.00
	14.2	On old work (one or more coats applied @ 2.20 kg/10 sqm)	sqm		25.50	

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
25	14.22	Painting on new work (two or more coats) to give an even shade with:				
	22.1	Satin synthetic enamel paint	sqm	33.84	55.00	1,861.20
26	14.23	Painting on old work (one or more coats) to give an even shade with:				
	23.1	Satin synthetic enamel paint	sqm	48.24	35.00	1,688.40
27	14.44	Removing white or colour wash by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete.	sqm	1200.00	4.30	5,160.00
28	14.46	Removing old paint or polish by paint remover or blow lamp or any other means as approved including preparing the surface smooth after removing the paint.	sqm	48.24	32.50	1,567.80
29	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	43.2	1:3:6 or richer mix	cum	8.4	549.00	4,611.60
30	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.2	Size above 200x300mm	sqm	35.28	646.00	22,790.88
31	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	9.1	Size 300x300mm	sqm	17.28	692.00	11,957.76
As per Estimate Amount Rs.						395230.84

Sub Engineer
Nagar Palik Nigam
Korba (C.G.)

Assistant Engineer
Nagar Palik Nigam
Korba (C.G.)

Executive Engineer
Nagar Palik Nigam
Korba (C.G.)