



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

कोरबा जोन

फा.क्र./104,105,111से121/निर्माण (कोरबा जोन)/2022/

कोरबा, दिनांक 17.06.2022

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 11.07.2022 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 11.07.2022 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 6 से शीतला माता मंदिर से बनाफर घर तक सी.सी.रोड एवं नाली का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,91,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
2	वार्ड क 6 में सिंधी गली एवं दर्शन घर के समीप सी.सी.रोड मरम्मत एवं प्रीकास्ट स्लेब बिछाने का कार्य (मरम्मत एवं संधारण मद)	3,75,000/-	3,800/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
3	वार्ड क 6 में बंभारी चौक से भूषण तिवारी धर तक सी.सी.रोड मरम्मत एवं प्रीकास्ट स्लेब बिछाने का कार्य (मरम्मत एवं संधारण मद)	3,95,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
4	वार्ड क 8 ईमली डुग्गू अंतर्गत पार्श्व घर के समीप आर.सी.सी. नाला का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,79,000/-	3,800/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
5	वार्ड क 8 में ईमली डुग्गू अंतर्गत शिव सायकल स्टोर के समीप सी. सी. रोड का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,71,000/-	3,750/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
6	वार्ड क 9 रापाखर्रा सामुदायिक भवन का मरम्मत एवं उन्नयन कार्य (मरम्मत एवं संधारण मद)	3,49,000/-	3,500/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
7	वार्ड क 9 डेलवाडीह सामुदायिक भवन का मरम्मत एवं उन्नयन कार्य (मरम्मत एवं संधारण मद)	3,38,000/-	3,400/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
8	वार्ड क 10 अंतर्गत सीतामणी कैंवट मोहल्ला के समीप सी.सी.रोड एवं आर.सी.सी.नाली का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,81,000/-	3,850/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
9	वार्ड क 10 सीतामणी हटरी बाजार के समीप आर.सी.सी.नाली एवं सीमेंट कांकीट रोड का मरम्मत एवं निर्माण कार्य (मरम्मत एवं संधारण मद)	3,80,000/-	3,800/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022

10	वार्ड क 11 अग्रोहा मार्ग के समीप सी.सी.रोड एवं आर.सी.सी.नाली का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,84,000/-	3,850/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
11	वार्ड क 11 आंगनवाडी केंद्र पानी टंकी मोहल्ला के पास सी.सी. रोड का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,70,000/-	3,700/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
12	वार्ड क 12 अमरेया पारा सुवेदू घर के समीप सी.सी.रोड एवं आर.सी.सी. नाली का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,84,000/-	3,850/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022
13	वार्ड क 12 अंतर्गत अटल आवास के पास सी.सी. रोड का मरम्मत कार्य (मरम्मत एवं संधारण मद)	3,80,000/-	3,800/-	750/-	Form-A	03 माह	सक्षम श्रेणी	11.07.2022

निविदा की शर्त:-

- निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाईट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
(स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
- निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
- निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
- निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
- ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
- शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।

- (3)
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
 14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
 15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
 16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा निधि मद में राशि रनिंग देयकों से 01 वर्ष की अविध हेतु सिक्कुरिटी के रूप में रोकी जावेगी।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
 23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।


(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-


 कार्यपालन अभियंता
 नगर पालिक निगम
 कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Development

Name of Work **MAINTENANCE OF RAPAKHARA SAMUDAYIK BHAWAN IN WARD NO. 009**


As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	13.2	1:3:6 or richer mix	cum	7.2	549.00	3,952.80
2	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	7.2	2970.00	21,384.00
3	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.				
	13.1	Size 600x600mm	sqm	72	1151.00	27,624.00
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	3.6	4073.00	14,662.80
5	17.1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :				
	1.1	Thickness upto 15mm	sqm	228	132.00	30,096.00
6	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	247.2	94.50	23,360.40
7	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	243.20	56.00	13,619.20
8	16.26	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	each	1.00	100.00	100.00
9	16.27	Dismantling windows chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	each	5.00	66.50	332.50
10	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	175.00	67.50	11,812.50

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3 00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	291.6	75.00	21,870.00
12	7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: 5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand)				
13	11.2 Providing and making 12mm thick cement plaster of mix: 2.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	cum	8.96	3263.00	29,236.48
14	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: 3.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	44.8	91.50	4,099.20
15	9.11 Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer.	sqm	58.8	107.00	6,291.60
16	9.15 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	108.00	67.50	7,290.00

As per Estimate Amount Rs. 322927.48

322928.00


Sub Engineer
Nagar PalikNigam
Korba (C.G.)



Assistant Engineer
Nagar PalikNigam
Korba (C.G.)


Name of Work - PROPOSED ESTIMATE FOR CONSTRUCTION OF HALL (C.G)

Internal Electrification Works

SN	SOR	ITEM DESCRIPTION	NO	QT	U	RATE	AMOUNT
(B) AS PER CG PWD ELECTRICAL SOR 2020=							
1	6.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earthing etc. complete as required. P.F. should be greater than 0.9, with BEE Star rating					
	6.1.3	1200 mm sweep	1	2.00	Ea	1697.00	3394
2	5.9	Providing and fixing round/ hexagonal fan box (125mm dia) depth 75mm (max.) with 12mm dia steel bar hook, 1.6mm thick MS sheet	1	2.00	Ea ch	42.00	84
3	6.12	Providing and fixing phenolic laminated sheet cover of 180 mm dia 3 mm thick on the fan box etc. as per specification. (If provided	1	2.00	Ea ch	56.00	112
4	6.6	Supplying, installation, testing and commissioning of following sizes heavy duty (continuous running) 1400 rpm exhaust fan in existing opening in wall including earthing etc. complete as per specification.					
	6.6.1	300 mm sweep	1	1.00	Ea	2446.00	2446
5	6.16	Supplying, installation, testing and commissioning of following sleek LED panel down lighters (luminaries) in round/ square shape complete with electronic driver heat sink capacitor and all other accessories on surface/ in false ceiling etc. as per specification and					
	6.16.2	36 watt, size 600 x 600mm	1	1.00	Ea	2342.00	2342
6	6.15	Supplying, installation, testing and commissioning of following LED fitting (luminaries) down lighters in round/ square shape complete with electronic driver heat sink capacitor and all other accessories on surface/ in false ceiling etc. as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio \geq					
	6.15.6	18/20 Watt	1	1	Ea	868.00	868
7	6.19	Supplying, installation, testing and commissioning of following LED tube light fitting including batten with Electronic Driver Heat sink Capacitor complete with all other accessories on surface/ in false ceiling, including connection, earthing etc complete as per specification and IP20, P.F. should be greater					
	6.19.4	36 watt {4 feet}	1	1	Ea	718.00	718
8	32.79.1	Supplying of following LED Bulk Head complete with Electronic Driver Heat sink Capacitor 10 watt	1	1	Ea ch	1012.00	1012
9	1.7	Wiring for light/ fan/ exhaust fan / call bell point with 3x1.5 sqmm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) with 5/6 amp modular switch, modular base and cover plate, suitable size G.I.					
	1.7.1	Short Point	1	2	Poi	266.00	532
	1.7.2	Medium Point	1	2	Poi	424.00	848
	1.7.3	Long Point	1	0	Poi	588.00	0

1		Wiring for light plug point with 3x2.5 sq mm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) along with modular type 6 Amp switch and 3 pin 6 amps socket outlet with modular base and cover					
	1.10.1	Short Point	1	2	Poi	442.00	884
	1.10.2	Medium Point	1	2	Poi	659.00	1318
	1.10.3	Long Point	1	0	Poi	922.00	0
12	1.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) as per specification and IS: 694 (2010), IS: 9537 (2000 Part					
	1.13.1	3 X 1.5 sq. mm in 20mm conduit	1	10	Me	92.00	920
	1.13.3	3 X 2.5 sq. mm in 20mm conduit	1	10	Me	172.00	1720
	1.13.6	3 X 4 sq. mm in 25mm conduit	1	10	Me	145.00	1450
	1.13.14	6 X 10 sq. mm in 40mm conduit	1	10.00	Me	515.00	5150
16	5.4	Supplying and fixing following modular switch, socket, other accessories on the existing modular plate & switch box including connections but excluding modular plate etc. as per					
17	5.4.9	Fan regulator (two module size) electronic stepped type moving all rounds	1	1.00	Each	223.00	223
	5.4.17	Computer Outlet Jack	1	1.00	Each	242.00	242
18	5.6	Providing and fixing composite unit for computer points having modular type 1 No 6 pin 16 amp socket outlet, 1 No 16 amp switch, 3 Nos 3 pin 6 amp socket outlets, 3 Nos 6 amp switches, suitable G.I. box, base and cover plates, earthing the sockets and switch box	1	1.00	Each	816.00	816
20	9.11	Supplying and fixing SP MCB, 240 volts, 'C' curve, suitable for inductive load in the existing MCB DB complete with connections,					
	9.11.2	6 amps to 32 amps	1	1.00	Each	148.00	148
G.TOTAL (In Indian Rupees)=							25227


 Sub Engineer,
 Municipal
 Corporation Korba
 (C.G.)


 Assist. Engineer,
 Municipal
 Corporation
 Korba (C.G.)