

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2019/292

सिस्टम टेन्डर नं. 54633
ई-निविदा आमंत्रण सूचना

कोरबा, दिनांक 13/08/2019

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015, से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 51 अंतर्गत सार्वजनिक सामुदायिक / सांस्कृतिक भवन का संधारण एवं भवन में नयी सुविधाओं की व्यवस्था बाबत।	7.00	5300/-	02 माह	वर्ग डी एवं प्रवर श्रेणी	03.09.2019 से

शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		13.08.19	10.30	13.08.19	10.30	Release Tender
2		Bid Submission	13.08.19	10.30	03.09.19	17.30	
3	Tender Open		04.09.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
ABSTRACT

Name of Work **WARD NO. 51 SARVJANIK SAMUDAYIK / SAANSKRITIK BHAWAN KA SANDHARAN AVM BHAWAN ME NAYI**
SUVIDHAON KI VYAVASTHA. (COUNCILLOR FUND)
As per SOR : **SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]**

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
			cum	19.11	185.00	3,535.35
	1.1	In all types of soils.				
			cum	4.44	371.00	1,647.24
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.				
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
			cum	4.32	2970.00	12,830.40
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).				
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
			cum	7.82	4073.00	31,850.86
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).				
5	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
			cum	6.5	4163.00	27,059.50
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).				
6	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
			kg	500.00	54.50	27,250.00
	12.1	Thermo-Mechanically treated bars FE 415	kg	10.00	43.50	435.00
7	3.14	Providing and mixing water proofing material in PCC/RCC work in the proportion recommended by the manufacturer.				
			sqm	60	273.00	16,380.00
8	3.16	Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.				
9	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
			sqm	26.91	139.00	3,740.49
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.				
10	4.13	Grading roof for water proofing treatment with:				


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	13.1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	8.53	3817.00	32,559.01
11	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	cum	10.7	3350.00	35,845.00
12	8.13	Providing and fixing flush door shutters, conforming to IS 2202 (Part 1), interior grade, commercial type, core of block board construction with frame of first class hard wood and well matched commercial ply veneering with vertical grains, cross bands and face veneers on both faces of shutters excluding hinges.				
	13.2	35 mm. thick (single leaf)	sqm	8.40	1370.00	11,508.00
13	8.52	Providing, and fixing M.S. round and square bars with MS flat of required pattern in wooden frames for windows & clerestory windows including applying a priming coat of red oxide zinc chromate primer, welding etc complete				
	52.1	Plain grill	kg	180.00	68.00	12,240.00
14	8.96	Providing and fixing M.S. bright finished or black enameled Double spring hinges with iron screws:				
	36.2	125 mm	each	15.00	286.00	4,290.00
15	8.97	Providing and fixing M.S. bright finished or black enameled Piano hinges 1mm thick with 35mm wide flange including necessary iron screws.				
16	8.99	Providing and fixing M.S. bright finished or black enameled sliding door bolts with bolts, nuts and necessary iron screws:				
	39.1	300x16mm	each	30.00	77.50	2,325.00
17	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	200.00	68.00	13,600.00
18	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	150.00	75.00	11,250.00
19	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	57.00	96.50	5,500.50
20	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	57.00	113.00	6,441.00
21	12.51	Extra for nosing in steps and treads of Kota stone slab.	metre		69.50	
22	14.9	Distemping with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)	sqm	700.00	38.00	26,600.00
	9.2	On old work (one or more coats)	sqm		17.50	
23	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	1033.00	94.50	97,618.50
24	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	500.00	41.00	20,500.00


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	14.2	On old work (one or more coats applied @ 2.20 kg/10 sqm)	sqm		25.50	
25	14.22	Painting on new work (two or more coats) to give an even shade with:				
	22.1	Satin synthetic enamel paint	sqm	32.52	55.00	1,788.60
26	14.23	Painting on old work (one or more coats) to give an even shade with:				
	23.1	Satin synthetic enamel paint	sqm	48.24	35.00	1,688.40
27	14.44	Removing white or colour wash by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete.	sqm	1200.00	4.30	5,160.00
28	14.46	Removing old paint or polish by paint remover or blow lamp or any other means as approved including preparing the surface smooth after removing the paint.	sqm	48.24	32.50	1,567.80
29	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	43.2	1:3:6 or richer mix	cum	8.4	549.00	4,611.60
30	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.2	Size above 200x300mm	sqm	35.28	646.00	22,790.88
31	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	9.1	Size 300x300mm	sqm	17.28	692.00	11,957.76
32	10.1	Providing corrugated G.I. sheet roofing including vertical/ curved surfaces fixed with galvanized iron, J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead including painting with primer and paint on overlapping of sheets complete excluding the cost of purlins rafters and trusses. (Zinc coating not less than 272 gms/sqm)				
	1.4	0.5 mm thick sheet (weight 4.30 kg/m ²)	sqm		540.00	
33	10.5	Providing ridges or hips of 60cm overall width in plain G.I. sheet fixed with galvanized washers J or L hooks, bolts and nuts 8mm G.I. limpet and bitumen washers complete.				
	5.4	0.50 mm thick sheet with zinc coating not less than 275 gm/sqm	sqm	112.00	380.00	42,560.00
34	10.10	Extra for providing and fixing wind ties of 40x6mm flat iron section.	metre	40.00	118.00	4,720.00
35	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	Kg	300.00	66.00	19,800.00
36	12.56	25mm thick Local RAJIM/ Red Flag stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid over & jointed with grey cement slurry mixed with pigments to match the shade of the stone i/c grinding, rubbing and polishing.	sqm	252	516.00	130,032.00
37	12.57	25mm thick Local RAJIM/ Red Flag stone slab in riser of steps, skirting, dado and pillars laid on 12mm (Average) thick cement mortar 1:4 (1 cement : 4 coarse sand) and joint with grey cement slurry mixed with pigments to	sqm	80.00	595.00	47,600.00


S.N.	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		match the shade of the slab i/c grinding, rubbing and polishing.				

As per Estimate Amount Rs. 699282.89

Say Rs. 7,00,000/-


Sub Engineer
Nagar Palik Nigam
Korba (C.G.)


Assistant Engineer
Nagar Palik Nigam
Korba (C.G.)


Executive Engineer
Nagar Palik Nigam
Korba (C.G.)

1.1		In all types of soil up to 1/2 wall				
2.1.1B		Grinding and filling in pink with sand/Coarse sand not hard material 20mm. Thick in layers not exceeding 10mm in depth consolidating each deposited layer by ramming and watering including drainage etc. complete.				
		Grinding and filling in pink with 1:3 cement mortar with 20mm sand aggregate using 20mm. gauge or 6x works with pink level including cost of form work.				
		Grinding and filling in pink with 1:4 graded sand aggregate 40mm 20mm. gauge				