

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2020/11

सिस्टम टेन्डर नं. 63939
ई-निविदा आमंत्रण सूचना

कोरबा, दिनांक 12/05/2020

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015, (विद्युत) दिनांक 01.01.2015से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार प्रतिशत दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रू में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	पौनी पसारी योजनांतर्गत ईतवारी बाजार में पौनी पसारी बाजार निर्माण कार्य।	29.42	22100/-	04 माह	वर्ग डी एवं प्रवर श्रेणी	04.06.2020 से


शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री एवं उद्घानिकी में स्नातक नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		12.05.20	10.30	12.05.20	10.30	Release Tender
2		Bid Submission	12.05.20	10.30	03.06.20	17.30	
3	Tender Open		04.06.20	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
 For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA

TECHNICAL SANCTION

Name of work - Constuction and development of work under Pouni Pasari Scheme

DETAILED ESTIMATE

GENERAL ABSTRACT

AMOUNT OF WORK -

Rs.- 30.00 Lakhs

PROVISION-

S.NO.	SUB HEAD	QUANTITY	UNIT	RATE (Per SQ.M/RMT./Nos.)	AMOUNT (In Rs.)
(A)	BUILDING WORK-				
1	Shed with Chabutra-	152.00	SQ.M	8302.63	1262000.00
2	Toilet Block-	19.80	SQ.M	13735.64	272000.00
	Internal Electrification(Toilet Block & Shed Area)-				199000.00
	Internal Sanitary & Water Supply Work-				99000.00
	TOTAL BUILDING(A)-	171.80	SQ.M	10663.41	1832000.00
(B)	DEVELOPMENT WORK-				
1	Drain (300x400 mm) -	50.00	RMT.	2420.00	121000.00
2	Parking & Paved Area-	264.72	SQ.M	902.84	239000.00
3	Septic Tank with Soak pit.-	1	NO.	154000.00	106000.00
4	Borewell with Pump-	1	NO.	98000.00	90000.00
5	Electric Poles-	10	NOS.	24700.00	247000.00
6	Rain Water Harvesting	2	NOS.	20500.00	41000.00
7	Installation of Water Cooler/Purifier with Platform,Protection Jali & Electrification with Connection etc. -	1	Job	94500.00	94500.00
8	Construction of Cement Concrete Approach Road-	180	Sqm	950.00	171000.00
	TOTAL DEVELOPMENT (B)-				1109500.00
	TOTAL(A+B)-				2941500.00
	Adding extra 2 % for Contingencies Rs.-				58830.00
	GRAND TOTAL Rs.-				3000330.00
	Or Say Rs.-				3000000.00

SOR Used -

Building work (PWD Building 01.01.2015)

Electrification work - Electrical (PWD E&M SOR 01.01.2015)

NON SOR ITEM- Water Cooler with plaform, Jali & Elecrification


ESTIMATED AMOUNT - Rs 30.00 Lakh

T.S. No. /Date : 1/787 / 18-09-2019.

T. S. No. 1/787 Dt. 18/9/2019

Technically Approved for Construction and development of work under Pouni Pasari scheme

In ward No. 30 CD, CDW- (in words) Rs. Thirty Lakh Only


 Executive Engineer,
 Municipal Corporation,
 KORBA (Chhattisgarh)
 Executive Engineer
 Municipal Corporation
 Korba (C.G.)

पौनी पसारी योजना

DETAILED ESTIMATE

"REPORT & SPECIFICATIONS"

S. No.	Particulars	Specifications
A)	Civil Work	
1	SHED WITH CHABUTRA	
a	Foundation	R.C.C. works including isolated footing, column, Beam (All M-20).
b	Filling	Crushed Stone Dust of Sand/Moorum.
c	Brick Work	fly-ash lime bricks in Chabutra.
d	Steel tubular truss structure	tubes Grade-300.
e	Flooring	polyvinyl chloride sheet in flooring damp proof base using rubber based adhesive flooring.
f	Painting	Putty, ACRYLIC SMOOTH exterior paint, Distemper.
g	Plastering	15 mm thick cement Plaster in outer wall in cm 1:6 and 6mm thick cement plaster in cm 1:4 on column area.
h	Roofing	precoated gaivanized iron profile sheets.
2	TOILET BLOCK	
a	Foundation & Super Structure	R.C.C.framed structure including isolated footing, column, Beam, (All M-20).
b	Filling	Crushed Stone Dust of Sand/Moorum.
c	Brick Work	fly-ash lime bricks.
d	Structure	R.C.C. M-20.
e	Flooring	Ceramic Tiles Flooring
f	Joinery	frames made of cold rolled pressed steel sheet & UPVC frame with Flush Door & PVC Doors.
g	Painting	Putty, ACRYLIC SMOOTH exterior paint, Distemper.

	Particulars	Specifications
1	Development Work	
1	Parking & Paved Area	
a	Granular Sub-base-	150 mm Thick.
b	Sand Filling-	150 mm Thick.
c	P.C.C.	100 mm thick in Parking Only.
d	Paver-	60mm thick precast interlocking concrete blocks.
2	ELECTRICAL POLE	
a	Pole	4 m High.
b	LED Light	25-30 watt
3	DRAIN	
a	Structure	R.C.C. M-20.
b	P.C.C.	100 mm thick (P.C.C. M-10).
c	Filling	Crushed Stone Dust of Sand/Moorum.
d	Top Grating	Steel work.
4	SEPTIC TANK WITH SOAK PIT	
a	Structure	R.C.C. M-20.
b	P.C.C.	150 mm thick (P.C.C. M-10).
c	Soak pit	1.20x1.20x1.20m
d	Flooring	25mm thick 1:2:4 Cement Concrete.
e	Manhole-	Precast RCC Manhole 450x600 mm

Particulars	Specifications
S BOREWELL WITH PUMP	
a Casin Pipe-	200 mm Dia 90m Depth, 4hp Pump.
b Pump-	4 HP.
Rates Adopted :-	
i	The Rates adopted for estimate are referred from the SOR for <u>Building Works</u> with effect from 01-01-2015 issued by Engineer-in-Chief PWD, Raipur (C.G.).
ii	The Rates adopted for estimate are referred from the SOR for <u>Road Works</u> with effect from 01-01-2015 issued by Engineer-in-Chief PWD, Raipur (C.G.).
ii	The Rates adopted for estimate are referred from the SOR for <u>Electrical Works</u> with effect from 01-01-2015 issued by Engineer-in-Chief PWD, Raipur (C.G.).
iv	The Rates adopted for estimate are referred from the SOR for <u>Water Supply And Sewerage Works</u> with effect from 07-02-2013 issued by Engineer-in-Chief PHE, Raipur (C.G.).