कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

जलप्रदाय शाखा :– साकेत भवन आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फैक्स : 07759–221929, पो. बाक्स नं. : 12 पिन कोड : 495677

Website :www.Korbamunicipal.in Email : mck.watersupply@gmail.com

फा.क्र./1171/ज.प्र.स./2019/ सिस्टम निविदा क. 51827 कोरबा, दिनांक 10.06.2019

निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा शासकीय एवं अर्धशासकीय विभागो में कार्यरत् उचित श्रेणी में पंजीकृत अनुभव निविदाकार/फर्मो से (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) शेडयूल अनुसार आयटम दरों पर ई–टेंडरिंग के माध्यम से निविदाएं आमंत्रित की जाती हैं :–

क्र.	कार्य का नाम	प्राक्कलन राशि	अमानत राशि	कार्यावधि	निविदा खुलने की तिथि
1.	जल उपचार संयंत्र कोहड़िया में स्थापित 33 के.व्ही.ए. सब स्टेशन का मरम्मत, संधारण विविध सामग्री प्रदाय एवं स्थापना कार्य।	8,96,910.00	7000/-	03 माह	02.07.2019

शर्तें :–

1. जिन अनुभवी निविदाकार /फर्मो द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नह होगी।
3. निविदा प्राप्त करने के इच्छुक अनुभवी निविदाकार/फर्मो को आवेदन के साथ साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों का अनुभव प्रमाण पत्रों की जानकारी, आयक प्रमाण पत्र/पेन नं. एवं जी.एस.टी. प्रमाण पत्र एवं अमानत राशि ऑन लाईन जमा कर स्केन कापी बेवसाइट पर अपलो करना अनिवार्य होगा।
4. निविदा प्रपत्र उन्ही अनुभवी निविदाकार/फर्मों को दिया जावेगा। जिन्हे इस प्रकार के कार्य का अनुभव हों।
5. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
6. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
7. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
8. सम्पूर्ण किये गये कार्यो के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए रोकी जावेगी।
9. ठेके से संबंधित निविदा प्रपत्र उन्ही ठेकेदारो को प्रदाय किये जावेंगें जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचा राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नही किया जावेगा।
10. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनिय 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप प्रत्येक देयक से कटौती की जावेगी।

. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम कोरबा की वेब साइट www.korbamunicipal.in पर भी य टेन्डर उपलब्ध है।

11. अन्य सूचनाएं नगर पालिक निगम साकेत भवन, रामपुर, कोरबा के जल प्रदाय शाखा से प्राप्त की जा सकती है।
12. **छ.ग.वि.मण्डल एवं छत्तीसगढ़ अनुज्ञापन मण्डल (विद्युत) में 'अ' श्रेणी का पंजीकृत/लाईसेंस अनिवार्य है।**
13. **निविदाकार को 33 के.व्ही. वर्क का कार्य अनुभव हो।**

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		10.06.19	15.00	10.06.19	15.00	Release Tender
2		Bid Submission	10.06.19	15.00	01.07.19	17.30	
3	Tender Open		02.07.19	10.30	--	--	

EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORTION, KORBA

Estimate for Compete Maintains, Supply, Repairing with Testing of 33KVA Sub Station at Water Treatment Plant Kohariya Korba.

Sl No.	Description	Qty	Rate	Amount Rs. P.
01.	Supply & Fixing of approved Make 33KV Glazed Porcelain Disc Type Insulator with Tension Hardware on Existing pole/Support/Cross Arm Channel as required Complete	12 Set	3200/-	38,400.00
02.	Supply & Fixing of approved Make 33KV Glazed Porcelain Pin Insulator with JI Spindle Existing pole/Support/Cross Arm Channel as required Complete	18 No	525/-	9,450.00
03.	Supply & fixing of D.O Fuse Down Road Assly Completed with Chanel Cross Arm as required	02 No	6500/-	13,000.00
04.	Supply & Erection of Stander ACSR Aluminum Conductor for Bus Bar Confirming to IS 398/1961 from Ground level including Jumpering tearing off Connection etc Size 95Sqmm Dog conductor	70 Mtr	120/-	8,400.00
05.	Supply & fixing of JVS make – earth Leakage Relay rated Voltage 110V/ Burden 0.5MA /0.10MA	01 No	28500/-	28,500.00
06.	Supply & fixing of Ganges Operating Rotary Switch for On/Off Spring Charging of VCB	04 No	1200/-	4,800.00
07.	Supply & Fixing of HRC Fuse 16 Amp 440V with Base	28 No	220/-	6,160.00
08.	Supply & Fixing of 110V/2N2C Relay Make – PLA with Base	06 No	750/-	4,500.00
09.	Supply & Fixing of KV Meter Size – 125/125MM	02 No	1800/-	3,600.00
10.	Supply & Fixing of Analog AMP Meter as per Required Amp	04 No	1200/-	4,800.00
11.	Supply & Laying of Sub Control Cable of PT/CT Control Device of Transformer and Vacuum Breaker Size – 4 Core 2.5Sqmm Copper Multi Cable Make – Policab, Gloster with Excavation of cable trench laying Filling with labor charge	150 Mtr	220/-	33,000.00
12.	Supply & Laying of Sub Control Cable of PT/CT Control Device of Transformer and Vacuum Breaker Size – 6 Core 4Sqmm Copper Multi Cable Make – Policab, Gloster with Excavation of cable trench laying Filling with labor charge	70 Mtr	280/-	19,600.00
13.	Supply & Commissioning of Earth Excavation of Pit 10 Fit Depth 4X4 Fit with Copper Plate, And GI Pipe, Copper Strip & Required Cool & Salt as per IS	02 No	35400/-	70,800.00
14.	Supply & fixing of Feeder Protection & Transformer Protection JVS Make – Over Current Rely Rated Voltage 110/30, Rated Burden 10VAC/15VAC/25VAC	03 No	26500/-	79,500.00
15.	Supply & Fixing of Gange Operating Air Brick switch on Existing 2 Pole structure with insulator and all other Accessories complete locking type arrangement as required	02 No	41500/-	83,000.00
16.	Supply & Erection of 33KV DC Fuse Unit on Existing 2 Pole Structure with insulator and all other Accessories complete including locking arrangement As required	02 Set	32500/-	65,000.00
17.	Supply & Erection of Single Pole Nonlinear resistor type lighting Arrestor suitable for 3 Wire 33KV Over Had Line with rated Voltage 30KV with nominal discharge rating 10KA and completed with Earth connected	02 Set	38200/-	76,400.00

18.	Supply & Erection of 33KV, 110V, 10VAC Oil Immersed Voltage Transformer on 2 Pole Structure with Post Insulator & all other Accessories as required	03 No	48000/-	1,44,000.00
19.	Supply & Installation of 2V 200Amp Exide Make Battery Bank Total Voltage 30V	15 No	7800/-	1,17,000.00
20.	Supply & Installation of 33Kva 800Amp Isolator on fixing two pole structure	01 Set 03 No	32000/-	32,000.00
21.	Commissioning testing,& Repairing with labor charges	01 Job	55000/-	55,000.00
	Total Amount Rs. (Eight Lack Ninty Six Thousand Nine Hundred Ten Only/-)			8,96,910.00

Sub Engineer
Municipal Corporation,
Korba

Assistant Engineer
Municipal Corporation,
Korba

Executive Engineer
Municipal Corporation,
Korba