



कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क./485, 486, 488/निर्माण (कोसा.)/2019


कोरबा, दिनांक 28.02.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

| क्र | कार्य का नाम | प्राक्कलन राशि में | धरोहर राशि रू में | निविदा प्रपत्र का मूल्य | कार्यावधि | ठेकेदार का वर्ग | निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि | निविदा प्रपत्र प्राप्त करने की अंतिम तिथि | निविदा खुलने की अंतिम तिथि |
|-----|---|--------------------|-------------------|-------------------------|-----------|-----------------|---|---|----------------------------|
| 1 | वार्ड क्रमांक 29 पोड़ीबहार में मंच, शेड एवं सामुदायिक भवन का मरम्मत एवं पेंटिंग का कार्य । (षार्षद मद 2018-19) | 4,50,000/- | 4500/- | 750/- | 03 माह | सक्षम श्रेणी | 13.03.2019 | 15.03.2019 | 23.03.2019 |
| 2 | वार्ड क्रमांक 17 गुलापी हॉटल से नायक घर तक आर.सी.सी. नाली एवं सी.सी. रोड एवं मरम्मत कार्य । (मरम्मत एवं संधारण मद) | 3,96,813/- | 4000/- | 750/- | 03 माह | सक्षम श्रेणी | 13.03.2019 | 15.03.2019 | 23.03.2019 |
| 3 | वार्ड क्रमांक 32 रिसदी श्रीवारस्तव गोइल्ला में आर.सी.सी. गंच का निर्माण कार्य । (विधायक मद 2018-19) | 3,50,000/- | 3500/- | 750/- | 03 माह | सक्षम श्रेणी | 13.03.2019 | 15.03.2019 | 23.03.2019 |

उपरोक्त कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है साथ ही यह जानकारी विभागीय वेबसाइट Website : www.korbamunicipal.in एवं www.uad.cg.gov.in में देखा एवं डाउनलोड किया जा सकता है। उक्त निविदा में किसी भी प्रकार का संशोधन किया जाता है तो विभागीय वेबसाइट पर देखा जा सकता है।


कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

॥ स्वच्छ भारत निर्माण में योगदान दें ॥


OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
ABSTRACT


Work CONSTRUCTION OF RCC MUNCH IN SHRIVASTAV MOHALLA RISDI WARD NO. 32
IR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

| EF | ITEM DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|----|--|------|---------|---------|-----------|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. | | | | |
| .1 | In all types of soils. | cum | 24.57 | 185.00 | 4,545.45 |
| 7 | Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M. | cum | 16.80 | 65.00 | 1,092.00 |
| | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | cum | 4.80 | 371.00 | 1,780.80 |
| | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. | | | | |
| | 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). | cum | 4.47 | 2659.00 | 11,885.73 |
| | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. | | | | |
| | 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | cum | 16.11 | 4163.00 | 67,065.93 |
| | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: | | | | |
| | Thermo-Mechanically treated bars FE 415 | kg | 1135.75 | 54.50 | 61,898.37 |
| | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: | | | | |
| | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. | sqm | 28.56 | 139.00 | 3,969.84 |
| | Columns, Pillars, Piers and likes- rectangular or square in shape | sqm | 21.60 | 297.00 | 6,415.20 |
| | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ) | sqm | 32.11 | 235.00 | 7,545.85 |
| | Beams, lintels, cantilevers & walls | sqm | 24 | 202.00 | 4,848.00 |
| | Weather shade, chhajja, Cornices and mouldings | sqm | 16.80 | 294.00 | 4,939.20 |
| | Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to S:12894-2002 of class designation 4.0 in foundation and plinth in: | | | | |
| | Cement Mortar 1:6 (1 cement : 6 coarse sand) | cum | 19.68 | 3263.00 | 64,215.84 |
| | Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | cum | 18.00 | 121.00 | 2,178.00 |

| REF | ITEM DESCRIPTION | UNIT | QTY | RATE | AMOUNT |
|-----|---|------|--------|---------|-----------|
| .11 | Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2mm and braced with flat iron diagonals 20x5mm size with top and bottom rails of T-iron 40x40x6mm with 38mm steel pulleys complete with bolts, nuts, locking arrangement stoppers, handles including applying a priming coat of red oxide zinc chromate primer. | sqm | 5.67 | 3330.00 | 18,881.10 |
| 15 | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer. | kg | 200.00 | 67.50 | 13,500.00 |
| 1 | Providing and making 6mm thick cement plaster of mix: | | | | |
| .2 | In Cement mortar 1:4 (1 cement : 4 fine sand) | sqm | 24.00 | 87.00 | 2,088.00 |
| 2 | Providing and making 12mm thick cement plaster of mix: | | | | |
| 4 | In Cement Mortar 1:6 (1 cement : 6 fine sand) | sqm | 98.4 | 91.50 | 9,003.60 |
| 1 | Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: | | | | |
| 4 | In Cement Mortar 1:6 (1 cement : 6 fine sand) | sqm | 120 | 107.00 | 12,840.00 |
| | Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. | | | | |
| | Size 600x600mm | sqm | 24.00 | 1151.00 | 27,624.00 |
| | Distemping with acrylic washable distemper to give an even shade. | | | | |
| | On new work (Two or more coats) | sqm | 120.00 | 38.00 | 4,560.00 |
| | Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even. | sqm | 124 | 94.50 | 11,718.00 |
| | Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: | | | | |
| | On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) | sqm | 124.00 | 56.00 | 6,944.00 |
| | Painting on new work (two or more coats) to give an even shade with: | | | | |
| | Satin synthetic enamel paint | sqm | 9.27 | 55.00 | 509.85 |

As per Estimate Amount Rs. 350048.76


Sub-Engineer
Nagar Palik Nigam
Korba(C.G.)


Asst. Engineer
Nagar palik Nigam
korba(C.G.)