

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2019/ 521

सिस्टम टेन्डर नं. 53645
ई-निविदा आमंत्रण सूचना


कोरबा, दिनांक 25/07/2019

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015, से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 4 अंतर्गत अग्रसेन चौक से दुरपा रोड, लवली केयर स्कूल से रेलवे लाईन तक सी.सी. रोड एवं नाली का कवरिंग का कार्य।	16.12	12100/-	04 माह	वर्ग डी एवं प्रवर श्रेणी	17.08.2019 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपोजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		25.07.19	10.30	25.07.19	10.30	Release Tender
2		Bid Submission	25.07.19	10.30	16.08.19	17.30	
3	Tender Open		17.08.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Construction of Cement Concrete Road and Drain Covering Work from Agrasen Chowk to Durpa Road Lovely Care School and Upto Railway Line at Ward No. 4

Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	SOR Ref.	DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	16.4	Demolishing cement concrete including disposal of material within 50 metre lead.								
		2 1:3:6 or richer mix								
			2	280.00	0.20	0.20	22.40			
			500	0.90	0.45	0.10	20.25			
			1	180.00	0.60	0.08	8.64			
						Total=	51.29	Cum	549.00	28158.21
2	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.								
		3 In cement mortar.								
			2	80.00	0.20	0.60	19.200			
			1	32.00	0.30	0.60	5.760			
			1	18.00	0.60	0.60	6.480			
						Total=	31.440	Cum	263.00	8268.72
3	16.4	Demolishing cement concrete including disposal of material within 50 metre lead.								
		1 1:4:8 or richer mix								
			1	80.00	2.50	0.10	20.00			
						Total=	20.00	Cum	329.00	6580.00
4	3.1	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
		3 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).								
			1	80.00	2.50	0.10	20.00			
						Total=	20.00	Cum	2970.00	59400.00
5	2.1	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
		1 Foundations, footings, base of columns and plinth beam in any shape and size.								
			4	400.00		0.30	480.00			
			2	140.00		0.12	33.60			
			47	2.80		0.12	15.79			
						Total=	529.39	Sqm	139.00	73585.49
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
		1 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			2	400.00	0.20	0.30	48.00			
			1	180.00	0.60	0.10	10.80			

			889	0.90	0.45	0.12	43.21			
						Total=	102.01	Cum	4163.00	424667.63
7	3.1	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	1	Thermo-Mechanically treated bars FE 415				Total=	7262.00	Kg	54.50	395779.00
8	3.2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			1	140.00	2.80	0.12	47.040			
						Total=	47.040	Cum	4073.00	191593.92
9	3.9	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.								
			889	0.90	0.45	0.12	43.21			
						Total=	43.21	Cum	469.00	20263.33
10	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
	2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.					245.00	Kg	68.00	16660.00
11	1.26	Carriage by mechanical transport upto 5 km lead:								
	1	Earth					102.73	Cum	111.00	11403.03
NON SOR ITEM										
12	NS-2	Shifting of pipe line of any size including excavation, cutting, threading, fixing all complete.					66.00	per point	1200.00	79200.00
13	NS-1	Cleaning of drain of any size upto bottom level including taking out the RCC slab and disposal of all garbage, waste etc. upto a lead of km								
							436.00	Rm	680.00	296480.00
TOTAL =										1612039.33

Say Rs = 1612000.00

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

Sub Engineer
Municipal Corporation
Korba (C.G.)