

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2019 1470

सिस्टम टेन्डर नं. 50174
ई-निविदा आमंत्रण सूचना

कोरबा, दिनांक 01/03/2019

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	इमलीडुगू चौक के पास पार्किंग क्षेत्र, फुटपाथ एवं लैण्ड स्केपिंग एवं विकास कार्य	38.02	28600/-	04 माह	वर्ग डी एवं प्रवर श्रेणी	26.03.2019 से


शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाइ ईश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो गांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		01.03.19	15.00	01.03.19	15.00	Release Tender
2		Bid Submission	01.03.19	15.00	25.03.19	17.30	
3	Tender Open		26.03.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

			1	110.00	1.00	0.10	11.00				
			1	110.00	2.00	0.10	22.00				
			52	0.30	0.30	0.60	2.81				
							102.91	Cum	2970.00	305642.70	
5	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.									
	1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).									
			1	50.00	1.20	0.15	9.000				
			2	50.00	0.20	0.60	12.000				
			100	1.00	0.60	0.10	6.000				
							27.000	Cum	4163.00	112401.00	
6	3.3	Providing and laying design mix reinforced cement concrete with crushed graded stone aggregate 20mm nominal size using batching plant, transit mixer and concrete pump, in all works upto plinth level excluding cost of form work.									
	3	M-30 Grade									
			1	30.00	9.00	0.30	81.00				
			1	30.00	6.00	0.30	54.00				
							135.00	Cum	4362.00	588870.00	
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:									
	1	Thermo-Mechanically treated bars FE 415					8100.00	Kg	54.50	441450.00	
8	3.2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.									
	5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).									
			1	110.00	10.00	0.15	165.000				
			1	260.00	0.30	0.10	7.800				
							172.800	Cum	4073.00	703814.40	
9	3.9	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.									
			100	1.00	0.60	0.10	6.000				
							6.000	Cum	469.00	2814.00	
10	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:									
	3	Cement Mortar 1:5 (1 cement : 5 coarse sand)									
			1	60.00	0.30	0.60	10.800				
			1	130.00	0.30	0.60	23.400				
			1	70.00	0.30	0.60	12.600				
							46.800	Cum	3350.00	156780.00	
11	11.2	Providing and making 12mm thick cement plaster of mix:									
	3	In Cement Mortar 1:5 (1 cement : 5 fine sand)									
			1	60.00		0.90	54.00				
			1	130.00		0.90	117.00				
			1	70.00		0.90	63.00				

					Total=	234.00	Sqm	96.50	22581.00
9.43	Providing and fixing in position chain linked steel wire mesh made of 4mm dia G.I. wire of required width mesh to concrete/ wooden/angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete.								
	2 Aperture 75x75mm								
		1	130.00		2.10	273.00			
					Total=	273.00	Sqm	291.00	79443.00
13	9.6 Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
	2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.								
						912.00			
					Total=	912.00	Kg	68.00	62016.00
14	9.3 Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.								
	1 Electric resistance or induction butt welded tubes Grade-250								
						5166.60			
					Total=	5166.60	Kg	88.50	457244.10
15	18.76 Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.					70.000	m	440.00	30800.00
	3 150 mm dia pipe.								
16	14.2 Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
		1	60.00		0.90	54.00			
		1	130.00		0.90	117.00			
		1	70.00		0.90	63.00			
					Total=	234.00	Sqm	74.50	17433.00
17	14.2 Painting on new work (two or more coats) to give an even shade with:								
	1 Painting on new work (two or more coats) to give an even shade with:					504.48	Sqm	55.00	27746.40

	Providing and fixing plain cement concrete fibre reinforced heavy duty designer glazed floor tiles with uniform colour (for coloured tiles) and texture conforming to IS: 1237 (for abrasion wear) and IS : 516 (for compressive strength) of approved make, colours, shades and size on cement Mortar bed and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.								
2	On floor, steps and risers over 20mm thick bed of cement Mortar 1:4 (1 cement : 4 coarse sand)								
		1	110.00		2.40	264.00			
					Total=	264.00	Sqm	905.00	238920.00

NON SOR ITEM (PART B)

1	NS-1	Installation, Testing, Commissioning of 1 H.P. Submersible Pump including Starter, Suction and Delivery Pipe and Water Proof Cable of Required length.					1.00	No.	22000.00	220000.00
2	NS-2	Tensile fabric work 900 GSM with M.S. pipe frame as per Design and Drawing.	4	3.5	1.20	16.80	Sqm	8200.00	137760.00	

TOTAL = 3802000.60

Say Rs.= 3802000.00

Asstt. Engineer
Municipal Corporation
Korba (C.G.)

Sub Engineer
Municipal Corporation
Korba (C.G.)