

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क.1283 / निर्माण / 2022

सिस्टम टेंडर नं 114724

कोरबा दिनांक 16.11.2022

द्वितीय ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 एवं सड़क कार्य हेतु दिनांक 01.01.2015 एवं विद्युत कार्य हेतु दिनांक 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त सशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती हैं :-

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	नगर पालिक निगम कोरबा में निर्मित पुस्तकालय हेतु आवश्यक अतिरिक्त सिविल कार्य	25.65	26000/-	02 माह	वर्ग डी एवं प्रवर श्रेणी	09.12.2022 से

शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा करने की पात्रता नहीं होगी।
3. निविदाकार एवं निर्माता को विगत 03 वर्षों राशि रु. 1.80 लाख का औसत टर्नओवर होना आवश्यक है।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य दीर्घा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र स्कैन कर अपलोड करना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		16.11.2022	17.30	16.11.2022	17.30	Release Tender
2		Bid Submission	16.11.2022	17.30	08.12.2022	17.30	
3	Tender Open		09.12.2022	10.30	--	--	



EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE


Name of work:- Additional work of Central Library

As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
	9.53	9.53 Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side having 12 mm air gap including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary								
			1	32.50	3.10		100.75			
							100.75	sqm	3159.00	318269.25
12	9.47	9.47 Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved								
		1 For fixed portion								
							250.00			
						Total	250.00	kg	331.00	82750.00
						=				
	2	For shutter of doors, windows & ventilators including providing and making					145.00	kg	338.00	49010.00
21	9.63	Providing and fixing clear float toughened glass door or partition in required thickness frameless in appropriated sizes inclusive of edge molding polish and making required size slot or hole for patch fitting/hardware etc. The glass to be assembled together with patch fitting and hardware								
		1. 12 mm thick for door/partition	2	1.5		2.1	6.30			
						Total	6.30	sqm	2560.00	16128.00

	9.64	Providing and fixing of stainless steel grade 316 patch fitting and hardware of approved (Hardwyn, Ozone, Godrej) make in frame less toughened glass door or partition in proper alignment with all tools tackles and labour etc complete.							
16	9.2	5. Corner patch fitting with pivot SS grade 304				2.00	nos	3058.00	6116.00
	22.3 electr	Supply, installation, testing & commissioning and putting into operation and final testing of automatic lift complete with ARD and all standard equipments, accessories and control equipments as per manufacturer's design and as per CPWD specification (Part III LIFTS) 1981 and fulfilling following requirements on turn key basis. A. Type : Passenger lift B. Load : 8 passenger/ 544 Kg C. Speed : 1.5 metre per second D. Control : AC2 E. Operation : Microprocessor based simplex collective selective with/without lift attendant F. Total rise : About 9 mtrs G. Landings : 4 All on same side H. Floors served : G, 1, 2, 3 I. Signals : Digital car position indicator, car travel direction indicator in car & at all landings							
						1.00	nos	1813579.00	1813579.00
		Add or deduct for providing all additional parts/ equipments or for enhancing the capacity of parts/ equipments in automatic lift for 8 persons, speed 1.5 m/sec for every additional floor beyond initial G+3 floors.				1.00	nos	94457.00	94457.00
	6.58	Supplying, installation, testing and commissioning of Acrylic LED light (a) Specification of Acrylic 3 mm thick x 3 " width x 4 " depth *(impose) (b) Specification of LED modules :- Each Module should have 6 Nos				80.00	sqf	2312.00	184960.00
TOTAL=									2565269.25
say rs.=									2565000.00


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)