



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

फा.क्र./22,23,24/निर्माण कोसाबाड़ी जोन/2022

कोरबा, दिनांक 19.05.2022

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 & Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 18.06.2022 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 18.06.2022 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 29 पोड़ीबहार में एस.एल. आर.एम. सेन्टर का मरम्मत एवं जिर्णोद्धार का कार्य। (मरम्मत एवं संधारण मद)	3,57,000/-	4,000/-	750/-	Form-A	02 माह	सक्षम श्रेणी	18.06.2022
2	वार्ड क्र. 31 मैग्जीन भट्ठा में एस.एल.आर.एम. सेन्टर का मरम्मत एवं जिर्णोद्धार का कार्य। (मरम्मत एवं संधारण मद)	3,50,000/-	4,000/-	750/-	Form-A	02 माह	सक्षम श्रेणी	18.06.2022
3	वार्ड क्र. 33 अंतर्गत रामपुर में एस.एल.आर.एम. सेन्टर का मरम्मत एवं जिर्णोद्धार का कार्य। (मरम्मत एवं संधारण मद)	3,35,000/-	4,000/-	750/-	Form-A	02 माह	सक्षम श्रेणी	18.06.2022

निविदा की शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोष में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।

6. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष साथ ही 5 प्रतिशत पृथक (मरम्मत एवं संधारण मद को छोड़कर) से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्क्यूरिटी के रूप में रोकी जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईंट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नवा रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।


(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE

Name of Work :- Maintenance And Renovation Of S.L.R.M Center ward no 29
 PODIBANAR

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

S.N	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	14.45	14.45 Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to scratches etc. complete								
		outer building	2	27.40		3.90	213.72			
			2	10.20		3.90	79.56			
			4	10.20		3.90	159.12			
			6	4.50		3.60	97.20			
			4	3.70		3.30	48.84			
			8	2.00		3.30	52.80			
			2	27.40		2.10	-115.08			
			1	10.20		2.10	-21.42			
						Total	514.74	sqm	5.20	2676.65
3	17.1	17.1 Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lea								
		17.1.1 Thickness upto 15mm								
			7	7.50	0.50		26.25			
			8	7.50	0.90		54.00			
			1	10.20	1.20		12.24			
						Total	92.49	Sqm	132.00	12208.68
4	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	3	Cement Mortar 1:5 (1 cement : 5 coarse sand)								
			1	13.50	0.20	0.40	1.08			
			3	7.10	0.20	0.40	1.70			
			5	2.50	0.20	0.40	1.00			
						Total	3.78	Cum	3350.00	12676.40
						=				


	5	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc								
a			2	28.00			56.00			
			2	35.00			70.00			
						Total =	126.00	Kg	67.50	8505.00
	11.2	Providing and making 12mm thick cement plaster of mix								
	4	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
			4	15.30	1.50		91.80			
			4	9.00	1.60		57.60			
						Total =	149.40	sqm	91.50	13670.10
6	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, JK wall putty) on walls to					414.74			
						Total =	414.74	sqm	94.50	39192.93
	14.1	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.					264.74	sqm	44.50	11780.93
	1	On new work (Two or more coats)								
	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:					350.00	sqm	56.00	19600.00
	1	On new work (Two or more coats)								

	30.13	Supply and fixing of pre-coated TILE PATTERN profile sheets of approved make, colour, over all size, corrugation shape and pitch, having total coated thickness (TCT) 0.45 mm (approx weight 4.9 kg/sqm) with Zn-Al coating and superior paint and having yield strength of 550 MPa. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I.								
			5	1.00	5.00		25.00	sqm	942.00	23550.00
	10.16	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws or with polymer coated J or L hooks, bolts and nuts and or G.I. seam bolts and nuts, G.I. plain and bitumen washers complete :					30.00	m	553.00	16590.00
	9.43	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete.								
		Aperture 75x75mm	5	9.50	1.50		71.25	sqm	291.00	20733.75

	6	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.										
			1	120.00			120.00	kg	66.00	7920.00		
	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.										
	5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).										
			1	20.00	1.50	0.10	3.00					
						Total =	3.00	Cum	4073.00	12219.00		
	12.65	12.65 Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 5MPa										
			1	20.00	1.20		24.00	sqm	632.00	15168.00		
	4.19	Finishing walls with water proofing cement paint of required shade to give an even shade.										
			2	27.40	1.80		98.64					
			2	15.00	1.80		54.00					
							152.64	sqm	41.00	6258.24		
	14.23	Painting on old work (one or more coats) to give an even shade with:										
	14.23.1	Satin synthetic enamel paint										
							245.00	Sqm	35.00	8575.00		
16	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a										
			4	1.20	1.20	15.20	87.55					
			2	0.90	2.10	21.50	81.27					
						Total	168.82	kg	75.00	12661.65		

		g.b Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
		etc. of stair cases including use of chequered plate wherever required, all complete.								
		@3.06kg/m								
		Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.					95.00	kg	70.00	6650.00
			3	1.80	1.80		9.72	SQM	692.00	6726.24
(A) Total=										257362.57
SANITATION WORK										
19.13		19.13 Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
		19.13.1 Bib cock (250 grams)					4.00	each	185.00	740.00
		19.13.2 Bib cock (350 grams)					4.00	each	237.00	948.00
(B) total=										1688.00
LED BOARD(C)										
6.58		Supplying, installation, testing and commissioning of Acrylic LED light (a) Specification of Acrylic 3 mm thick x 3 " width x 4 " depth *(imbose) (b) Specification of LED modules :- Each Moduel should have 6 Nos LED of 1 watt					21.50	sqf	2312.00	49708.00


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

of work :- Internal Electrification

per Schedule of rates public works department [PWD ELECTRICAL-01-06-2020] PART- B

S.N	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Wiring for light/ fan/ exhaust fan / call bell point with 3x1.5 sqmm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) with 5/6 amp piano type switch, phenolic laminated sheet, suitable size M.S. box etc as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	1	Short Point	10				10	Point	240.00	2400.00
	2	Medium Point	4				4	Point	376.00	1504.00
2	1.3	Extra for providing and fixing light plug point on board in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) point wiring with piano type 3 pin 5/6 amp socket outlet and 5/6 amp switch including cost of phenolic laminated sheet and M.S. box etc. as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)	1				1.00	Point	87.00	87.00
3	1.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	4.13.2	3 X 2.5 sq. mm in 20mm conduit	2	80.00			160.00	Metre	111.00	17760.00
4	6.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earthing etc. complete as required. P.F. should be greater than 0.9, with BEE Star rating from 3 star and above, IS: 374:2019 including all amendments.								
	3	1400 mm sweep	6				6	Each	1773.00	10638.00

5	Supplying, installation, testing and commissioning of following LED fitting (luminaries) Panel Light in round/ square shape complete with electronic driver heat sink capacitor and all other accessories on surface/ in false ceiling etc. as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio ≥ 100 lumens /watt.							
8.22.5	12 Watt	8			8.00	Each	588.00	4704.00
8.22.6	15 Watt	6			6.00	Each	679.00	4074.00
6	5.1	Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as per specification.						
	5.1.1	5/6 amps one way switch	1		1.00	Each	25.00	25.00
	5.1.4	15/16 amps switch	3		3.00	Each	59.00	177.00
	5.1.5	3 pin 5/6 amp socket outlet	3		3.00	Each	42.00	126.00
	5.1.6	6 pin 15/16 amp socket outlet	2		2.00	Each	73.00	146.00
	5.1.7	Plug Top 3 pin 5/6 Amps (For light plug).	2		2.00	Each	38.00	76.00
	5.1.8	Plug Top 3 pin 16 Amps (For power plug).	1		1.00	Each	51.00	51.00
	5.1.12	Fan regulator Electronic, step type moving all round	8		8.00	Each	130.00	1040.00
	5.1.13	Ceiling rose 3 pin 5 amps	2		2.00	Each	32.00	64.00
	5.1.15	Batten/ angle holder	16		16.00	Each	38.00	608.00
7	9.1	Providing and fixing following rating and breaking capacity MCCB in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as per specification, IS/ IEC: 60947-2 and Ics = 100 % Icu.						
	11.17.2	3 pole MCCB, 25-63A, Fixed Thermal Release, 10KA	3		3.00	Each	1483.00	4449.00
(D)TOTAL =								47929.00

A+B+C+D= 356687.57

SAY RS.= 357000.00

AB

[Signature]