



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

सर्वमंगला जोन

फा.क्र./705 से 709/निर्माण (सर्वमंगला जोन)/2022/

कोरबा, दिनांक 20.07.2022

निविदा आमंत्रण की सूचना

नगर पालिक निगम कोरबा द्वारा लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्यों हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 17.08.2022 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 17.08.2022 सायंकाल 4:30 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र 58 अंतर्गत ईमलीछापर चौक के समीप मंच एवं सागर मल घर से महावीर घर तक सी.सी.रोड का मरम्मत कार्य। (मरम्मत संधारण मद)	3,94,900/-	4000/-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.08.2022
2	वार्ड क्र 61 आदर्श नगर में सतसंग भवन का मरम्मत कार्य। (मरम्मत संधारण मद)	3,38,700/-	3500/-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.08.2022
3	वार्ड क्र. 58 अंतर्गत ईमलीछापर चौक में गौरह्ला घर के पास स्थित शोड एवं कमरा मरम्मत कार्य। (मरम्मत संधारण मद)	3,37,700/-	3500/-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.08.2022
4	वार्ड क्र. 56 अंतर्गत डगनियाखार के पंखादफाई क्षेत्र में स्थित कलवर्ट व नाली का मरम्मत कार्य। (मरम्मत संधारण मद)	2,92,500/-	3000/-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.08.2022
5	वार्ड क्र. 54 सर्वमंगला नगर के शांति मोहल्ला में सामुदायिक भवन का मरम्मत कार्य। (मरम्मत संधारण मद)	2,18,000/-	2200/-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.08.2022

निविदा की शर्तें:-

- निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथ-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा-
 (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित शपथ पत्र एवं निविदा प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।

5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकाना प्रमाण पत्र, पैन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एमआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमोंक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे— खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है, तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ. डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
17. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रवृत्ति के कार्यों को छोड़कर 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्क्यूरिटी के रूप में रोकੀ जावेगी। (मरम्मत संधारण मद के कार्यों को छोड़कर)
18. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
19. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
20. ईंट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
21. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
22. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
23. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
24. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट—

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


प्रतिलिपि :- प्रो.प्र.प्र. संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नवा रायपुर छ.ग. को [www. uad.cg.gov.in](http://www.uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

मोबाईल नं.—


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
DETAILED ESTIMATE

Name Of Work :- Maintenance Of Shed , Room At Near Gouraha Ghar Imlichhapar Chowk W.N. 58 (Marammat Sandharan Mad)

As Per SOR :- SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING - 01.01.2015] & [ELECTRICAL SOR]

S. N.	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
			1	12.00		15.00	180.00			
						Total	180.00	Sqm	7.20	1296.00
2	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
		Room :- Col	4	1.50	1.50	1.50	13.50			
		Wall	1	10.40	0.40	0.40	1.66			
		Step	1	1.80	1.10	0.40	0.79			
						Total	15.96	Cum	185.00	2951.86
3	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.					20.12	cum	65.00	1307.80
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		Col	4	1.50	1.50	0.10	0.90			
			1	4.20	3.60	0.20	3.02			
						Total	3.92	Cum	371.00	1455.80

5	1.19	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
			1	4.20	3.60	0.30	4.54			
						Total	4.54	Cum	242.00	1097.71
6	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								
		col	4	1.40	1.40	0.10	0.78			
		wall	1	15.60	0.40	0.08	0.50			
		Under Flooring	1	4.20	3.60	0.10	1.51			
		Step	1	1.80	1.10	0.10	0.20			
						Total	2.99	Cum	2659.00	7958.92
7	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			1	19.40	0.20	0.05	0.19			
			1	8.00	3.60	0.12	3.46			
						Total	3.65	Cum	4073.00	14866.45
8	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		Col	4	1.30	1.30	0.40	2.70			
			4	0.20	0.30	1.20	0.29			
			4	0.20	0.30	3.00	0.72			
		Plinth Beam	1	16.40	0.20	0.30	0.98			
		Lintel Beam	1	16.40	0.20	0.20	0.66			
		Chhajja	1	4.20	0.50	0.09	0.19			
		Slab Beam	1	16.40	0.20	0.20	0.66			
		Slab	1	5.20	4.30	0.12	2.68			
						Total	8.88	Cum	4163.00	36968.27

			1	19.00		0.12	2.28			
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)				Total	2.28	metre	34.00	77.52
			1	5.20		Total	22.36			
13	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				Total	22.36	sqm	235.00	5254.60
	5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)								
		Shed	1	15.60	0.30	0.70	3.28			
			1	15.60	0.20	3.00	9.36			
			1	1.80	1.00	0.40	0.72			
			1	1.80	0.70	0.20	0.25			
			1	1.80	0.40	0.20	0.14			
						Total	13.75			
		Deduction---								
			1	1.00	0.20	2.10	0.42			
			1	1.20	0.20	1.20	0.29			
						Total	0.71			
						Total	13.04	cum	3350.00	43697.40
14	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:					9.67	Cum	121.00	1170.07
15	9.13	Providing and fixing steel door/window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.					30.00	Kg	75.00	2250.00
16	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.					80.00	Kg	67.50	5400.00

17	9.16	Providing and fixing M.S. frames of doors, windows, ventilators and rainboards joints mitred and welded with 15x3 mm lugs 10cm long embedded in cement concrete blocks 15x10x10cm of grade M-10 or with wooden plugs and screws or with dash fastener or rawl plugs and screws or with fixing clips or with bolts and nuts as required including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer.								
	16.2	Angle-iron frames				50.00	Kg	73.50		3675.00
18	11.1	Providing and making 6mm thick cement plaster of mix:								
	1.2	a) Cement mortar 1:4 (1 cement : 4 fine sand)				28.70	sqm	87.00		2496.90
19	11.2	Providing and making 12mm thick cement plaster of mix:								
	2.3	b) Cement Mortar 1:5 (1 cement : 5 fine sand)				65.20	sqm	96.50		6291.80
20	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	3.3	b) Cement Mortar 1:5 (1 cement : 5 fine sand)				65.20	Sqm	113.00		7367.60
21	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Asteck Super fine W/R of (NCL), Vcon, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.				121.20	Sqm	94.50		11453.40
22	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.								
	14.1	on new work (Two or more coats applied @ 134 kg/10 sqm)				65.20	Sqm	41.00		2673.20
23	14.9	Distemper with acrylic washable distemper to give an even shade								
	9.1	on new Work (Two or more coats)				56.24	sqm	38.00		2137.12
24	14.22	Painting on new work (two or more coats) to give an even shade with								
	22.1	on synthetic enamel paint								
			1	2.00	1.00	2.10	4.20			
			2	1.20		1.20	2.88			
			4	0.60		0.30	0.72			
						Total	7.80	Sqm	55.00	429.00

25	18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.									
	76.2	100 mm dia pipe.	2	4.00			8.00	Metre	267.00		2136.00
26	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (1/2-10mm).									
	13.1	Size 600x600mm	1	4.20		3.60	15.12				
			1	15.60		0.30	4.68				
						Total	19.80	Sqm	1151.00		22789.80
27	12.65	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 300 sqcm) and shape/ pattern, over 100mm thick average complete coarse sand bed with joints of 2mm thick filled by fines and including leveling									
	65.2	Precast interlocking (rubber mould) precast interlock concrete blocks									
			1	10.00		10.00	100.00				
						Total	100.00	Sqm	632.00		63200.00
28	14.23	Painting of old work (one or more coats) to give an even shade with:									
	23.1	Synthetic enamel paint									
			1	1.50	5.00	2.40	18.00				
						Total	18.00	Sqm	35.00		630.00
29	11.14	Brushing walls with water proofing cement paint of required shade to give an even shade.									
	14.2	Oil based (one or more coats) (1/2-20 kg/10 sqm)					68.00	Sqm	25.00		1700.00
30	14.9	Prepasting with acrylic wall paper temper to give an even shade									
	9.2	Oil based (one or more coats)					82.00	Sqm	17.50		1435.00

31	14.15	Removing dry or oil bound disinfectant by scraping sand paper and preparing the surfaces smooth including necessary repair to scratches etc. complete.										
									150.00	Sqm	5.20	780.00
32	14.16	Removing old paint or polish by using remover or blow lamp or any other means approved including preparing the surface smooth after removing the paint										
				1.50	5.00	2.40	18.00					
						Total	18.00	Sqm			32.50	585.00

ELECTRICAL PART

33	6.1	Supplying, installation testing and commissioning of following size exhaust fan including wiring										
	1.3	300mm Sweep										
							2.00	each	1697.00			3394.00
34	5.9	Providing and fixing round/ hexagonal fan box with 12mm dia steel bar hood					1.00	each	42.00			42.00
35	6.12	Providing and fixing phenolic laminated sheet cover of 180 mm dia 3mm thick on the fan box etc.					1.00	each	56.00			56.00
36	6.6	Supplying, installation testing and commissioning of following size heavy duty 1440 rpm exhaust fan in										
	6.1	300mm sweep					1.00	each	2446.00			2446.00
37	6.16	Supplying, installation testing and commissioning of following sleek LED Panel down lighters										
	16.2	30 watt, size 600 x 600mm										
							2.00	each	2342.00			4684.00
38	6.15	Supplying, installation testing and commissioning of following sleek LED fitting square shape										
	15.6	18 watt										
							2.00	each	868.00			1736.00
39	6.19	Supplying, installation testing and commissioning of following sleek LED tube light fitting including bracket with electronic driver heat sink										
	19.4	30 watt (4feet)										
							1.00	each	718.00			718.00

40	32.79.1	Supplying of following LED Bulk head complete with electronic driver heat sink Capacitor 10 watt										
								1.00	each	1012.00		1012.00
41	1.7	Wiring for light/ fan/ exhaust fan/ call bell point with 3x1.5 sq mm FRLS PVC										
	1.7.1	Switch Point						2.00	Point	266.00		532.00
	1.7.2	Maximum Point						2.00	Point	424.00		848.00
	1.7.3	Light Point						2.00	Point	588.00		1176.00
42	1.10	Wiring for light Plug point with 3x1.5 sq mm FRLS PVC insulated copper conductor wire for phase, neutral and earth in concealed										
	10.1	Switch Point						1.00	Point	442.00		442.00
	10.2	Maximum Point						1.00	Point	659.00		659.00
	10.3	Light Point						1.00	Point	922.00		922.00
43	1.12	Wiring for power Plug point with 3x1.5 sq mm FRLS PVC insulated copper conductor wire for phase, neutral and earth in concealed										
	12.2	Maximum Point						1.00	Point	1171.00		1171.00
	12.3	Light Point						1.00	Point	1705.00		1705.00
44	1.13	Wiring for circuit / sub main wiring along with earth wire with the following sizes of FRLS PVC										
	13.1	1.5 sq. mm in 20mm conduit						10.00	metre	92.00		920.00
	13.3	3 sq. mm in 20mm conduit						8.00	metre	172.00		1376.00
	13.6	3 sq. mm in 25mm conduit						12.00	metre	145.00		1740.00
	13.1	6 sq. mm in 40mm conduit						7.00	metre	515.00		3605.00
45	1.15	Supplying and fixing of following size FRLS PVC conduit along with accessories in concealed complete as per specification										
	15.1	20mm						15.00	metre	42.00		630.00
	15.2	25mm						12.00	metre	53.00		636.00
46	3.14	Supplying and drawing UTP 4 pair category LAN wire in existing surface						3.00	metre	19.00		57.00
47	9.11	Supplying and fixing SP MCB 240 amp MCB Curve suitable for inductive load in the existing MCB DB complete with connection										
	11.2	240 to 32 amp						2.00	each	148.00		296.00

6.61	Specification and installation of angle iron including angle size 40 x 5mm thick with specification					1.00	kg	66.00	66.00
------	--	--	--	--	--	------	----	-------	-------


As per Estimate Amount Rs.

337666.50

Say Rs.

337,700/-

Sd/-
Nagar Palik Nigam



Astt. Engr
Nagar Palik Nigam
Korba

