



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

परिवहन नगर जोन

फा.क्र./45,46 एवं 47/निर्माण (टी.पी. नगर जोन)/2021/

कोरबा, दिनांक 01.10.2021

निविदा आमंत्रण की सूचना

लोक नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग, से एकीकृत पंजीयन अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु कार्य क्र. 01 एवं 03 प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान प्रतिशत दरों पर तथा कार्य क्र. 02 शेड्यूल अनुसार आयटम दरो पर मैनुअल निविदा फार्म "ए एवं बी" वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति के माध्यम से मुहरबंद निविदाएं आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 21.10.2021 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 23.10.2021 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 02 गेवराघाट के आंगनवाडी के पास स्थित बाऊण्डीवाल के अन्दर ओपन जिम प्रदाय एवं स्थापना कार्य। आईटम दर पर (एल्डरमेन मद)	6,00,000/-	4,500/-	750/-	Form-B	04 माह	सक्षम श्रेणी	23.10.2021
2	वार्ड क्र. 14 पंप हाउस आत्मानंद स्कूल के पास दुर्गा पण्डाल का द्वार परिवर्तन एवं विकास कार्य तथा विभिन्न स्थान के मंचों में एस.एस.रेलिंग का कार्य एवं पानी टंकी के समीप स्थित सामुदायिक भवन में विकास कार्य। (एल्डरमेन मद)	5,50,000/-	4,125/-	750/-	Form-A	04 माह	सक्षम श्रेणी	23.10.2021
3	वार्ड क्र. 15 ढोढीपारा में सी.सी. रोड एवं नाली का निर्माण कार्य। (पार्षद मद 2021)	7,00,000/-	5,250/-	750/-	Form-A	04 माह	सक्षम श्रेणी	23.10.2021

निविदा की शर्त:-


1. निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं. -495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा

4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनों लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र, पेन नम्बर, शपथ पत्र, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) के अनुरूप प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही कंडिका क्र. 01 से 03 तक के लिए 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईंट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।

23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।
24. निविदाकार द्वारा आपूर्ति किये जाने वाले सामाग्री के निर्माता/कंपनी/फर्म द्वारा अधिकृत विक्रेता/डीलरशीप प्रमाण पत्र प्रस्तुत करना होगा।
25. निविदाकार द्वारा जिस निर्माता कंपनी के आयटम प्रदाय करने हेतु दर प्रस्तुत की जा रही है, उन्हे उस कम्पनी का आई एस.ओ. सर्टिफिकेट संलग्न करना अनिवार्य होगा अन्यथा निविदाकार इस निविदा के लिए अपात्र होगा।
26. निविदाकार आपूर्ति किये जाने वाले प्रत्येक जिम सामाग्रियों की कम्पनी का आयटम कैटलॉग जिसमें उस सामाग्री की समस्त तकनीकी जानकारी स्पष्ट रूप से विनिर्दिष्ट हो प्रस्तुत किया जाना अनिवार्य होगा।
27. निविदाकार को आपूर्ति किये जाने वाली सामाग्री से संबंधित यथा आपूर्ति किये जाने वाले सामाग्री के निर्माण कर्ता/कम्पनी/फर्म द्वारा जारी अधिकृत विक्रेता/डीलरशीप प्रमाण पत्र आयटम कैटलॉग एवं आई.एस.ओ. एक ही कंपनी का होना अनिवार्य है।
28. निविदाकार के पास अधिकृत विक्रेता/डीलरशीप फर्म कंपनी में उत्पादों का पूर्व में किसी शासकीय संस्था में प्रदान किये जाने संबंधी कार्यादेश प्रमाण पत्र एवं अनुभव प्रमाण पत्र प्रस्तुत करना होगा साथ ही यह भी सुनिश्चित करना होगा की उपरोक्त प्रमाण पत्र कार्यालय अभियंता अथवा प्रवर श्रेणी के अधिकारी द्वारा जारी किया गया हो प्रस्तुत करना अनिवार्य होगा।

नोट:-


1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

कोरबा, दिनांक

फा.क. /निर्माण टी.पी. नगर जोन/2021/
प्रतिलिपि :-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, मंत्रालय, अटल नगर नया रायपुर (छ.ग.) को
uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।


कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

ABSTRACT

Neser Atmanand school

Name of Work : MAINTENANCE AND CHANGE FACE (GATE) OF DURGA PANDAL & DEVELOPMENT OF COMMUNITY BUILDING & SS
FIXING WORK IN VARIOUS MANCH AT PUMP HOUSE WARD NO -14 R
 As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.				
	3.3	In cement mortar.	cum	8.54	263.00	2,246.02
2	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	13.1	1:4:8 or leaner mix	cum	4.92	329.00	1,618.68
3	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	20.88	185.00	3,862.80
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moonum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	12.3	371.00	4,563.30
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	3.18	2659.00	8,455.62
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	2.59	4073.00	10,549.07
6	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	20.06	3263.00	65,455.78
7	11.2	Providing and making 12mm thick cement plaster of mix.				
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	82.54	91.50	7,552.41
8	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	50.84	107.00	5,439.88
9	12.12	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	sqm	49.56	963.00	47,726.28
10	14.10	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.				
	10.1	On new work (two or more coats)	sqm	225.6	44.50	10,039.20
11	14.12	Applying one coat of cement primer on wall surface (applied @ 0.80 litres/10 sqm) complete.	sqm	509.6	23.00	11,720.80
12	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	265	94.50	25,042.50
13	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	284	41.00	11,644.00
14	14.22	Painting on new work (two or more coats) to give an even shade with:				


S.N.	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		Satin synthetic enamel paint	sqm	60	55.00	3,300.00
15	12.6	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm				
	55.2	Pigment Coloured (rubber mould) precast interlock concrete blocks	sqm	124	632.00	78,368.00
16	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	190	67.50	12,825.00
17	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	8.00	65.00	520.00
18	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	0.24	4163.00	999.12
19	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	20.00	54.50	1,090.00
20	9.3	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.				
	3.1	Electric resistance or induction butt welded tubes Grade-250	kg	106.08	88.50	9,388.08
21	10.11	Supply and fixing of pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm	13.50	636.00	8,586.00
22	10.10	Extra for providing and fixing wind ties of 40x6mm flat iron section.	metre	8.00	118.00	944.00
23	11.5	Neat Cement punning.	sqm	22.50	33.00	742.50
24	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.1	Size upto 200x300mm	sqm	24.10	587.00	14,146.70

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
25	9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.			
	9.1	Size 300x300mm	sqm	10.00	692.00
26	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. INTERNAL WORK - EXPOSED ON WALL			
	4.2	20 mm nominal outer dia Pipes.	metre	30.00	151.00
	4.3	25 mm nominal outer dia Pipes.	metre	50.00	199.00
27	19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:			
	13.1	Bib cock (250 grams)	each	5.00	185.00
	13.2	Bib cock (350 grams)	each	7.00	237.00
28	19.18	Providing and fixing gun metal non- return valve (horizontal type) of approved quality (screwed end) :			
	18.1	25 mm nominal bore	each	2.00	413.00
29	19.42	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	LTR	1000.00	7.30
30	19.6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. This included jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. EXTERNAL WORK			
	6.8	75 mm nominal inner dia pipes	metre	2.00	1682.00
31	19.15	Providing and fixing stainless steel drain jali of approved make/quality.	each	2.00	51.00
32	9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.			
	57.2	SS Grade 304	kg	319.60	525.00

As per Estimate Amount Rs. 550191.74

SAY R.S. 5,50,000=00


Sd/- Engineer
Nagar Palik Nigam
Korba (C.G.)


Asstt. Engineer
Nagar Palik Nigam
Korba (C.G.)