



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

कोरबा जोन

फा.क्र./24 एवं 25/निर्माण (कोरबा जोन)/2021/

कोरबा, दिनांक 30.01.2021

## निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 25.02.2021 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 25.02.2021 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 06 में ईतवारी बाजार के समीप शौचालय का निर्माण कार्य। (पार्षद निधि वर्ष 2019-20)	3,92,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	25.02.2021
2	वार्ड क्र. 12 स्थित दुर्गा पण्डाल एवं शेड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,80,300/-	3,900/-	750/-	Form-A	03 माह	सक्षम श्रेणी	25.02.2021

### निविदा की शर्तें:-

1. निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. चौक, साकेत भवन कोरबा, जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनोंक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
  - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
  - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
  - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होंगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।

क्रमशः.....02

8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई. सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी। मरम्मत कार्य हेतु परफार्मेंस गारंटी की राशि नहीं काटी जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में प्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

मोबाईल नं.- .....

कार्यपालन अभिज्ञता  
नगर पालिक निगम  
कोरबा (छ.ग.)

5

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of work:- Construction Of Urinal Near Itwari Market At Ward No - 06  
(Parsad Fund)

As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S.N.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT		
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated										
			1	In all types of soil								
				column	6	1.20	1.20	1.20	10.37			
				wall	2	9.00	0.40	0.30	2.16			
					5	2.60	0.40	0.30	1.56			
				paverblock	2	15.00	1.00	0.20	6.00			
			2	6.00	1.50	0.20	3.60					
							Total=	23.69	Cum	185.00	4382.28	
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming										
					6	1.20	1.20	0.10	0.86			
									Total=	0.86	Cum	371.00
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level										
			3	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal								
				column	6	1.20	1.20	0.10	0.86			
				wall	2	9.00	0.40	0.10	0.72			
					5	2.60	0.40	0.10	0.52			
					1	9.00	2.60	0.10	2.34			
				paverblock	2	15.00	1.00	0.15	4.50			
		2	6.00	1.50	0.15	2.70						
							Total=	11.64	Cum	2659.00	30961.40	

4	2.1	Providing and fixing form work including centring, shuttering, setting, staging, propping bracing etc. complete and including removal at all levels, for:								
	1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below column below plinth	24	0.20	0.90		4.32			
		plinth beam	2	9.00	0.20		3.60			
			5	2.60	0.20		2.60			
			10	0.80	0.70		5.60			
						Total=	16.12	Sqm	139.00	2240.68
	5	Columns, Pillars, Piers and likes- rectangular or square in shape								
		column above plinth	24	0.20		2.10	10.08			
						Total=	10.08	sqm	297.00	2993.76
5	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each								
							23.69			
						Total=	23.69	Cum	65.00	1539.72
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth								
	1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal								
		raft	6	1.20	1.20	0.25	2.16			
		below plinth	6	0.20	0.20	0.90	0.22			
		plinth beam	2	9.00	0.20	0.20	0.72			
			5	2.60	0.20	0.20	0.52			
		column above plinth	6	0.20	0.20	2.10	0.50			
		for tank	4	0.20	0.20	2.10	0.34			
			1	5.00	2.00	0.20	2.00			
						Total=	6.46	Cum	4163.00	26876.33
7	3.4	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition					0.00	Cum	97.50	


37


8	12	Providing and placing in position reinforcement for R.C. work including straightening, cutting, bending, binding etc. complete as per drawings								
	1	Thermo-Mechanically treated								
			1	100	6.46		645.60			
							Total=	645.60	kg	54.50 35185.20
9	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in								
	3	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
			2	9.00	0.20	0.80	2.88			
			5	2.60	0.20	0.80	2.08			
			2	9.00	0.20	1.80	6.48			
			5	2.60	0.20	1.80	4.68			
			10	0.60	0.10	0.60	0.36			
			2	15.00	0.20	0.50	3.00			
			2	5.00	0.20	0.50	1.00			
							Total=	20.48	Cum	3263.00 66826.24
10	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.								
	2	Size above 200x300mm								
			4	2.60		2.10	21.84			
			4	1.50		2.10	12.60			
			1	8.40		2.10	17.64			
			2	9.00		2.50	45.00			
			2	2.60		2.50	13.00			
			6	1.00		2.10	12.60			
			10	1.00		1.00	10.00			
							Total=	132.68	sqm	587.00 77883.16

	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including								
	1	Size 300x300mm	2	4.50	2.60		23.40			
			2	4.50	1.00		9.00			
						Total=	32.40	sqm	692.00	22420.80
12	12.65	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm								
		paverblock	2	15.00	1.00		30.00			
			2	6.00	1.50		18.00			
						Total=	48.00	sqm	632.00	30336.00
13	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level								
	5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal								
			2	15.00	0.20	0.20	1.20			
			2	6.00	0.20	0.20	0.48			
			2	9.00	0.60	0.20	2.16			
						Total=	3.84	Cum	4073.00	15640.32

19

8.149	Providing and fixing factory made PVC door shutters of specified thickness made of styles and rails of PVC hollow section of specified size 59x24 mm and wall thickness 2 mm ± 0.2 mm with inbuilt edging on both sides. The styles and rails mitred and joined at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws.								
2	8.149.1 24 mm thick door	2	0.90	2.00		3.60			
					Total=	3.60	sqm	2399.00	8636.40
								TOTAL=	326242.83

  
 Asstt. Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)

**PART - B - SANITATION WORK**

18.76	Providing and fixing on wall face UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.								
1	75 mm dia pipe.	1	24.00			24.00	metre	182.00	4368.00
2	110 mm dia pipe.	1	20.00			20.00	metre	267.00	5340.00
2	18.17 Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :					2	each	1430.00	2860.00
1	White Size 550x450 mm								
3	18.77 Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.								
1	Tee/ Tee with door/ Bend 45°/ Bend 90°								
1	75 mm					2.00	each	113.00	226.00
2	110 mm					10.00	each	154.00	1540.00
3	Vent cover								
1	75 mm					4.00	each	34.00	136.00
6	Nahani trap 110x75mm					6.00	each	90.50	543.00




	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent								
	1	15 mm nominal outer dia .Pipes.				50.00	metre	110.00	5500.00	
	3	25 mm nominal outer dia .Pipes.				30.00	metre	199.00	5970.00	
	4	32 mm nominal outer dia .Pipes.				25.00	metre	271.00	6775.00	
5	19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:								
	6	Stop cock (concealed) (600 grams)				12.00	each	494.00	5928.00	
	4	Pillar Cock (400 grams)				2.00	each	398.00	796.00	
6	19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
	1	Bib cock (400 grams)				6.00	each	382.00	2292.00	
7	19.15	Providing and fixing stainless steel drain jali of approved make/quality.				4.00	each	51.00	204.00	
8	19.16	Providing and fixing brass/gun metal gate valve with C.I. wheel of approved quality (screwed end):								
	1	25 mm nominal bore				5.00	each	436.00	2180.00	
	2	32 mm nominal bore.				5.00	each	510.00	2550.00	
9	18.13	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:								
		Wall corner type urinal of				3.00	each	1659.00	4977.00	


10	18.15	Providing and fixing one piece construction white vitreous squearing plate urinal with an integral rim longitudinal flushing pipe, standard size G.I. flush pipe for back and front flush, C.P. brass								
						3.00	each	2014.00	6042.00	
11	19.42	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and making necessary holes for inlet,				1000.00	litre	7.30	7300.00	
TOTAL =									65527.00	

Part A 326242.83

391769.83

**Say Rs.= 392000.00**

  
Asstt. Engineer  
Municipal Corporation  
Korba (C.G.)

  
Sub Engineer  
Municipal Corporation  
Korba (C.G.)