



# कार्यालय नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क्र./95 से 97, 100,102, 106 से 107 एवं 110 से 111/सर्वमंगला नगर जोन/2019/

कोरबा दिनांक 16.08.2019

## निविदा आमंत्रण सूचना

लोक निर्माण विभाग द्वारा एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग (भवन), रायपुर द्वारा 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर मुहरबंद निविदाएं आमंत्रित की जाती हैं।

क्र.	कार्य का नाम	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने हेतु आवेदन जमा करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की तिथि
1	वार्ड क. 54 बरमपुर बस्ती में सी.सी. रोड एवं नाली का मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	3,96,500/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
2	वार्ड क. 54 आजाद नगर में शासकीय प्राथमिक स्कूल का मेंटेनेंस कार्य (मरम्मत संधारण मद) प्रथम निविदा	3,95,000/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
3	वार्ड क. 54 मंझवार मोहल्ला में नाली एवं बरमुपर में मंच का मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	3,81,000/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
4	वार्ड क. 57 गैराताल में सी.सी. रोड एवं नाली का मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	3,95,100/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
5	वार्ड क. 58 के निचले बस्ती में सी. सी. रोड एवं नाली का मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	3,97,500/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
6	वार्ड क. 61 आदर्श नगर कुसमुण्डा के कम्युनिटी सेन्टर मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	3,95,500/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
7	वार्ड क. 61 गोवरा बस्ती में सी.सी. रोड एवं नाली का मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	3,93,500/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
8	वार्ड क. 62 कुवैना बस्ती में सी.सी. रोड एवं नाली का मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	3,96,200/-	4,000/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19
9	वार्ड क. 62 कुवैना बस्ती के मंच का मेंटेनेंस कार्य। (मरम्मत संधारण मद) प्रथम निविदा	2,27,000/-	2,500/-	750/-	03 माह	डी. एवं प्रवर श्रेणी	28.08.19	30.08.19	07.09.19


### शर्तें:-

- निविदा दरें प्रचलित एस.ओ.आर से कम या अधिक प्रतिशत दरों पर दिया जावें, सी.एस.आर. के अंतर्गत के आईटमों पर पृथक से आईटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय से उपरोक्त कार्य हेतु नाम के सम्मुख अंकित राशि नगद जमा कर उपर लिखित तिथि को सौर्य 5.30 बजे तक अवकाश के दिन को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो रु. 50.00 अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किये जावेंगे। निर्धारित तिथि को सौर्य 3.00 बजे के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो, उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने के इच्छुक ठेकेदारों को आवेदन के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनर शीप डीड ) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले

- की जानकारी, पिछले वित्तीय वर्ष का आयकर प्रमाण पत्र, पेनकार्ड नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन का पंजीयन प्रमाणपत्र, कर्मचारी राज्य बीमा संगठन का पंजीयन प्रमाणपत्र तथा प्रशिक्षित अभियंता नियुक्त करने संबंधी प्रमाण पत्र, वर्तमान में संचालित निर्माण कार्य की जानकारी का नोटरी द्वारा सत्यापित शपथपत्र एवं अमानत राशि का एफ.डी.आर./टी.डी.आर./नगद जमा की रसीद संलग्न करना अनिवार्य होगा, अन्यथा निविदा प्रपत्र जारी नहीं किया जा सकेगा।
6. निविदा प्रपत्र उन्ही ठेकेदारों को दिया जावेगा, जिन्हें इस प्रकार के कार्यों का अनुभव हो।
  7. पूर्ण रूप से भरे निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती हैं और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहें तो उनके समक्ष खोली जावेगी।
  8. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयकों के साथ काटी जावेगी जो कार्यपूर्णता के दिनांक से 01 वर्ष के लिये रोव जावेगी तथा 5 प्रतिशत राशि पृथक से 3 वर्ष की परफॉरमेंस गारंटी के रूप में सिक्यूरिटी के रूप में रोकी जावेगी।
  9. आवेदन के साथ रु 10.00 लाख या उससे अधिक लागत के निर्माण कार्यों की निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार ( नियोजन एवं सेवा शर्तों का विनिमय ) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत पंजीयन करना आवश्यक होगा।
  10. छ.ग. भवन और अन्य सन्निर्माण कर्मकार ( नियोजन एवं सेवा शर्तों का विनिमय) अधिनियम,1996 के तहत निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
  11. ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
  12. निविदा प्रपत्र अहस्तान्तरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
  13. निविदा दरें एस.ओ.आर. से असामान्य होने पर सफल निविदाकार से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के रूप में समतुल्य परफारमेंस गारंटी राष्ट्रीयकृत बैंक द्वारा जारी एफ.डी.आर./पोस्ट ऑफिस का टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम पर देय होगा, उसे मांग तिथि से 07 दिवस के भीतर जमा कराना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा निरस्त की जावेगी।
  14. निविदा के संबंध में किसी भी प्रकार के विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
  15. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम,कोरबा के पास सुरक्षित रहेगा।
  16. ठेकेदारों को उपरोक्त कार्य में नियोजित किये गये श्रमिकों का भुगतान उनके बैंक खातों के माध्यम से किया जाना अनिवार्य होगा।
  17. उपरोक्त निविदा सूचना की विस्तृत जानकारी नगर पालिक निगम, कोरबा की वेबसाइट [www.korbamunicipal.in](http://www.korbamunicipal.in) के साथ ही समाचार पत्रों में भी इस टेन्डर का प्रकाशन देखा जा सकता है।

**नोट :-**

1. उपरोक्त निविदा तिथियों में कोई शासकीय अथवा स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय/स्थान माना जावे।
2. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर./अथवा नगद जमा राशि की रसीद आवेदन के साथ ही स्वीकार किये जावेंगे। जो कि आयुक्त नगर पालिक निगम,कोरबा के नाम पर देय होगा।

  
 कार्यपालन अभियंता  
 नगर पालिक निगम  
 कोरबा (छ.ग.)

**OFFICE OF THE NAGAR PALIK NIGAM, KORBA ( C.G.)**

**DETAILED ESTIMATE**

Name of work : MAINTANANCE OF GOVT PRYMARY SCHOOL AT AJAD NAGAR WARD NO54

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	16.26	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.								
			2				2.00			
						<b>Total</b>	2.00	each	100.00	200.00
2	16.27	Dismantling windows chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead..								
			2x3				6.00			
						<b>Total</b>	6.00	each	66.50	399.00
3	14.45	Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to scratches etc. complete.								
			2X2	6.30		3.10	78.12			
			2X2	4.60		3.10	57.04			
			2	6.30	4.60		57.96			
		-OUTER	2	14.00		3.80	106.40			
			2	5.00		3.80	38.00			
		-CHAJJA	2	14.00		0.70	19.60			
			1	24.00		0.70	16.80			
			2X2	3.00		3.00	36.00			
						<b>Total</b>	409.92	sqm	5.20	2131.58
4	16.37	Dismantling lime/ cement plaster or skirting at any height raking out joints and cleaning the surface for plaster including disposal of rubbish within 50 metres								

	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
	lead.									
		10	2.50	2.00		50.00				
		10	2.00		3.00	60.00				
		5	1.50	2.50		18.75				
						<b>Total</b>	128.75	sqm	11.00	1416.25
5	16.43									
	Demolishing cement concrete including disposal of material within 50 metre lead.									
	43.1									
	1:4:8 or leaner mix									
		2	6.30	4.60		57.96				
						<b>Total</b>	57.96	cum	329.00	19068.84
6	17.1									
	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :									
	1.1									
	Thickness upto 15mm									
		15	2.50	2.50		93.75				
						<b>Total</b>	93.75	sqm	132.00	12375.00
7	3.1									
	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.									
	1.3									
	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).									
		2	6.30	4.60	0.08	4.34				
						<b>Total</b>	4.34	cum	2970.00	12889.80
	1.5									
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm									


	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	nominal size).								
		1	13.00	4.60	0.13	7.77			
		1	16.00	7.50	0.08	9.60			
					<b>Total</b>	17.37	cum	4073.00	70748.01
8	3.14 Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.					40.00	kg	43.50	1740.00
9	12.12 Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.								
		2	6.50	4.80		62.40			
		1	44.00		0.15	6.60			
					<b>Total</b>	69.00	sqm	963.00	66447.00
10	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					409.92	sqm	94.50	38737.44
11	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								


REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		2	14.00		4.40	123.20			
		2	4.90		4.40	43.12			
		2	14.00	0.60		16.80			
					<b>Total</b>	183.12	sqm	56.00	10254.72
12	14.9	Distempering with acrylic washable distemper to give an even shade.							
	9.1	On new work (Two or more coats)							
		2x2	6.30		2.20	55.44			
		2x2	4.60		2.20	40.48			
		2	6.30	4.60		57.96			
					<b>Total</b>	153.88	sqm	38.00	5847.44
13	14.23	Painting on old work (one or more coats) to give an even shade with:							
	23.1	Satin synthetic enamel paint							
		3X2x2	1.20		1.20	17.28			
		3x2	1.00		2.10	12.60			
		2x4x2	0.45		0.45	3.24			
					<b>Total</b>	33.12	sqm	35.00	1159.20
14	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.							
	6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.							
						185.00	Kg	68.00	12580.00
15	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.							
						350.00	kg	75.00	26250.00
16	9.2	Structural steel work riveted or bolted or welded in built-up							


ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.					600.00			
				<b>Total</b>	600.00	Kg	66.00	39600.00
17 10.12 Supply and fixing of polymer precoated galvalume profile sheets (PPGL) of approved size, shape and pitch of corrugation, total coated thickness (TCT) 0.60 mm +/- 5%, epoxy primer on both side of the sheet and colour polyester top coat 18-20 microns and 6-7 microns on bottom. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses	1	14.00	7.50		105.00	sqm	693.00	72765.00

ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
and including cutting to size and shape wherever required.								

As per Estimate Amount Rs. 394609.27  
 Say Rs. 395000-00

  
 Sub Engineer  
 Nagar Palik Nigam  
 Korba (C.G.)

  
 Aast. Engineer  
 Nagar Palik Nigam  
 Korba (C.G.)

  
 E.E. Engineer  
 Nagar Palik Nigam  
 Korba (C.G.)