



कार्यालय नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क./311 /दर्री जोन/2019-20/

कोरबा दिनांक 21.10.2019

निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरो पर तथा शेड्यूल अनुसार आईटम दरों पर मैन्युअल निविदा वेब साईट से डाउनलोड कर त्रि-लिफाफा पद्धति के माध्यम से निविदा आमंत्रित की जाती है।

- 01 निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 21.11.2019 सायंकाल 3:00 बजे तक
- 02 निविदा खुलने की अंतिम तिथि - 21.11.2019 सायंकाल 4:00 बजे तक

क.	कार्य का नाम	प्राक्कलन राशि	घरोहर राशि	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क्र.52 अंतर्गत नगोईखार व फटीलाईजर सामुदायिक भवन का संधारण एवं भवन में नयी सुविधाओं की व्यवस्था बाबत। (पार्षद मद 2019-20)	7,00,000/-	7,000/-	750/-	Form-A	02 माह	सक्षम श्रेणी	21-11-19

निविदा की शर्तें :-

- निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक प्रतिशत दरों पर दिया जावें, सी.एस.आर. के अंतर्गत के आईटमो पर पृथक से आईटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथो - हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमो यथा कोरियर, सर्विस,साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा प्रपत्र आयुक्त नगर पालिक निगम,साकेत भवन आई.टी.आई.चौक कोरबा, जिला - कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम,कोरबा के वेबसाईट WWW.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form- A/B/ABC (जारी दिनांक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि- लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा :-
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र,आयकर चुकता प्रमाण पत्र,निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर.जो कि आयुक्त नगर पालिक निगम,कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा निविदा प्रपत्र होगा।
(स) तृतीय लिफाफे में उपरोक्त दोनो लिफाफे होंगे तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम,(साड़ा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साड़ा) के हित के विरुद्ध कार्य किया गया हो उनहे निविदा भरने की प्राप्ति नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनर शीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची,उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर प्रमाण पत्र/पैन नम्बर जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र,कर्मचारी भविष्य निधि संगठन,कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एन.आई.टी.) हस्ताक्षर युक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र.04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक,निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
- निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
- निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
- निर्धारित प्रारूप में निविदा प्रपत्र,निविदा प्रपत्र शुल्क ,अमानत राशि , निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाये जाने पर ही निविदा दर संबंधित लिफाफा खोला जावेगा,अन्यथा निविदा निरस्त कर दी जावेगी।
- ठेकेदार को अपनी दरे शब्दों एवं अंकों में लिखना अनिवार्य होगा।
- शासन के विभिन्न विभागों जैसे :- खनिज विभाग,श्रम विभाग,समाज कल्याण विभाग,इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों /आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
- ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्राक्धान के अंतर्गत कार्यवाही की जावेगी।
- कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई. सी.द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी संपूर्ण जवाबदारी ठेकेदार की होगी।
- सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जब की निविदा की दरों में काफी कमी हो जैसे निविदा दाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदा दाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर.आफिस

- अथवा एन.एस.सी. जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम से देय होगा, जो माग तिथि से 15 दिवस के भीतर जमा करवाया होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
- किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिए कार्मस सिक्यूरिटी के रूप में रोकी जावेगी।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 01 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथ पत्र कंडिया क्र.- 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तातरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम, कोरबा के पास सुरक्षित रहेगा।
 23. निविदा खुलने की तिथि में अवकाश होने पर अगामी तिथि को निविदा संबंधित कार्यवाही मानी जावेगी।

नोट :-

01. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगर जमा रसीद पृथक से लिफाफे में स्वीकार किये जायेंगे जो आयुक्त नगर पालिक निगम, कोरबा के नाम से देय हो।
02. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम.....

पूर्ण पता.....

मोबाई न.-.....

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

Name of Work WARD NO. 52 SARVJANIK SAMUDAYIK / SAANSKRITIK BHAWAN KA SANDHARAN AVM BHAWAN ME NAYI
SUVIDHAON KI VYAVASTHA. (COUNCILLOR FUND)

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	19.11	185.00	3,535.35
2	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	4.44	371.00	1,647.24
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	7.82	4073.00	31,850.86
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).	cum	4.32	2970.00	12,830.40
5	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	500.00	54.50	27,250.00
6	3.16	Making 50mm thick plinth protection of plain cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded crushed stone aggregate 20mm nominal size) over 75mm bed of dry brick ballast 40mm nominal size well rammed and consolidated and grouted with sand including finishing the top smooth.	sqm	60.00	273.00	16,380.00
7	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	6.50	4163.00	27,059.50
8	3.14	Providing and mixing water proofing material in PCC/ RCC work in the proportion recommended by the manufacturer.	kg	10.00	43.50	435.00
9	4.13	Grading roof for water proofing treatment with:				
	13.1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum	8.53	3817.00	32,559.01
10	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	26.91	139.00	3,740.49
11 9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	200.00	68.00	13,600.00
12 9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	150.00	75.00	11,250.00
13 11.2	Providing and making 12mm thick cement plaster of mix:				
2.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	57.00	96.50	5,500.50
14 11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
3.3	In Cement Mortar 1:5 (1 cement : 5 fine sand)	sqm	57.00	113.00	6,441.00
15 14.9	Distempering with acrylic washable distemper to give an even shade.				
9.1	On new work (Two or more coats)	sqm	700.00	38.00	26,600.00
16 14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	1033.00	94.50	97,618.50
17 14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
14.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	500.00	41.00	20,500.00
18 7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
5.3	Cement Mortar 1:5 (1 cement : 5 coarse sand)	cum	10.70	3350.00	35,845.00
19 8.13	Providing and fixing flush door shutters, conforming to IS 2202 (Part 1), interior grade, commercial type, core of block board construction with frame of first class hard wood and well matched commercial ply veneering with vertical grains, cross bands and face veneers on both faces of shutters excluding hinges.				
13.2	35 mm. thick (single leaf)	sqm	8.40	1370.00	11,508.00
20 8.52	Providing, and fixing M.S. round and square bars with MS flat of required pattern in wooden frames for windows & clerestory windows including applying a priming coat of red oxide zinc chromate primer, welding etc complete				
52.1	Plain grill	kg	180.00	68.00	12,240.00
21 8.96	Providing and fixing M.S. bright finished or black enameled Double spring hinges with iron screws:				
26.2	125 mm	each	15.00	286.00	4,290.00
22 8.99	Providing and fixing M.S. bright finished or black enameled sliding door bolts with bolts, nuts and necessary iron screws:				
29.1	300x16mm	each	30.00	77.50	2,325.00
23 10.5	Providing ridges or hips of 60cm overall width in plain G.I. sheet fixed with galvanized washers J or L hooks, bolts and nuts 8mm G.I. limpet and bitumen washers complete.				
5.4	0.50 mm thick sheet with zinc coating not less than 275 gm/sqm	sqm	112.00	380.00	42,560.00

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
10.10	Extra for providing and fixing wind ties of 40x6mm flat iron section.	metre	40.00	118.00	4,720.00
25	9.2 Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	Kg	298.00	66.00	19,668.00
26	12.56 25mm thick Local RAJIM/ Red Flag stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid over & jointed with grey cement slurry mixed with pigments to match the shade of the stone i/c grinding, rubbing and polishing.	sqm	252.00	516.00	130,032.00
27	12.57 25mm thick Local RAJIM/ Red Flag stone slab in riser of steps, skirting, dado and pillars laid on 12mm (Average) thick cement mortar 1:4 (1 cement : 4 coarse sand) and joint with grey cement slurry mixed with pigments to match the shade of the slab i/c grinding, rubbing and polishing.	sqm	80.00	595.00	47,600.00
28	14.22 Painting on new work (two or more coats) to give an even shade with:				
	22.1 Satin synthetic enamel paint	sqm	32.52	55.00	1,788.60
29	14.23 Painting on old work (one or more coats) to give an even shade with:				
	23.1 Satin synthetic enamel paint	sqm	48.24	35.00	1,688.40
30	14.44 Removing white or colour wash by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete.	sqm	1200.00	4.30	5,160.00
31	14.46 Removing old paint or polish by paint remover or blow lamp or any other means as approved including preparing the surface smooth after removing the paint.	sqm	48.24	32.50	1,567.80
32	16.43 Demolishing cement concrete including disposal of material within 50 metre lead.				
	13.2 1:3:6 or richer mix	cum	8.40	549.00	4,611.60
33	12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.2 Size above 200x300mm	sqm	35.28	646.00	22,790.88
34	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	9.1 Size 300x300mm	sqm	17.28	692.00	11,957.76

As per Estimate Amount Rs. 699150.89

say Rs. 7,00,000/-

Sub Engineer
Nagar Palik Nigam
Korba (C.G.)

Assistant Engineer
Nagar Palik Nigam
Korba (C.G.)

Executive Engineer
Nagar Palik Nigam
Korba (C.G.)