कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

कोसाबाड़ी जोन

फा.क्र./513, 514, 515 एवं 516/निर्माण (कोसा.)/2019 — कोरबा, दिनांक 29.01.2020

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.08.2015** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्युल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल निविदा वेबसाईट से डाउनलोड कर त्रि–लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :–

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि – 18.02.2020 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि – 18.02.2020 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रू में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 18 बालको रोड ढेंगुरनाला गभेल समाज भवन के पास सामुदायिक भवन निर्माण कार्य। **(विधायक मद)**	10,00,000/-	8,000/-	750/-	Form-A	04 माह	सक्षम श्रेणी	18.02.2020
2	वार्ड क्र. 21 बुधवारी में भीम बहादुर सोनी के घर के पास शेड व चबूतरा का निर्माण कार्य। **(विधायक मद)**	5,00,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	18.02.2020
3	वार्ड क्र. 25 ब्रम्हवाटिका परशुराम मार्ग पंचमुखी हनुमान मंदिर के पास घंटाघर (हेलीपेड बायपास मार्ग पर) के पास सामुदायिक भवन निर्माण सह अहाता निर्माण कार्य। **(विधायक मद)**	20,00,000/-	15,500/-	750/-	Form-A	05 माह	सक्षम श्रेणी	18.02.2020
4	वार्ड क्र. 29 में बरेठ सामुदायिक भवन पोड़ीबहार के पास सार्वजनिक मंच एवं सामुदायिक भवन निर्माण कार्य। **(विधायक मद)**	10,00,000/-	8,000/-	750/-	Form-A	04 माह	सक्षम श्रेणी	18.02.2020

निविदा की शर्तेः–

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो–हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा **आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला–कोरबा (छ.ग.) पिन नं.–495677** के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाऍं स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाईट **www.korbamunicipal.in/uad.cg.gov.in** डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनॉक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि–लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगाः–

क्रमशः...............02

(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोष में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।

(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।

(स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।

5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।

6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकरी पिछले वित्तीय वर्ष का **आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं** विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।

7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कमाँक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।

8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लेवें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।

9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।

10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।

11. ठेकेदार को अपनी दरें शब्दों एवं अंको में लिखना अनिवार्य होगा।

12. शासन के विभिन्न विभागों जैसेः– खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय–समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।

13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।

14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरूद्ध तत् समय में एम.आई. सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।

15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस. सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से **15 दिवस** के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।

16. सम्पूर्ण किये गये कार्यों के लिये **5 प्रतिशत** सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष **5 प्रतिशत पृथक से 03** वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।

17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।

क्रमशः...............03

18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किए जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना आवश्यक होगा।
19. ईंट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोटः–

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समयएवं स्थान माना जावे।

(ठेकेदार के हस्ताक्षर)

नाम ....

पूर्ण पता ....

....

मोबाईल नं.– ....

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT

[illegible]me of Work :- Construction of Samudayik Bhawan Near Gabhel Samaj Bhawan, Balco Road Dhengur Na[illegible] Ward No. 18

As per S[illegible] - Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno.	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling				
	In all types of soil	62.45	Cum	185.00	11553.25
2	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto	62.45	Cum	65.00	4059.25
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	2.70	Cum	371.00	1001.70
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.				
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	11.81	Cum	2659.00	31402.79
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	Foundations, footings, base of columns and plinth beam in any shape and size.	40.80	Sqm	139.00	5671.20
	Columns, Pillars, Piers and likes- rectangular or square in shape	48.00	Sqm	297.00	14256.00
	Beams, lintels, cantilevers & walls	51.80	Sqm	202.00	10463.60
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves	102.12	Sqm	235.00	23998.20
	Weather shade, chhajja, Cornices and mouldings	8.40	Sqm	294.00	2469.60
6	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.				
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal	31.95	Cum	4163.00	133007.85
7	Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	17.96	Cum	97.50	1751.10
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:				
	Thermo-Mechanically treated bars	3220.00	kg	54.50	175490.00
9	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in:				
	Cement Mortar 1:6 (1 cement : 6 coarse sand)	35.60	Cum	3263.00	116162.80
10	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	25.60	Cum	121.00	3097.60
11	7.11 Half brick thick brick masonry with fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in superstructure above plinth level upto plinth level:				
	Cement Mortar 1:4 (1 cement : 4 coarse sand)	16.50	Sqm	382.00	6303.00
12	Providing and making 6mm thick cement plaster of mix:				
	In Cement mortar 1:4 (1 cement : 4 fine sand)	102.35	Sqm	87.00	8904.45
13	Providing and making 12mm thick cement plaster of mix:				
	In Cement Mortar 1:5 (1 cement : 5 fine sand)	195.38	Sqm	96.50	18854.17
14	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	In Cement Mortar 1:5 (1 cement : 5 fine sand)	187.66	Sqm	113.00	21205.58

Sno.	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
[illegible]	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including	150.00	Kg	75.00	11250.00
16	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including	300.00	Kg	67.50	20250.00
17	12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey				
	Size upto 200x300mm	24.60	Sqm	587.00	14440.20
18	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed				
	Size 300x300mm	17.00	Sqm	692.00	11764.00
19	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm),				
	Size 600x600mm	63.04	Sqm	1151.00	72559.04
20	9.47 Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed				
	For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/	150.00	Kg	338.00	50700.00
21	9.51 Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall be paid in basic item):				
	With float glass panes of 5 mm thickness	12.15	Sqm	708.00	8602.20
22	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	485.39	Sqm	94.50	45869.36
23	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade.				
	On new work (two or more coats)	485.39	Sqm	52.50	25482.98
24	Painting on new work (two or more coats) to give an even shade with:				
	Satin synthetic enamel paint	22.82	Sqm	55.00	1255.10
25	Providing and fixing water closet squatting pan (Indian type W.C. pan),100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures				
	White Long pattern W.C. pan of size 580 mm	2.00	Each	2459.00	4918.00
26	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				
	White Size 550x450 mm	2.00	Each	1430.00	2860.00
27	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring				
	110 mm dia pipe	10.00	Mtr.	267.00	2670.00
28	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382				
	Tee/ Tee with door/ Bend 45°/ Bend 90°				
	110 mm	6.00	Each	154.00	924.00
	Nahani trap 110x75mm	4.00	Each	90.50	362.00

Sno.	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass [illegible]aded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes				
	15 m[illegible]ominal outer dia .Pipes.	10.00	Mtr.	110.00	1100.00
	20 mm no[illegible]al outer dia .Pipes	20.00	Mtr.	151.00	3020.00
30	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:				
	Bib cock (400 grams)	6.00	Each	382.00	2292.00
	Stop cock (concealed) (600 grams)	4.00	Each	494.00	1976.00
31	Providing and fixing stainless steel drain jali of approved make/quality.	4.00	Each	51.00	204.00
32	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings	1000.00	Ltr.	7.30	7300.00
33	Boring/driling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/strainer pipe, by itable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and				
	All Types Of Soil				
	150 mm dia.	25.00	Mtr.	339.00	8475.00
	Rocky strata including Boulders				
	150 mm dia.	65.00	Mtr.	396.00	25740.00
34	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing				
	Rocky strata including Boulders				
	150 mm dia.	20.00	Mtr.	424.00	8480.00
35	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories				
	150 mm nominal size dia.	27.50	Mtr.	540.00	14850.00
36	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the				
	down method, collecting water samples & getting tested in approved laboratory, i/c disinfection of tube well, all complete, including hire &	5.00	hour	654.00	3270.00
37	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all				
	150 mm dia	1.00	Each	217.00	217.00
38	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data	1.00	Point	1502.00	1502.00
39	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of				
	15 mm dia. nominal bore	17.20	Mtr.	149.00	2562.80
	20 mm dia. nominal bore	20.00	Mtr.	185.00	3700.00
	25 mm dia. nominal bore	50.00	Mtr.	258.00	12900.00
40	Providing and fixing gun metal non- return valve (horizontal type) of approved quality (screwed end)				
	32 mm nominal bore	1.00	Nos	556.00	556.00
41	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end)				
	25 mm nominal bore	2.00	Nos	436.00	872.00

S.No.	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
42	Providing and fixing of submersibal Moter pump i/c all accecssories 2 HP single phase.	1.00	Nos	19886.00	19886.00
43	Supplying and fixing GI pipe B class 32 mm dia	30.00	Nos	298.00	8940.00
44	Supplying installation and commisioning of 1-3 HP 1 phase starter.	1.00	Nos	4125.00	4125.00
45	Supplying and fixing following size submersible cable 3x2.5 sq. m	50.00	Nos	67.50	3375.00
46	Supplying and making waterproffing joint 3x2.5 sq. m	1.00	Nos	275.00	275.00
47	Supplying and laying of approved make stainless of 6mm	50.00	Nos	16.50	825.00
	As per SOR Total Estimate Amount Rs.				1000001.81
	Say Amount Rs.				1000000.00

Sub Engineer
Municipal Corporation
Korba (C.G.)

Asst. Engineer
Municipal Corporation
Korba (C.G.)