रभि

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. /686/ निर्माण/2024

सिस्टम टेंडर नं.152681

कोरबा दिनांक 07.02.2024

ई–निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग में एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा (सड़क) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) शेड्यूल अनुसार प्रतिशत दर पर ई प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म–। में निविदाएँ आमंत्रित की जाती है।

क्र	कार्य का नाम	प्राक्कलन राशि(लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड 35, 36, 37, 14 में [redacted] बी टी रोड निर्माण कार्य ।	68.00	51000.00	4 माह (वर्षा ऋतू को छोडकर)	3000.00	वर्ग डी एवं प्रवर श्रेणी	29.02.2024 से . .....

शर्तें:–

1. निविदा दरें प्रचलित सी.एस.आर. से कम या अधिक का उल्लेख किया जावे। सी.एस.आर. के अंतर्गत के आयटमों पर पृथक आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरूद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नही होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग मे पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 03 वर्षो का आयकर चुकता प्रमाण पत्र/पेन नंबर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के एफ.डी.आर /टी.डी.आर. की प्रति ऑनलाईन अपलोड करना अनवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्यनिधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि, एफ.डी.आर/टी.डी.आर., शपथ पत्र का स्केन कॉपी ऑनलाईन सिस्टम पर अपलोड करना अनवार्य होगा।
   - अमानत राशि का वैध एफ.डी.आर./टी.डी.आर., निविदा प्रतिभागी शुल्क का डी.डी. एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई. चौक रामपुर कोसाबाडी पिन–495677 कोरबा को उपलब्ध करना अनिवार्य होगा।
   - निविदाकार को निविदा मे पंजीयन क्षमता के अंतर्गत वर्तमान में नगर पालिक निगम या अन्य विभागों कें उनके द्वारा किये जा रहे कार्यो का विवरण राशि सहित मूलप्रति में वैध शपथ पत्र (राशि रू. 100/– नॉनज्यूडिशियल स्टाम्प निविदा आमंत्रण दिनांक के पश्चात् का निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
   - अमानत राशि का एफ.डी.आर./टी.डी.आर. एवं निविदा प्रतिभागी शुल्क का डी.डी. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिये प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिये रोकी जावेगी एवं 5 प्रतिशत राशि परफारमेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारो द्वारा कर्मचारी भविष्यनिधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होगें।
6. निविदा मे भाग लेने वाले ठेकेदारो को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमो के तहत् पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. डामरीकरण कार्य का निविदा प्रपत्र क्रय करते समय ठेकेदार को स्वयं के स्वामित्व के आटोमेटिक ड्रम मिक्स प्लांट, रोलर एवं अन्य मशीनरी, हॉट मिक्स प्लांट, पेवर फिनिशर एवं रोड रोलर आदि मशीनों के प्रमाण पत्र आवेदन के साथ संलग्न कर आवश्यक होगा तथा निविदाकार का 60 कि.मी. की परिधि मे हॉट मिक्स प्लांट होना आवश्यक है।
8. ठेकेदार द्वारा 60/70 ग्रेड का डामर IOC, BPCL,HPCL से ही क्रय कर लगाना होगा। ठेकेदार को तल कंपनी को दी जाने वाली प्रदाय आदेश की प्रतिलिपि इस कार्यालय को देनी होगी।
9. कार्य में प्रयुक्त डामर खरीदी के देयक (बिल) कार्यालय में प्रस्तुत करने पर ही भुगतान किया जावेगा।
10. निविदा दरों में असामान्य कमी प्रतीत होने पर सफल निविदादाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.सी.सी. जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा मे निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नही किया जावेगा।
12. निविदा प्रपत्र फार्म–ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।

15 उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किया जा सकते है।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि :—

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को नंकण्वहण्हवअण्पद में अपलोड करने हेतु प्रेषित।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		07.02.2024	19.30	07.02.2024	19.30	Release Tender
2		Bid Submission	07.02.2024	19.30	28.02.2024	17.30	
3		Physical Document Submmission	07.02.2024	19.30	29.02.2024	15.00	
4	Tender Open		29.02.2024	16.00	--	--	

EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

TENDER/NIT HEADER DETAIL

ORGANIZATION NAME	Urban Administration and Development Department (UADD)	PROCUREMENT CATEGORY	WORKS
TENDER NO	[illegible]	TENDER DEALING OFFICER	- Navneet Kant Nath(DFLT)
NUMBER OF ITEMS ALREADY ATTACHED	1	MATCHING	NO
CURRENCY	INR - INDIAN RUPEE		
NIT TYPE	RESTRICTED TENDER	TENDER CATEGORY	PERCENTAGE
VENDOR CLASS	A, B, C, D		
PROBABLE AMOUNT OF CONTRACT(PAC) (INR)	6800192.95	OFFICE/DIVISION(PWD) NAME	COMMISSINOR, MUNICIPAL CORPORATION, KORBA
DIVISION / DISTRICT NAME	MUNICIPAL CORPORATION, KORBA	SECTION/CIRCLE(PWD) NAME	TENDER SECTION
DESCRIPTION	F.No. 686/ Const./2024/KMC		
DETAILED DESCRIPTION	[illegible] of BT Road at BALCO & TP Nagar Ward 35,36,37,14.		
E-AUCTION ENABLED?	N		
NUMBER OF BID PART(S)	2	BID PART NUMBER	1

ATTRIBUTE(S)

ATTRIBUTE NAME	ATTRIBUTE VALUE
BID VALIDITY PERIOD (in days)	120
Tender / Work Completion Time (in months)	6(VALUE)
Required Past Technical Experience	As per Tender Document/NIT
Required Financial Turnover (in INR)	AS PER NIT
Required Bid Capacity (in INR)	AS PER NIT

PAYMENT DETAILS

DETAILS	
Tender/Processing/Bid Fees	N/A
EMD/Bid Security	51000.00 INR

DATE-TIME DETAIL(S)

BID SUBMISSION START DATE	Feb 7, 2024 06:30:42:PM	BID DUE DATE	Feb 28, 2024 05:30:50:PM
BID OPEN DATE (SCHEDULED)	Feb 29, 2024 04:00.55:PM		

PRE-BID DISCUSSION DETAILS

PRE BID DISCUSSION NOT REQUIRED

ALTERNATE BID DECRYPTOR(S)

USER DETAILS
MR BUYER ADMIN(DFLT)
- MANORANJAN SARKAR(DFLT)
- Mitesh Verma(DFLT)
- Ramkumar Maheshwari(DFLT)
- Bhushan Ram Oraon(DFLT)
- Navneet Kant Nath(DFLT)
- Akhileshwar Prasad Shukla(DFLT)

TERM AND CONDITION DETAIL(S) - SPECIAL TERM(S)

SL. NO.	CATEGORY	DESCRIPTION
1	SPECIAL TERM(S)	SPECIAL TERM(S) As per Tender Document/NIT

TENDER SPECIFIC REQUIRED ATTACHMENT(S)

Envelop B

SL. NO.	SUPPORTING DOCUMENT NAME	MANDATORY	ALLOW EXEMPTION	GROUP
1	REGISTRATIONCERTIFICATE(ANY GOVTDEPTINCHHATTISGARH)	YES	NO	OTHER
2	INCOMETAXCLEARANCECERTIFICATE	YES	NO	OTHER
3	PARTNERSHIPDEED / MOA - COMPANY (IFREQUIRED)	YES	NO	OTHER
4	DECLARATIONFOR NOT BEINGBLACK LISTED	YES	NO	OTHER
5	LIST OFTECHNICALSTAFFDETAIL	YES	NO	OTHER
6	GST CERTIFICATEFROMCHHATTISGARH	YES	NO	OTHER
7	DECLARATIONFOR NOT ABOVE TOTAL WORK OF REGISTRACTION CAPACITY	YES	NO	OTHER

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

ABSTRACT

Work :... Tarring at Balco Zone & TP Nagar.

SOR :SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ROAD-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.11	Scarifying existing bituminous surface to a depth of 50 mm (Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead up to 1000 meters) as per clause 305.4.3.	Sqm.	7503	23.00	172,569.00
2	4.10	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	Cum	90	1434.00	129,060.00
3	5.1	Prime coat (Providing and applying primer coat with oil based bitumen emulsion (SS-1, grade confirming to IS:8887) on prepared surface of granular Base including clearing of road surface and spraying primer using mechanical means as per clause 502.				
	(i)	on WBM/WMM surface @0.85 Kg/sqm.	Sqm	16673	64.00	1,067,072.00
4	5.2	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503.				
	(i)	Bituminous surface @ 0.25 kg /Sqm	Sqm	15633	15.00	234,495.00
5	5.3	Bituminous Macadam (Providing and laying bituminous macadam as per clause 504 with mixed prepared in minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction)				
	B	With mechanical paver finisher	0			
	(ii)	for Grading-II(19 mm nominal maximum size, bitumen content 3.40%)	Cum	420.15	6255.00	2,628,038.25
6	5.8	Close Graded Premix Surfacing/Mixed Seal Surfacing (Mechanical means using minimum 40-60 TPH capacity of HMP. Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness using bitumen to the required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a Smooth wheeled roller 8-10 tonne capacity, and finishing to required level and grade, complete as per clause 508)				
	II.	With mechanical paver finisher	0			
	A	With bitumen	0			
	ii)	Type B (13.2 mm to 0.09 mm size aggregates)	Sqm	17344.6	146.00	2,532,311.60
7	4.13	Construction of Shoulders (Construction of shoulders as per clause 408 with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing				

Scanned with OKEN Scanner

...M DESCRIPTION		UNIT	QTY	RATE	AMOUNT
	surface, providing required cross fall, compacting, watering rolling and royalty charges etc. complete.				
B	With smooth wheeled roller	Cum	132.3	277.00	36,647.10
				As per Estimate Amount Rs.	6800192.95

S/E
Nagar Palik Nigam
Korba(C.G.)

A.E.
Nagar palik Nigam
korba(C.G.)

Executive Engineer,
Municipal Corporation,
KORBA (Chhattisgarh)