



कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क./43, 45, 46, 47, 48, 50, 51, 52, 53, 54, 55 /निर्माण (कोसा.)/2019

कोरबा, दिनांक 29.07.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत टेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्फलन राशि में	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्रमांक 20 काशीनगर अंतर्गत पप्पू पटेल से लोचन राठौर घर तक नाली का मरम्मत एवं निर्माण कार्य। (मरम्मत एवं संधारण मद)	3,98,883/-	21.08.2019	27.08.2019
2	वार्ड क्रमांक 21 बुधवारी बाजार में नाली का मरम्मत कार्य।(मरम्मत एवं संधारण मद)	3,99,000/-	21.08.2019	27.08.2019
3	वार्ड क्रमांक 21 के विभिन्न स्थानों में नाली एवं कलवर्ट का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	3,85,000/-	21.08.2019	27.08.2019
4	वार्ड क्र. 23 अंतर्गत सामुदायिक भवन के समीप नाली का मरम्मत एवं निर्माण कार्य। (मरम्मत एवं संधारण मद)	3,99,618/-	21.08.2019	27.08.2019
5	वार्ड क्र. 21 अंतर्गत बुधवारी में नाली का मरम्मत एवं निर्माण कार्य। (मरम्मत एवं संधारण मद)	3,99,618/-	21.08.2019	27.08.2019
6	वार्ड क्र. 30 के सामुदायिक भवन का मरम्मत एवं विभिन्न कार्य। (मरम्मत एवं संधारण मद)	3,52,000/-	21.08.2019	27.08.2019
7	वार्ड क्र. 29 पोड़ीबहार में कैलाश यादव घर एवं गगेश चौक के समीप सी.सी. सड़क का मरम्मत एवं संधारण कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019
8	वार्ड क्र. 29 पोड़ीबहार में आदर्श नगर नीचे मोहल्ला में आर.सी.सी. ड्रेन एवं सी.सी. रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019
9	वार्ड क्र. 30 मानिकपुर के विभिन्न सी.सी. सड़क का मरम्मत एवं संधारण कार्य। (मरम्मत एवं संधारण मद)	3,98,000/-	21.08.2019	27.08.2019
10	वार्ड क्र. 30 मानिकपुर नीचे मोहल्ला डीपरापारा में आर.सी.सी. नाली एवं सी. सी. रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019
11	वार्ड क्र. 30 मानिकपुर यादव मोहल्ला में आर.सी.सी. ड्रेन का मरम्मत कार्य। (मरम्मत एवं संधारण मद)	4,00,000/-	21.08.2019	27.08.2019

उपरोक्त कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है साथ ही यह जानकारी विभागीय वेबसाइट Website : www.korbamunicipal.in एवं www.uad.cg.gov.in में देखा एवं डाउनलोड किया जा सकता है। उक्त निविदा में किसी भी प्रकार का संशोधन किया जाता है तो विभागीय वेबसाइट पर देखा जा सकता है।

कार्यपालन अभियन्ता

॥ स्वच्छ भारत निर्माण में योगदान दें ॥

नगर पालिक निगम

कोरबा (छ.ग.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


ABSTRACT

Name of Work :- Maintenance Of Drain And Culvert At Various Place Ward No. 21

As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno.	ITEM DESCRIPTION	Qty	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of In all types of soil	27.60	Cum	185.00	5106.00
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	8.20	Cum	371.00	3042.20
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of				
a	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	8.20	Cum	2659.00	21803.80
b	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	9.00	cum	4073.00	36657.00
4	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
a	Foundations, footings, base of columns and plinth beam in any shape and size.	196.40	cum	139.00	27299.60
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.				
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	35.55	Cum	4163.00	147994.65
6	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding	4.55	Cum	469.00	2133.95
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:				
	Thermo-Mechanically treated bars	2300.00	kg	54.50	125350.00
8	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	30.00	Cum	65.00	1950.00
9	Carriage by mechanical transport upto 5 km lead:				
	Earth	60.00	Cum	111.00	6660.00
10	16.3 Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.				
c	16.3.3 In cement mortar.	10.40	cum	263.00	2735.20
11	16.43 Demolishing cement concrete including disposal of material within 50 metre				
b	1:3:6 or richer mix cum 549.00	7.80	cum	549.00	4282.20
As per SOR Total Estimate Amount Rs.					385014.60
Say Amount Rs.					385000.00


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)