

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

सिस्टम टेंडर नं. 198890

कोरबा दिनांक 07.09.2026

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा सड़क कार्य हेतु दिनांक 01.01.2025 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि
2. निविदा खुलने की अंतिम तिथि

- 01.10.2026 सायंकाल से 3.00 बजे तक

- 01.10.2026... सायंकाल 4.00 बजे से

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यविधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	कोसाबाड़ी जोन अंतर्गत वार्ड क. 32 पोडीबहार चर्च से लकी बिग बास्केट मोड़ तक डामरीकृत सड़क मरम्मत एवं पैच रिपेयर कार्य। (डी.एम.एफ. फंड)	139.92	105000.00	06 माह (वर्षा ऋतु छोड़कर)	3000/-	वर्ग सी एवं प्रवर श्रेणी	01.10.2026 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का रकन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति, स्वयं के स्वामित्व के आटोमेटिक ड्रम मिक्स प्लांट, पेवर, रोलर एवं अन्य मशीनरी के प्रमाणित बिल/आर.सी. की प्रति, लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। साथ ही ऑनलाईन दस्तावेज अपलोड निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से रिपेयरिंग कार्य हेतु 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन (वर्तमान तक वैधता) एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे। कर्मचारी भविष्य निधि संगठन (ई.पी.एफ.) एवं विभिन्न प्रावधानों की धारा 1952 के तहत निविदाकार का जीवित पंजीयन होना आवश्यक है साथ ही निविदा आमंत्रण दिनांक से विगत 03 माह की अवधि में जमा किये गये TRRN Payment Details वालान की प्रति प्रस्तुत करना तथा ऑनलाईन अपलोड किया जाना अनिवार्य होगा।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. डामरीकरण कार्य का निविदा प्रपत्र क्रय करते समय ठेकेदार को स्वयं के स्वामित्व के आटोमेटिक ड्रम मिक्स प्लांट, रोलर एवं अन्य मशीनरी, हॉल मिक्स प्लांट, पेवर फिनिशर एवं रोड रोलर आदि मशीनों के प्रमाण पत्र आवेदन के साथ संलग्न कर आवश्यक होगा तथा निविदाकार का 60 कि.मी. की परिधि में हॉल मिक्स प्लांट होना आवश्यक है। उक्त दस्तावेज फिजिकल लिफाफे के साथ ऑनलाईन भी जमा करना आवश्यक होगा।
8. ठेकेदार द्वारा 60/70 ग्रेड का डामर IOCL, BPCL, HPCL से ही क्रय कर लगाना होगा। ठेकेदार को उल्लेखित कंपनी को दी जाने वाली प्रदाय आदेश की प्रतिलिपि इस कार्यालय को देनी होगी।

9. कार्य में प्रयुक्त डामर खरीदी के देयक (बिल) कार्यालय में प्रस्तुत करने पर ही भुगतान किया जावेगा। कार्य में लाए जा रहे डामर गाड़ियों (टीपर) का वजन पचीं जमा करना अनिवार्य होगा।
10. किये गये कार्यों का प्रत्येक चल देयक के पूर्व ठेकेदार को स्वयं के व्यय पर कौर कटिंग किया जाकर प्रयोगशाला PWD लेब, शास.इंजीनियरिंग कॉलेज, राष्ट्रीय प्रौद्योगिकी संस्थान इत्यादि से परीक्षण कराकर परीक्षण रिपोर्ट जमा करना अनिवार्य होगा।
11. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
12. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
13. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
14. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
15. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
16. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
17. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
18. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
19. कार्य कियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
20. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
21. उपरोक्त कार्य हेतु जिला खनिज संस्थान न्यास मद द्वारा जारी प्रशासकीय स्वीकृति आदेश के सभी नियम एवं शर्तों का पालन करना अनिवार्य होगा।


 अधीक्षण अभियंता
 नगर पालिक निगम
 कोरबा (छ.ग.)

प्रतिलिपि—

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		07.09.2026	15.30	07.09.2026	15.30	Release Tender
2		Bid Submission	07.09.2026	15.30	28.09.2026	17.30	
3		Physical Document Submmission	07.09.2026	15.30	01.10.2026	15.00	
4	Tender Open		01.10.2026	16.00	--	--	


SUPERITENDING ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of Work - Tarring Work From podibahar church To Lucky big basket turnig at kosabadi zone ward no. 32

As per SOR Schedule of rates public works department [P.W.D ROAD - 15.06.2026]


S. N.	SOR Ref.	ITEM DESCRIPTION	NO.	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	3.11	Scarifying Existing bituminous surface to a depth of 50 mm Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material with in all leads & lifts.								
			1	1100.00	7.00		7700.00			
							7700.00	sqm	18.00	138600.00
2	3.2	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all leads & lifts as per relevant clauses of section 300.								
		Road Width Increment	2	1100.00	1.00	0.30	660.00			
		Pipe Culvert	1	8.00	1.50	1.50	18.00			
							678.00	Cum	88.00	59664.00
3	3.13	Construction of sub-grade with Material Obtained from Borrow Pits/Borrow Area Construction of sub-grade with approved material/selected soil having C.B.R. > 8 (unless specified otherwise in the contract) obtained from borrow pits/borrow area with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300 2								
		Sakuntala Clinic	1	250.00	7.50	0.30	562.50			
		Culvert	1	8.00	1.50	0.60	7.20			
							569.70	Cum	228.00	129891.60
4	4.1	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401.								
		Plant mix method (with Mechanically crushed stone only)								
	(b)	For Lower Sub-base with								
	(v)	Grading-V Material								
		Sakuntala Clinic	1	250.00	7.50	0.20	375.00			
							375.00	Cum	1337.00	501375.00
5	4.6	Wet Mix Macadam Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 408.								

		Sakuntala Clinic	1	250.00	7.50	0.20	375.00			
		For shoulder width increment	2	1150.00	1.00	0.20	460.00			
6	5.1	Prime coat					835.00	Cum	1365.00	1139775.00
		Providing and applying primer coat with oil based bitumen emulsion (SS-1, grade confirming to IS:8887) on prepared surface of granular base including clearing of road surface and spraying primer using mechanical means as per clause 502.								
		(i) on WBM / WMM surface @0.85 kg/ sqm.								
			1	250.00	7.00		1750.00			
							1750.00	SQM	65.00	113750.00
7	5.2	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503.								
		(i) Bituminous surface @ 0.25 kg / Sqm								
			1	130.00	4.50		585.00			
			2	1150.00	7.00		16100.00			
							16685.00	SQM	13.00	216905.00
		(ii) Granular surface treated with primes @ 0.30 kg / Sqm								
			1	250.00	7.00		1750.00			
							1750.00	SQM	15.00	26250.00
8	5.5	Dense Bituminous Macadam (Providing and laying dense graded bituminous macadam with 100-120 TPH capacity Batch type HMP using crushed aggregates of specified grading, premixed with bituminous binder @ 4.0 to 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects.								
	B	With Mechanical paver								
	II	for Grading II (26.5 mm nominal size bitumen content 4.50%)								
			1	130.00	4.50	0.07	40.95			
			1	250.00	7.00	0.15	262.50			
			1	1150.00	7.00	0.07	563.50			
							866.95	Cum	7211.00	6251576.45
9	5.7	Bituminous Concrete Providing and laying bituminous concrete with minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder @ 5.0 to 6.0% by weight of total mix of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects.								
	B	With Mechanical paver								
	III	for Grading II (13.2 mm nominal size aggregate) with bitumen 6.0 %								
			1	130.00	4.50	0.04	23.40			

		1	1150.00	7.00	0.04	322.00			
						345.40	Cum	8166.00	2820536.40
4.11	Construction of Shoulders								
	Construction of shoulders with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing surface, providing required cross fall, compacting, watering, rolling etc. complete as per clause 408.								
	(a) With Vibratory roller								
		2	800.00	1.50	0.30	720.00			
						720.00	Cum	278.00	200160.00
11	9.8 Plain cement concrete complete as per drawing and Technical Specifications								
	(i) PCC Grade M 15								
	Culvert Bed	1	8.00	1.50	0.20	2.40			
						2.40	Cum	3243.00	7783.20
	(ii) CC Grade M 20								
	Raft	1	8.00	1.50	0.15	1.80			
	Side	2	8.00	0.60	0.40	3.84			
	END	2	2.00	0.60	1.50	3.60			
	Deduction Culvert	-2	3.14/4	1.00	1.00	-1.57			
						7.67	Cum	3617.00	27742.39
12	3.19 Construction of RCC open drain								
	(a) Construction of RCC open drain with width 1.0m or 0.8 m (inside dimension) and average depth from inlet to outlet 1.0m or 0.8m (maintaing slope as per site conditions) with 150 mm thick RCC M-25 walls, 150 mm thick RCC M-25 bottom slab, over 100 mm thick (Av.) levelling course in PCC M-15 including excavation, dressing of sides and bottom, providing HYSD reinforcement consisting of 10mm dia horizontal bars @ 150 mm c/c and U-shaped 10 mm dia bars @ 150 mm c/c including cutting, bending and binding wires, placing in position, providing shuttering and concreting by using concrete mixer, compaction by vibration etc complete as per drawings and technical specifications.								
	(i) 1.0 m width x 1.0 m average depth								
		1	250.00			250.00			
						250.00	Mtr.	5239.00	1309750.00
13	(b) Construction of RCC open drain with width 0.60m or 0.45 m (inside dimension) and average depth from inlet to outlet 0.60m or 0.45 m (maintaing slope as per site conditions) with 120 mm thick RCC M-25 walls, 120 mm thick RCC M-25 bottom slab, over 100 mm thick (Av.) levelling course in PCC M-15 including excavation, dressing of sides and bottom, providing HYSD reinforcement consisting of 8 mm dia horizontal bars @ 150 mm c/c and U-shaped 8 mm dia bars @ 150 mm c/c including cutting, bending and binding wires, placing in position, providing shuttering and concreting by using concrete mixer, compaction by vibration etc complete as per drawings and technical specifications.								
	(i) 0.60 m width x 0.60 m average depth								

		1	250.00			250.00			
9.5	Providing and laying Reinforced Cement Concrete pipe NP 3 / prestressed concrete pipe. Laying Reinforced cement concrete pipe NP3 /prestressed concrete pipe complying to IS:458, with ends casted as per the requirements of flush jointing of pipes for culverts including joints duly filled and finished with cement mortar 1:2 but excluding bedding below pipes, excavation, protection works, backfilling, concrete and masonry works in head walls and parapets.					250.00	Mtr.	2767.00	691750.00
(D)	1000 mm dia					8.00			
		1	8.00			8.00	Mtr.	4482.00	35856.00
15	3.27 Construction of RCC drain/cover slab/chamber								
	(II) Construction of RCC drain/chamber/cover, placing in position, providing shuttering and concreting by using concrete mixer, compaction by vibration etc complete as per drawings and technical specifications excluding reinforcement. with RCC M-20								
		1	200.00	1.00	0.10	20.00			
						20.00	Cum	4015.00	80300.00
	(iii) Supplying, Fitting and Placing un-coated HYSD bar Reinforcement in Drain/cover/chamber complete as per Drawing and Technical Specifications.								
		20.00	78Kg/Cum	1560.00		1.56			
						1.56	MT	55619.00	86765.64
16	8.22 Road Marking with Hot Applied Thermoplastic Compound with Reflectorizing Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound as per MoRTH Grade 2.5 mm thick including reflectorizing glass beads @ 250 gms per sqm area.								
		2.5	1150.00	0.10		287.50			
						287.50	Mtr.	533.00	153237.50
Total=									13991668.18
Add 18% gst									2518500.27
GRAND TOTAL									16510168.45
Say Rs.=									165.10 lakh


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst Engineer
 Municipal Corporation
 Korba (C.G.)