



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

टी.पी. नगर जोन

फा.क्र./243, 244/निर्माण (टी.पी. नगर)/2024/

कोरबा, दिनांक 11.07.2024

## निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों के क्र. 01 हेतु नॉन एस.ओ. आर. दर के शेड्यूल अनुसार आयटम दरों पर निविदा प्रपत्र **Form-B** में एवं क्र. 02 के भाग-अ हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015** एवं भाग-ब हेतु **PWD Electrical SOR 01.06.2020** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निविदा प्रपत्र **Form-A** निम्नलिखित निर्माण कार्य हेतु मैन्युअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1.	टी.पी. नगर जोन अंतर्गत पंचवटी गेस्ट हाउस छत का सीपेज ट्रीटमेंट कार्य (मरम्मत एवं संधारण मद, प्रथम निविदा)	3,99,000/-	4,000/-	750/-	Form-B	03 माह	सक्षम श्रेणी	01.08.2024	02.08.2024
2.	टी.पी. नगर जोन अंतर्गत डी-2 बंगला का शेड, शौचालय एवं आंतरिक विद्युतीकरण का कार्य (मरम्मत एवं संधारण मद, प्रथम निविदा)	3,96,000/-	4,000/-	750/-	Form-A	03 माह	सक्षम श्रेणी	01.08.2024	02.08.2024

### निविदा की शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-  
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं निविदाओं में निविदाकार को फिजिकल दस्तोवज के साथ निविदा सूचना जारी होने के पश्चात् दिनांक का शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार् की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोश में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।  
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।  
(स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- निविदा ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अगले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, शपथ पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
- निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व रथल का स्वयं निरीक्षण कर लेवें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
- निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
- निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
- ठेकेदार को अपनी दरें शब्दों एवं अंको में लिखना अनिवार्य होगा।
- शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
- ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
- कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।

क्रमशः.....02

- सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर / टी.डी.आर. ऑफिस, टाईम डिपोजिट अथवा एन.एस.सी जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
- सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी। मरम्मत कार्य हेतु मात्र सुरक्षा राशि की कटौती की जावेगी।
  - निविदा में भाग लेने वाले ठेकेदारों को छग भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
  - निविदाकार को प्रत्येक निविदा में पंजीयन छमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथ पत्र कड़िका क 04 के प्रथम लिफाफा (ख) में प्रस्तुत करना अनिवार्य होगा।
  - ईट से संबंधित निर्माण कार्यों में प्लाई ऐश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
  - निविदा प्रपत्र अहस्तातरणीय होगा एवं सरतः निविदाओं पर विचार नहीं किया जावेगा।
  - निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
  - निविदा प्रपत्र From-A के क्लॉज नंबर-11 अनुसार एस्कैलेशन देय नहीं होगा।
  - ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गये प्रावधानों का पालन करना अनिवार्य होगा।
  - ठेकेदार द्वारा संपादित किये गये कार्यों के देयकों का भुगतान बजट आवंटन और राशि उपलब्ध होने पर किया जावेगा।
  - निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
  - निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट-


- अमानत राशि के रूप में एफ.डी.आर / टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
- उपरोक्त तिथियों में किसी भी तिथि को शासकीय / स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

पृष्ठा.क्र./243, 244/निर्माण (टी.पी. नगर)/2024/  
प्रतिलिपि :-

कोरबा, दिनांक 11.07.2024

- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, मंत्रालय अटल नगर नया रायपुर (छ.ग.) को [uad.cg.gov.in](http://uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।

हस्ताक्षर -  
फर्म का नाम -  
पता -  
मोबाईल नंबर -

  
कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)**  
**DETAILED ESTIMATE**

Name of work:- Maintenance of Shed, Toilet and Internal Electrification of D2 Bungalow at T.P. Nagar zone

As per TOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of								
	1	In all types of soil								
		column	5	1.00	1.00	1.10	5.50			
							Total	5.50	Cum	185.00
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	3	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								
			5	1.00	1.00	0.10	0.50			
						Total	0.50	Cum	2659.00	1329.50
5	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with								
							Total	5.50	Cum	65.00
9	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:								
	3	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
			1	5.50	0.20	2.40	2.64			
						Total	2.64	Cum	3263.00	8614.32
11	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
			5	1.00	1.00	1.10	5.50			
						Total	5.50	Cum	4073.00	22401.50

12	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete								
	1	Size 600x600mm								
			1	5.50	4.80				26.40	
									Total	26.40 sqm 1151.00 30386.40
15	12.46	15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry including rubbing and polishing etc. complete (single stone is to be used for risers and treads of steps and width of stone for skirting and dado shall be equal to the height of skirting & dado and length of 1.0 m).								
	1	Granite stone grey/pink								
			1	5.50	1.20				6.60	
									Total	6.60 sqm 1869.00 12335.40
									=	
16	9.15	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.								
		window	1	200.00					200.00	
									Total	200.00 Kg 67.50 13500.00
									=	
16	9.2	Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate								
			5	4.2	8.8				184.8	
			1	6	5	25.00			750.00	
									Total	934.80 kg 66.00 61696.80



					Total	26.40	sqm	91.50	2415.60
21	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.							
						26.40			
			1	5.5	4.8	26.40			
					Total	52.80	sqm	94.50	4989.60
22	14.1	Wall painting with acrylic premium emulsion (plastic) paint of required shade to give an even shade.				26.40	sqm	44.50	1174.80
	1	On new work (Two or more coats)							
23	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per				26.40	sqm	56.00	1478.40
	1	On new work (Two or more coats)							
35	14.22	Painting on new work (two or more coats) to give an even shade with:							
	2	Premium synthetic enamel paint	2	6.50	2.10	27.30			
			2	3.50	2.10	14.70			
			5	0.90	0.60	2.70			
					Total	44.70	sqm	47.00	2100.90
36	10.61	Providing and fixing at all height false ceiling consisting of frame work "W" / "U" / "L" sections made of G.I. sheet with zinc coating of grade 120 consisting of angle cleats of size 25mm wide x 1.6mm thick with flanges of 22mm and 37mm at 1200mm centre to centre one flange fixed to the ceiling with dash fastener 12.5mm dia x 40mm long with 6mm dia bolts to the angle hangers of 25x25x0.55mm of required length, and other end of angle hanger being fixed with nut and bolts to G.I. channels							
			1.5	5.50	4.80	39.60	sqm	658.00	26056.80
		Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse							
		Size 300x300mm	2	2.20	1.80	7.92	sqm	692.00	5480.64
		Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete							
		Size above 200x300mm	4	2.20	2.10	18.48			
			4	1.80	2.10	15.12			
					total=	33.60	sqm	646.00	21705.60



OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE


Name of work :electrification work

As per SOR: Schedule of rates public works department [PWD ELECTRICAL-01-06-2020] PART- B

S. No.	SOR Ref.	ITEM DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	7.1	Wiring for light/ fan/ exhaust fan / call bell point with 3x1.5 sqmm FRLS PVC Insulated stranded copper conductor wire for phase, neutral and earth in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) with 5/6 amp piano type switch, phenolic laminated sheet, suitable size M.S. box etc as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	1	Short Point	17				17	Point	240.00	4080.00
	2	Medium Point	4				4	Point	376.00	1504.00
2	1.3	Extra for providing and fixing light plug point on board in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) point wiring with piano type 3 pin 5/6 amp socket outlet and 5/6 amp switch including cost of phenolic laminated sheet and M.S. box etc. as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)	2				2.00	Point	87.00	174.00
3	1.13	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, wire in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)								
	4.13.2	3 X 2.5 sq. mm in 20mm conduit	2	45.00			90.00	Metre	111.00	9990.00
4	6.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earthing etc. complete as required. P.F. should be greater than 0.9, with BEE Star rating from 3 star and above, IS: 374:2019 including all amendments.								
	3	1400 mm sweep	2				2	Each	1773.00	3546.00
5	6.15	Supplying, installation, testing and commissioning of following LED fitting (luminaries) Panel Light in round/ square shape complete with electronic driver heat sink capacitor and all other accessories on surface/ in false ceiling etc. as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio $\geq$ 100 lumens /watt.								
	8.22.5	12 Watt	12				12.00	Each	588.00	7056.00



6.22.6	15 Watt	8				8.00	Each	679.00	5432.00
6	5.1	Supplying and fixing following piano type switch, socket, other accessories on the existing switch box/ cover including connections etc. as per specification.							
	5.1.1	2				2.00	Each	25.00	50.00
	5.1.4	6				6.00	Each	59.00	354.00
	5.1.5	8				8.00	Each	42.00	336.00
	5.1.6	4				4.00	Each	73.00	292.00
	5.1.7	4				4.00	Each	38.00	152.00
	5.1.8	2				2.00	Each	51.00	102.00
	5.1.12	2				2.00	Each	130.00	260.00
	5.1.13	7				7.00	Each	32.00	224.00
	5.1.15	4				4.00	Each	38.00	152.00
7	9.1	Providing and fixing following rating and breaking capacity MCCB in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as per specification, IS/ IEC: 60947-2 and Ics = 100 % Icu.							
	11.17.2	6				6.00	Each	1483.00	8898.00
								TOTAL =	42602.00

  
Sub Engineer  
Municipal Corporation  
Korba (C.G.)

  
Asst Engineer  
Municipal Corporation  
Korba (C.G.)

# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

## DETAILED ESTIMATE

### SANITATION WORK

As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

#### PART - C - SANITATION WORK


	76	Providing and fixing on wall face UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion							
	1	75 mm dia pipe.	1	30.00		30.00	metre	182.00	5460.00
	2	110 mm dia pipe.	1	30.00		30.00	metre	267.00	8010.00
	18.4	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same				2	each	4415.00	8830.00
3	18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				2	each	1605.00	3210.00
	1	Coloured Size 550x450 mm							
6	18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.							
	1	Tee/ Tee with door/ Bend 45°/ Bend 90°							
	1	75 mm				6.00	each	113.00	678.00
	2	110 mm				6.00	each	154.00	924.00
	3	Vent cover							
	1	75 mm				8.00	each	34.00	272.00
	6	Nahani trap 110x75mm				8.00	each	90.50	724.00
7	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of							
	1	15 mm nominal outer dia .Pipes.				60.00	metre	110.00	6600.00
	3	25 mm nominal outer dia .Pipes.				40.00	metre	199.00	7960.00
	4	32 mm nominal outer dia .Pipes.				30.00	metre	271.00	8130.00

19.13	Providing and fixing 15 mm nominal								
1	Bib cock (250 grams)					6.00	each	185.00	1110.00
9	19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved							
6	Stop cock (concealed) (600 grams)					3.00	each	494.00	1482.00
4	Pillar Cock (400 grams)					2.00	each	398.00	796.00
	Long nose bib cock (500 grams)					4.00	each	455.00	1820.00
	Two way bib cock (800 grams)					2.00	each	708.00	1416.00
	Basin mixer pillar tap with spout (1000 grams)					2.00	each	1248.00	2496.00
	Wall mixer with elegant knob (1400 grams)					2.00	each	1787.00	3574.00
	Hand shower set with flexible extension pipe					2.00	each	754.00	1508.00
	Toilet paper holder					2.00	each	248.00	496.00
	Soap dish plate					2.00	each	163.00	326.00
	Shower rose (revolving type) (150mm)					2.00	each	269.00	538.00
	Towel rail (600mm long x 20mm dia)					2.00	each	338.00	676.00
	cover of WC with flexible connection pipe					2.00	each	577.00	1154.00
10	19.15	Providing and fixing stainless steel drain jali of approved make/quality.				8.00	each	51.00	408.00
11	19.16	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):							
	1	25 mm nominal bore				2.00	each	436.00	872.00
	2	32 mm nominal bore.				2.00	each	510.00	1020.00
12	19.51	Constructing masonry Chamber 60x60x75 cm, inside with modular well burnt clay bricks of 35 kg/ cm <sup>2</sup> in cement mortar 1:4 (1 cement : 4 coarse sand) for fire hydrants, with C.I. surface box 350x350 mm top and 165 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) necessary excavation foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick finished with a floating coat of neat cement				2.00	each	4356.00	8712.00

19.42	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for					1000.00	litre	7.30	7300.00
-------	---	--	--	--	--	---------	-------	------	---------

TOTAL = 86502.00

Say Rs.=



Asstt. Engineer  
Municipal Corporation  
Korba (C.G.)



Sub Engineer  
Municipal Corporation  
Korba (C.G.)