

# कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

711/निर्माण/2024

सिस्टम टेंडर, नं. 155001

कोरबा दिनांक 18.06.2024

## द्वितीय ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकिकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है।

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि,	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	दरी जेन अंतर्गत वार्ड 52 में फर्टिलाइजर बस्ती में राजू घर से रमेश घर तक फिरत कश्यप घर से समारु घर तक मेन रोड इतवारी बाजार से सामुदायिक भवन तक स्वास्थ्य केंद्र से एन.टी.पी.सी. प्लांट रोड तक सी.सी. रोड एवं नाली का निर्माण कार्य। (15 <sup>वें</sup> वित्त आयोग)	25.00	18800/-	04. माह	750/-	वर्ग डी एवं प्रवर श्रेणी	04.07.2024 से

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक् से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (फाटर्नरशीप डीडी) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, शिगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
  - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
  - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
  - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कशकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में पलाई एश ब्रिक का उपयोग किया जाता अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपोजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा प्रपत्र फार्म -ए की कड़िका 11 अनुसार एस्कलेशन देय नहीं होगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।


प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को [uad.cg.gov.in](http://uad.cg.gov.in) में अपलोड करने हेतु प्रेषित।

कार्यपालक अभियंता  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)

**Date-Time Detail(s)**

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		18.06.2024	10.00	18.06.2024	11.00	Release Tender
2		Bid Submission	18.06.2024	10.00	03.07.2024	17.30	
3		Physical Document Submission	18.06.2024	15.00	04.07.2024	15.00	
4	Tender Open		04.07.2024	16.00	-	-	

  
**EXECUTIVE ENGINEER**  
**KORBA (CG)**  
 For, Commissioner Korba (C.G.)

**TENDER/NIT HEADER DETAIL**

ORGANIZATION NAME Urban Administration and Development Department (UADD) PROCUREMENT CATEGORY WORKS

TENDER NO. 155001 TENDER DEALING OFFICER ARUN KUMAR, SHARMA (DFLT)

NUMBER OF ITEMS ALREADY 1 MATCHING NO

ATTACHED CURRENCY INR - INDIAN RUPEE TENDER CATEGORY PERCENTAGE

NIT TYPE RESTRICTED TENDER OFFICE/DIVISION (PWD) COMMISSIONER, MUNICIPAL CORPORATION, KORBA

VRNDQR CLASS A, B, C, D NAME SECTION/CIRCLE (PWD) TENDER SECTION

PROBABLE AMOUNT OF 2500000.00

CONTRACT (PAC) (INR) MUNICIPAL CORPORATION, KORBA

DIVISION / DISTRICT NAME

DESCRIPTION F.No. 711/Const./Darri Zone/2024/KMC

DETAILED DESCRIPTION Construction of CC ROAD From Partilizer Basti Near Raju House to Ramesh's Firat Kashyap to samara near Uttar House Neat Shiv mandir Mainroad Itwari Bazar to Samudayik Bhawan Near up Swasthya Kendra to NTPC Plant Road and RCC Drain near Safiq Mirja House To Maheshwari Godam And Culvert Near Maheshwari Godam And Uttara House Partilizer Basti At Ward No 52.

IS AUCTION ENABLED? N BID PART NUMBER 1

NUMBER OF BID PART(S) 2

**ATTRIBUTE (S)**

ATTRIBUTE NAME	ATTRIBUTE VALUE
BID VALIDITY PERIOD (in days)	120
Tender / Work Completion Time (in months)	04 (VALUE)
Required Past Technical Experience	As per NIT/ Tender Document
Required Financial Turnover (in INR)	AS PER NIT
Required Bid Capacity (in INR)	AS PER NIT

**PAYMENT DETAILS**

DETAILS	
Tender/Processing/Bid Fees	N/A
END/Bid Security	18800.00 INR

**DATE-TIME DETAIL(S)**

BID SUBMISSION START Jun 18, 2024 10:00:07:AM BID DUE DATE Jul 3, 2024 05:30:15:PM

DATE Jul 4, 2024 04:00:25:PM PHYSICAL DOC SUBMISSION Jul 4, 2024 03:00:07:PM

BID OPEN DATE (SCHEDULED) Jul 4, 2024 04:00:25:PM END DATE

**PRE-BID DISCUSSION DETAILS**

PRE-BID DISCUSSION NOT REQUIRED

**ALTERNATE BID DECRYPTOR(S)**

USER DETAILS
MR BUYER ADMIN (DFLT)
- MANORANJAN SARKAR (DFLT)
- Mitresh Verma (DFLT)
- Ratikumar Maheshwari (DFLT)
- ARUN KUMAR SHARMA (DFLT)
- Bhushan Ram Oraon (DFLT)
- Vinod kumar Sandilya (DFLT)

**TERM AND CONDITION DETAIL(S) SPECIAL TERM(S)**

SL. NO.	CATEGORY	DESCRIPTION
1	SPECIAL TERM(S)	SPECIAL TERM(S) As per NIT/ Tender Document

**TENDER SPECIFIC REQUIRED ATTACHMENT(S)**

**Envelcp B**

SL. NO.	SUPPORTING DOCUMENT NAME	MANDATORY	ALLOW EXEMPTION	GROUP
1	REGISTRATION CERTIFICATE (ANY GOVT DEPT IN CHHATTISGARH)	YES	NO	OTHER
2	PARTNERSHIP DEED/MOA OF COMPANY (IF REQUIRED)	YES	NO	OTHER
3	DECLARATION OF NOT BEING BLACK LISTED	YES	NO	OTHER

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)**  
**DETAILED ESTIMATE**


Name of Work :- CONSTRUCTION OF CC ROAD From Fertilizer Basti Near Raju House to Ramesh & Firat Kashyap to Samar, Near Uttara House Near Mamta Kundu House Near Shiv Mandir, Main Road Itwari Bazar to Samudayik Bawan Near Up Swasthya Kendra to NTPC Plant Road and RCC Drain Near Safiq Mirja House to Maheshwari Godam and culvert Near Maheshwari Godam and Uttara House Fertilizer Basti At Ward No. 52

As per Sor :- Schedule of Rates Public Works Department [ PWD BUILDING 01-01-2015]

Sno.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of								
	In all types of soil					150			
	near safiq mirja house to maheshwari godam	1	300	1	0.5				
	culvert near maheshwari godam	1	10.00	1.50	0.50	7.50			
	fertilizer basti near raju house to ramesh & firat kashyap to samaru	2	30.00	3.20	0.20	38.40			
	culvert near Uttara house fertilizer basti	2	6.00	1.50	0.80	14.40			
	near up swasthya kendra to ntpc plant road	1	160.00	3.20	0.20	102.40			
						312.70	Cum	185.00	57249.50
2	Demolishing stone rubble masonry including arches, stacking of serviceable material and disposal of unserviceable material within 50 Metres lead.								
	In cement mortar	2x2	6.00	0.30	0.60	4.32	Cum	527.00	2276.64
3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.								
	In cement mortar.	2X2	300.00	0.20	0.40	96.00	Cum	263.00	25248.00
4	Demolishing cement concrete including disposal of material within 50 metre lead.								
	1:3:6 or richer mix	1	300.00	0.80	0.15	36.00			
		2X2	6.00	0.30	0.60	4.32			
						40.32	Cum	549.00	22135.68
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	near safiq mirja house to maheshwari godam	1	300.00	0.70	0.15	31.50			
		2	300.00	0.15	0.40	36.00			
		335	0.50	0.70	0.10	11.73			
	culvert near maheshwari godam	1	10.00	1.30	0.20	2.60			
		2	10.00	0.20	0.60	2.40			
		1	10.00	1.20	0.20	2.40			
	culvert near Uttara house fertilizer basti	1	6.00	1.30	0.20	1.56			
		2	6.00	0.20	0.60	1.44			
		1	6.00	1.20	0.20	1.44			
		1	6.00	1.00	0.15	0.90			
		2	6.00	0.15	0.60	1.08			
						93.05	Cum	4163.00	387346.34

Sno.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
6	Providing and fixing M.S. grill of approved pattern made of M. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.					60.00	kg	67.50	4050.00
7	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	335	0.50	0.70	0.10	11.73	Cum	469.00	5499.03
8	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
	Thermo-Mechanically treated bars FE 415					5600.00	Cum	54.50	305200.00
9	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).								
	near safiq mirja house to maheshvari godam	1	300.00	0.80	0.10	24.00			
	fertilzer basti near raju house to ramesh & firat kashyap to samaru	2	30.00	3.30	0.10	19.80			
	near utara house fertilzer basti	2	6.00	1.50	0.10	1.80			
	near up swasthya kendra to ntpc plant road	1	169.00	3.20	0.10	54.08			
						99.68	Cum	2659.00	265049.12
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	fertilzer basti near raju house to ramesh & firat kashyap to samaru	2	30.00	3.00	0.15	27.00			
	fertilzer basti near alag ram to near huleshvar	1	35.00	3.50	0.10	12.25			
	fertilzer basti near huleshvar to rati ram to	1	60.00	3.50	0.10	21.00			
	fertilzer basti near rati ram to anand ram	1	30.00	3.50	0.10	10.50			
	near utara house fertilzer basti	1	120.00	4.00	0.10	48.00			
	near mamta kundu house to near shiv mandir	1	200.00	3.00	0.10	60.00			
	main road near itwari bazar to samudaik bhawan	1	190.00	3.00	0.10	57.00			
	near up swasthya kendra to ntpc plant road	1	169.00	3.00	0.15	76.05			
						311.80	Cum	4073.00	1269961.40
10	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	Foundations, footings, base of columns and plinth beam in any shape and size.								
		2	300		0.15	90			
		4	300		0.4	480			
		2	10		0.2	4			
		4	10		0.6	24			
		2	35		0.15	10.5			
		12	3		0.15	5.4			

No.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
		2	6		0.2	2.4			
		4	6		0.6	14.4			
		2	6		0.15	1.8			
		4	6		0.6	14.4			
		2	200		0.1	40			
		80	3		0.1	24			
		2	190		0.1	38			
		80	3		0.1	24			
		2	170		0.15	51			
		68	3		0.15	30.6			
						854.50	Sqm	139.00	118775.50
	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
		1	10.00	0.80		8			
		1	22.40		0.20	4.48			
		1	6.00	0.80		4.8			
		1	14.40		0.20	2.88			
						20.16	Sqm	235.00	4737.60
11	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
		2	300.00	0.20	0.50	60.00			
		2	10.00	0.15	0.50	1.50			
		2	6.00	0.15	0.60	1.08			
						62.58	Cum	65.00	4067.70
12	Carriage by mechanical transport upto 5 km lead:								
	Earth					250.12	Cum	111.00	27763.32
<b>As per SOR Total Estimate Amount Rs.</b>									<b>2,499,959.82</b>
<b>Say Rs</b>									<b>2,500,000.00</b>

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Asst. Engineer  
 Municipal Corporation  
 Korba (C.G.)