

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 135/2024

सिस्टम टेंडर नं.153399

कोरबा दिनांक 27.02.2024

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 एवं विद्युत (01.06.2020) से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 29 पोडीबहार में चंद्रा समाज के सामुदायिक भवन के पास न.पा.नि. कोरबा द्वारा निर्मित सामुदायिक भवन के उपर हॉल निर्माण (विधायक मद)	25.00	18800/-	4 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	21.03.2024 से

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीडी) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संचारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्क्यूरीटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाइंग एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो गांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं राशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा प्रपत्र फार्म -ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यालय अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		26.02.2024	15.00	27.02.2024	15.00	Release Tender
2		Bid Submission	27.02.2024	15.00	20.03.2024	17.30	
3		Physical Document Submission	27.02.2024	15.00	21.03.2024	15.00	
4	Tender Open		21.03.2024	16.00	--	--	



EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

TENDER/NIT HEADER DETAIL

ORGANIZATION NAME	Urban Administration and Development Department (UADD)	PROCUREMENT CATEGORY	WORKS
TENDER NO.	153399	TENDER DEALING OFFICER	- MANORANJAN SARKAR (EE)
NUMBER OF ITEMS ALREADY ATTACHED	2	MATCHING	NO
CURRENCY	INR - INDIAN RUPEE	TENDER CATEGORY	MIXED PERCENTAGE ITEM RATE
NIT TYPE	RESTRICTED TENDER	OFFICE/DIVISION (PWD)	COMMISSINOR, MUNICIPAL CORPORATION, KORBA
VENDOR CLASS	A, B, C, D	NAMES	TENDER SECTION
PROBABLE AMOUNT OF CONTRACT (PAC) [INR]	1022568.00	SECTION/CIRCLE (PWD)	
DIVISION / DISTRICT NAME	MUNICIPAL CORPORATION, KORBA	NAME	
DESCRIPTION	F.No. 135/Constr. / Kosabadi Zone/2024/KMC		
DETAILED DESCRIPTION	Construction of Hall above Community Building near the community building of Chandra Samay Built by N.P.N. Korba in Ward. No. 29 Podibahar.		
IS AUCTION ENABLED?	N	BID PART NUMBER	1
NUMBER OF BID PART(S)	2		

ATTRIBUTE (S)

ATTRIBUTE NAME	ATTRIBUTE VALUE
BID VALIDITY PERIOD (in days)	120
Tender / Work Completion Time (in months)	4 (VALUE)
Required Past Technical Experience	As per NIT/ Tender Document
Required Financial Turnover (in INR)	AS PER NIT
Required Bid Capacity (in INR)	AS PER NIT

PAYMENT DETAILS

DETAILS	
Tender/Processing/Bid Fees	N/A
EMD/Bid Security	18800.00 INR

DATE-TIME DETAIL (S)

BID SUBMISSION START DATE	Feb 27, 2024 07:30:01:PM	BID DUE DATE	Mar 20, 2024 05:30:10:PM
BID OPEN DATE (SCHEDULED)	Mar 21, 2024 04:00:20:PM	PHYSICAL DOC SUBMISSION END DATE	Mar 21, 2024 03:00:33:PM

PRE-BID DISCUSSION DETAILS

PRE-BID DISCUSSION NOT REQUIRED

ALTERNATE BID DECRYPTOR (S)

USER DETAILS
MR BUYER ADMIN (DFLT)
- ram kumar sahu (DFLT)
- MANORANJAN SARKAR (DFLT)
- Mitresh Verma (DFLT)
- ARUN KUMAR SHARMA (DFLT)
- Bhushan Ram Craon (DFLT)
- Vinod kumar Sandilya (DFLT)

TERM AND CONDITION DETAIL (S) - SPECIAL TERM (S)

SL. NO.	CATEGORY	DESCRIPTION
1	SPECIAL TERM(S)	SPECIAL TERM(S) As per NIT/ Tender Document

TENDER SPECIFIC REQUIRED ATTACHMENT (S)

Envelop B

SL. NO.	SUPPORTING DOCUMENT NAME	MANDATORY	ALLOW EXEMPTION	GROUP
1	REGISTRATION CERTIFICATE (ANY GOVT DEPT IN CHHATTISGARH)	YES	NO	OTHER
2	PARTNERSHIP DEED/MOA OF COMPANY (IF REQUIRED)	YES	NO	OTHER
3	DECLARATION OF NOT BEING BLACK LISTED	YES	NO	OTHER
4	LIST OF TECHNICAL STAFF DETAIL	YES	NO	OTHER
5	GST CERTIFICATE FROM CHHATTISGARH	YES	NO	OTHER
6	INCOME TAX CLEARANCE CERTIFICATE	YES	NO	OTHER

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Name of Work : CONSTRUCTION OF HALL ABOVE COMMUNITY BUILDING NEAR THE COMMUNITY BUILDING OF CHANDRA SAMAJ BUILT BY N.P.N. KORBA IN WARD NO-29 PODI BAHAR
 As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1	In all types of soils.								
		-stage	6	1.50	1.50	2.00	27.00			
		-for dome	2x6	1.20	1.20	1.20	20.73			
		-p.b	2	19.00	0.40	0.40	6.08			
			2	12.00	0.40	0.40	3.84			
		-for beam	12	1.20	1.20	1.20	20.73			
			2	19.00	0.50	0.50	9.50			
			2	12.00	0.50	0.50	6.00			
		-for gate	3	1.50	1.50	1.50	10.12			
							Total	104.00	cum	185.00
										19240.00
2	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.								
	3.3	In cement mortar.								
			6	1.50	0.20	1.00	1.80			
							Total	1.80	cum	263.00
										473.40
3	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
	1.1	Foundations, footings, bases of columns plinth beam,								

REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
	curtain wall in any shape and size and all type of wall below plinth level.								
	-f2	6x4	1.20		0.30	8.64			
	-f3	6x4	0.80		0.40	7.68			
	-col b.pl.	6	1.00		9.00	54.00			
	-p.b	2x2	11.70		0.30	14.04			
		2x2	4.50		0.30	5.40			
	-for i beam	12x4	0.80		0.80	30.72			
		2x2	19.00		0.30	22.80			
		2x2	13.00		0.30	15.60			
	-for gate	3x4	1.20		0.40	5.76			
	-f3	3	1.60		0.40	1.92			
	-p.b.	2x1	6.00		0.30	3.60			
					Total	170.16	sqm	139.00	23652.24
1.5	Columns, Pillars, Piers and likes- rectangular or square in shape								
	-for stage	5	1.00		3.50	17.50			
	-col. for gate	3	1.60		4.00	19.20			
					Total	36.70	sqm	297.00	10899.90
1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
		1	12.50	5.10		63.75			
					Total	63.75	sqm	235.00	14981.25
1.8	Beams, lintels, cantilevers & walls								
		2x2	4.50		0.30	5.40			
	-back	1x2	11.70		0.30	7.02			
	-front	1x2	11.70		0.50	11.70			
	-tie beam	1x2	4.50		0.50	4.50			
	-for gate	1x2	6.00		0.30	3.60			
		1	6.00	0.30		1.80			
					Total	34.02	sqm	202.00	6872.04
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.							
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).							

REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		6	1.50	1.50	0.10	1.35			
		1	11.70	4.50	0.10	5.26			
					Total	6.61	cum	2659.00	17575.99
1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		1	6.00	3.00	0.15	2.70			
					Total	2.70	cum	4073.00	10997.10
5	3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
	2.1 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	-f1	6	1.50	1.50	0.30	4.05			
	-f2	6	1.20	1.20	0.40	3.45			
	-f3	6	0.80	0.80	0.40	1.53			
	-col. b.p.l	6	0.20	0.30	0.90	0.32			
	-p.b.	2	11.70	0.20	0.30	1.40			
		2	4.50	0.20	0.30	0.54			
	-col. above plinth	5	0.30	0.20	3.00	0.90			
	-s.b	1	11.70	0.20	0.30	0.70			
		1	11.70	0.20	0.50	1.17			
		2	4.50	0.20	0.30	0.54			
	-sus beam	1	4.50	0.20	0.50	0.45			
	-slab beam	1	12.30	5.10	0.13	8.15			
	-for I-beam f1	12	1.20	1.20	0.60	10.36			
	-f2	12	0.60	0.60	0.60	2.59			
	-beam	2	19.00	0.20	0.30	2.28			
		2	12.00	0.20	0.30	1.44			
	-for gate f1	3	1.50	1.50	0.30	2.02			
	-f2	3	1.20	1.20	0.40	1.72			
	-col. b.p.l.	3	0.40	0.40	0.40	0.19			
	-p.b.	1	6.00	0.40	0.40	0.96			
	-col.	3	0.40	0.40	3.00	1.44			
	-beam	1	6.00	0.20	0.30	0.36			
					Total	46.56	cum	4163.00	193829.28
6	3.12 Providing and placing in position reinforcement for								


REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
	R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:									
12.1	Thermo-Mechanically treated bars FE 415									
		46.56	90.00			4190.40				
						Total	4190.40	kg	54.50	228376.80
7	7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:									
	5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand)									
		1	11.70	0.20	3.00	7.02				
	-stair step	2	1.50	1.20	0.15	0.54				
		2	1.50	0.90	0.15	0.40				
		2	1.50	0.60	0.15	0.27				
		2	1.50	0.30	0.15	0.13				
		1	6.00	0.20	0.50	0.60				
						Total	8.96	cum	3263.00	29236.48
8	7.6 Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:									
							7.72			
							0.60			
						Total	8.32	cum	121.00	1006.72
9	9.2 Structural steel work riveted or bolted or welded in built-up sections, trusses and frames work upto a height of 5m above plinth level, including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.									
	-I-Beam 200x100=25kg/mtr	12	6.00	25.00		1800.00				


REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		2	19.00	25.00		950.00			
						Total			
10	12.9					2750.00	Kg	66.00	181500.00
	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.								
	9.3 AMMENDMENT(NO-650/086 DT 20-09-2016) Crazy ceramic tile flooring with under layer 12 mm thick cement mortar 1:4 (1-cement : 4 coares cement) with joint not exceeding 5 mm , including filling the gaps with ordinary cement mixture and mixing with sythetick polyster fibers tringular in shape having specific gravity of 1.34 top 1.40 cross section size ranging from 10 to 40 micron and length up to 6 mm mixing fiber @125 gram per 52 kg of cement in cement mortar includig providig af mixig water profig material I mortar 1 kg per 50 kg of cement, all complete as per directio of Egieer-I Chrрге.								
	-for floor	1	20.00	12.00		240.00			
		1	9.00	4.00		36.00			
	- for stair	2	1.50	2.00		6.00			
						Total			
						282.00	sqm	386.00	108852.00
11	11.1								
	Providing and making 6mm thick cement plaster of mix:								
	1.2								
	In Cement mortar 1:4 (1 cement : 4 fine sand)								
		1	12.50	5.10		63.75			

REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT	
						Total	63.75	sqm	87.00	5546.25
12	11.2									
	2.4									
		1	11.70			3.50		40.95		
		2	11.70			1.00		23.40		
		2	4.50			1.00		9.00		
	-stage col.	2	1.00			4.00		8.00		
	gate col.	3	1.60			4.00		19.20		
						Total	100.55	sqm	91.50	9200.32
13	11.3									
	3.4									
		1	11.70			3.50		40.95		
						Total	40.95	sqm	107.00	4381.65
14	12.13									
	13.1									
		1	11.70		4.60			53.82		
						Total	53.82	sqm	1151.00	61946.82
15	9.1									

REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
						400.00			
					Total	400.00	kg	61.50	24600.00
16	14.13								
	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.								
						400.00			
					Total	400.00	sqm	94.50	37800.00
17	14.12								
	Applying one coat of cement primer on wall surface (applied @ 0.80 litrs/10 sqm) complete.								
						400.00			
					Total	400.00	sqm	23.00	9200.00
18	14.15								
	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	15.1								
	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
						400.00			
					Total	400.00	sqm	56.00	22400.00

As per Estimate Amount Rs. 1022568.24
Say Rs.


Sub Engineer
Nagar Palik Nigam,
Korba


Aast. Engineer
Nagar Palik Nigam,
Korba


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


DETAILED ESTIMATE

Name of Work :- वार्ड क्र. 29 पोड़ीबहार में नगर पालिक निगम, कोरबा द्वारा निर्मित चंद्रा समाज के सामुदायिक भवन के पास सामुदायिक भवन के ऊपर हॉल निर्माण।

As per Sor :- Item Rate

Sno.	ITEM DESCRIPTION	Unit	Qty	Rate	Amount
1	Excavation of Works Contract for self supporting roof on your following building of dimensions as mentioned below shed : (a) Span : 12.00 MTR (Actual) (b) Arch Rise : 1.50 MTR (c) Length : 19.00 MTR (With Projection) (d) Arch Length : 13.40 Mtr (e) No of Bays : 1 No. (f) Area Per Bay : 10 Mtr (g) Building Height : 5.00 Mtr Material Specification : Imported Color Coated Galvalume Sheet : BMT : 1.10 mm APT : 1.15 mm Tolerance : +/- 0.02 mm Coil width : 912 mm Tolerance : +/- 4mm ALZ 150 GMS, 350 Tensile strength Original Embossing of lable with make.	SQM	254.72		


Sub-Engineer
Municipal Corporation
Korba (C.G.)


Asst. Engineer
Municipal Corporation
Korba (C.G.)

Executive Engineer
Municipal Corporation
Korba (C.G.)