



कार्यालय, नगर पालिक निगम, कोरवा (छ.प्र.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरवा (छ.प्र.)

बालको नगर जोन

फा.क्र./2064,2066,2067,2068,2070,2076 एवं 2077/निर्माण (बालको नगर जोन)/2024-25/

कोरवा, दिनांक 18.11.2024

द्वितीय निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत राक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयुक्त दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल निविदा वेबसाइट से डाउनलोड कर मुहरबंद लिफाफा में निविदा आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - 06.12.2024 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 06.12.2024 सायंकाल 4:30 बजे

क्र.	कार्य का नाम	प्राक्कलन राशि में	घरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्र. 42 दशहरा मैदान शिवनगर में बाउण्ड्रीवाल निर्माण कार्य। (अधोसंरचना मद वर्ष 2024-25) द्वितीय निविदा	5,00,000/-	5,000 /-	750/-	Form-A	03 माह	राक्षम श्रेणी	06.12.2024
2	वार्ड क्र. 34 बेलगिरी बस्ती में अमर सिंह होटल के पास मुक्तिधाम निर्माण कार्य। (प्रभारी मंत्री मद वर्ष 2024-25) द्वितीय निविदा	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	राक्षम श्रेणी	06.12.2024
3	वार्ड क्र. 35 न्यू शांतिनगर में सी.सी. रोड व नाली निर्माण कार्य। (प्रभारी मंत्री मद वर्ष 2024-25) द्वितीय निविदा	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	राक्षम श्रेणी	06.12.2024
4	वार्ड क्र. 38 शासकीय प्राथमिक शाला सेक्टर 04 में अहाता निर्माण कार्य। (जिला खनिज संस्थान न्यास मद वर्ष 2024-25) द्वितीय निविदा	7,09,000/-	5,500 /-	750/-	Form-A	04 माह	राक्षम श्रेणी	06.12.2024
5	वार्ड क्र. 42 शासकीय प्राथमिक शाला शिवनगर (बीच मोहल्ला) में अहाता निर्माण कार्य। (जिला खनिज संस्थान न्यास मद वर्ष 2024-25) द्वितीय निविदा	2,97,600/-	3,000 /-	750/-	Form-A	03 माह	राक्षम श्रेणी	06.12.2024
6	वार्ड क्र. 35 नगर पालिक निगम कोरवा द्वारा निर्मित वरिष्ठ जन हेतु अनुभव भवन बालकोनगर के प्रथम तल में हॉल निर्माण। (विधायक मद वर्ष 2024-25) द्वितीय निविदा	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	राक्षम श्रेणी	06.12.2024
7	वार्ड क्र. 35 राधा कृष्ण मंदिर हाउसिंग बोर्ड कालोनी के पास बालको स्थित नगर पालिक निगम कोरवा द्वारा निर्मित सामुदायिक भवन के प्रथम तल का निर्माण कार्य। (विधायक मद वर्ष 2024-25) द्वितीय निविदा	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	राक्षम श्रेणी	06.12.2024

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से भेजना होगा अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला-कोरवा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरवा के वेबसाईट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनांक तक समस्त संशोधनों के साथ) आयुक्त, नगर पालिक निगम, कोरवा के नाम पर देय निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा मुहरबंद लिफाफा में मान्य किया जावेगा जो निम्नानुसार होगा:-
 - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित निविदा प्रपत्र शुल्क का डीडी, निविदाओं में निविदाकार को फिजिकल दस्तावेज के साथ निविदा सूचना प्रसारित होने के पश्चात् राशि रु. 100/- के स्टॉम्प पर निष्पादित शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्य की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरवा के नाम पर देय होगा प्रस्तुत करना होगा।
 - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफे होंगे तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम, कोरवा के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम, कोरवा के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले 03 वित्तीय वर्षों का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. (जीवित) पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधिसंगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना ठेकेदार के हस्ताक्षर सहित निविदा दस्तावेजों के साथ प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिका स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंको में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध निविदा शर्तानुसार एवं मेयर इन काउंसिल के निर्णयों के अनुरूप कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरवा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रकृति के कार्यों को छोड़कर शेष कार्यों के देयकों से 5 प्रतिशत की दर से पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्क्यूरिटी के रूप में रोकी जायेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य

- पूर्णता तिथि से किया जायेगा। उक्त समयवाधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित राशि रु. 100/- नॉन ज्यूडिशियल स्टॉम्प पेपर पर निष्पादित शपथ पत्र निविदा दस्तावेजों के साथ संलग्न करना अनिवार्य होगा।
 19. ईंट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त, नगर पालिक निगम कोरवा का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
 23. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
 24. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
 25. ठेकेदार द्वारा संपादित किये गए कार्यों के देयको का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
 26. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
 27. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।


(ठेकेदार के हस्ताक्षर)

नाम

पूर्ण पता

.....

मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरवा (छ.ग.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
ABSTRACT

Name of Work **CONSTRUCTION OF HALL IN FIRST FLOOR FOR SINIOR CITIZEN AT ANUBHAW BHAWAN BALCO NAGAR**
 S per SOR : **CONSTRUCTED BY NAGAR PALIK NIGAM KORBA AT WARD NO 35**
SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	sqm	32	7.20	230.40
2	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.				
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	14.59	185.00	2,699.15
			cum	0.95	371.00	352.45
4	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	0.95	2659.00	2,526.05
5	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	3237.3	54.50	176,432.85
6	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	10.12	139.00	1,406.68
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	56.32	297.00	16,727.04
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	82.04	235.00	19,279.40
	1.8	Beams, lintels, cantilevers & walls	sqm	45.92	202.00	9,275.84
	1.15	Stair cases of all types excluding spiral and folded plate type, including risers and landings	sqm	15.72	230.00	3,615.60
7	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	29.43	4163.00	122,517.09
8	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	26.71	3263.00	87,154.73

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
11.2	Providing and making 12mm thick cement plaster of mix:				
2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)				
10 11.5	Neat Cement punning	sqm	181.86	91.50	16,640.19
11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:	sqm	11.52	33.00	380.16
3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)				
12 11.1	Providing and making 6mm thick cement plaster of mix:	sqm	177.78	107.00	19,022.46
1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)				
13 14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	76.88	87.00	6,688.56
14 14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:	sqm	425	94.50	40,162.50
15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	425	56.00	23,800.00
15 10.11	Supply and fixing of pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	sqm		636.00	
16 12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.				
13.1	Size 600x600mm				
17 12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.	sqm	91.04	1151.00	104,787.04
7.1	Size upto 200x300mm				
18 12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.	sqm	15.6	587.00	9,157.20
9.1	Size 300x300mm	sqm	10	692.00	6,920.00

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.				
20	57.2 SS Grade 304	kg	140	525.00	73,500.00
9.51	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall be paid in basic item):				
21	51.1 With float glass panes of 4 mm thickness	sqm	10.8	611.00	6,598.80
9.58	Extra for providing and fixing tinted glass panes in aluminium door, window, ventilator shutters and partitions instead of float glass.				
22	58.1 4 mm thickness	sqm	8.64	107.00	924.48
9.54	Providing and fixing anodized aluminium framed grill (minimum anodic coating of grade AC 15) of approved shape, pattern and design including cutting, bending, hoisting and erecting/ fixing to door, window frame or to wall with fixing clips or hold fasteners or bolts and nuts as required etc. complete.	kg	10	396.00	3,960.00
23	9.47 Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved shade according to IS: 1868, minimum anodic coating shall be of grade AC-15 (Glazing to be paid for separately).				
24	17.1 For fixed portion	0	130	331.00	43,030.00
7.23	Extra for brick work, where height of work exceeds 4.0 metre from immediate below floor level.	cum	20.58	94.50	1,944.81
25	3.4 Extra for laying PCC/RCC of any grade in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	15.71	97.50	1,531.72
26	8.12 Providing and fixing flush door shutters, conforming to IS : 2202 (Part-I), decorative type core of block board construction with frame of first class hard wood and well matched teak ply veneering with vertical grains or cross bands and face veneers on both faces of shutters excluding hinges.				
27	12.2 35 mm. thick (single leaf)	sqm	3.78	2005.00	7,578.90
9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	270	75.00	20,250.00
28	14.22 Painting on new work (two or more coats) to give an even shade with:				
29	22.1 Satin synthetic enamel paint	sqm	24.84	55.00	1,366.20
18.4	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :				

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1.1	White pedestal type	each	2	2882.00	5,764.00
18.13	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:				
13.1	Flat back half stall urinal of size 460x380x250mm	each	2	1776.00	3,552.00
13.3	Wall corner type urinal of sizes 340x410x265mm	each	2	1659.00	3,318.00
31.18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				
17.1	White Size 550x450 mm	each	3	1430.00	4,290.00
32.18.25	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				
25.1	32 mm dia				
33.18.30	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing :	each	2	68.50	137.00
30.1	5mm thick mirror				
34.18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.	sqm	2	2016.00	4,032.00
76.2	110 mm dia pipe.				
35.18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.	metre	23	267.00	6,141.00
77.5	"P" trap 110mmx110mm long				
77.6	Nahani trap 110x75mm	each	2	227.00	454.00
36.19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.	each	2	90.50	181.00
INTERNAL WORK - EXPOSED ON WALL					
4.1	15 mm nominal outer dia .Pipes.	metre	33	110.00	3,630.00
4.3	25 mm nominal outer dia .Pipes.	metre	20	199.00	3,980.00
37.19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:				
14.1	Bib cock (400 grams)	each	4	382.00	1,528.00
14.4	Piller Cock (400 grams)	each	3	398.00	1,194.00
14.6	Stop cock (concealed) (600 grams)	each	3	494.00	1,482.00
14.7	Angle valve for basin mixer and geyser points (450 grams)	each	5	382.00	1,910.00
4.15	Shower rose (revolving type) (150mm)	each	2	269.00	538.00
.16	Towel rail (600mm long x 20mm dia)	each	2	338.00	676.00
38.19.42	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow	1000.00	7.30		7,300.00

REF ITEM DESCRIPTION

39

3.1

pipes but without fittings and the base support for tank
 Providing and laying nominal mix plain cement concrete with crushed
 stone aggregate using concrete mixer in all works upto plinth level
 excluding cost of form work.

UNIT QTY RATE AMOUNT

1.5

1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm
 nominal size).


cum 6.3 4073.00 25,659.90

As per Estimate Amount Rs. 906227.20

Add Electrification (+) 93800.

1000027.20

say Rs 10,00,000



S/E

Nagar Palik Nigam
 Korba(C.G.)



A.E.

Nagar palik Nigam
 korba(C.G.)