

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 623/2025

सिस्टम टेंडर नं. 167012

कोरबा दिनांक 11.04.2025

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्चरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र Form-A में निविदा आमंत्रित की जाती है:-

1. फिजिकल सबमिशन लिफाफा प्राप्त होने की अंतिम तिथि — 08.05.2025 सायंकाल से 3.00 बजे तक
2. निविदा खुलने की अंतिम तिथि — 08.05.2025 सायंकाल 4.00 बजे से

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (डिमांड ड्राफ्ट)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क. 46 अयोध्यापुरी तालाब में जल संवर्धन हेतु निर्माण (पंचरी,सीसी रोड गहरीकरण) (प्रभारी मंत्री मद)	25.00	18800/-	04 माह	750/-	वर्ग डी एवं प्रवर श्रेणी	08.05.2025 से

शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र, पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
 - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट एवं निर्धारित प्रारूप में शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से आयुक्त,नगर पालिक निगम,कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा के पते पर भेजना होगा। निर्धारित तिथि को सायं 03:00 बजे के पश्चात् फिजिकल सबमिशन लिफाफा स्वीकार नहीं किया जायेगा।
 - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निर्धारित प्रारूप में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात् का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
 - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का डिमांड ड्राफ्ट जो कि आयुक्त, नगर पालिक निगम,कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
7. ईट से संबंधित निर्माण कार्यों में प्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
8. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
9. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईड डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
10. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
11. निविदा प्रपत्र फार्म -ए की कंडिका 11 Price Adjustment (एस्कलेशन) देय नहीं होगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।
15. ठेकेदार द्वारा संपादित किए गए कार्यों के देयकों का भुगतान कार्य विशेष हेतु बजट आबंटन एवं राशि उपलब्ध होने पर किया जाएगा।
16. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
17. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
18. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		11.04.2025	15.30	11.04.2025	15.30	Release Tender
2		Bid Submission	11.04.2025	15.30	07.05.2025	17.30	
3		Physical Document Submission	11.04.2025	15.30	08.05.2025	15.00	
4	Tender Open		08.05.2025	16.00	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE


Name of Work :- Construction of 2 nos Ghat at Ayodhyapuri pond ward no. 46


As per Sor :- Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

Sno.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
1	1.1 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	1.1.1 In all types of soils.								
		1	10	6	0.9	54.00			
		2	10	0.6	0.9	10.80			
		1	10	9	0.9	81.00			
		2	10	0.6	0.9	10.80			
				Total		156.60	cum	185	28971
2	1.17 Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
		1	156.60		0.7	109.62			
				Total		109.62	cum	65	7125.3
3	1.18 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		1	10	6	0.1	6.00			
		2	7.5	0.6	0.1	0.9			
		1	10	7.5	0.1	7.50			
		2	10	0.6	0.1	1.20			
				Total		6.90	cum	371	2559.9
4	3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								

3.2 Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.								
5	1	10	6	0.1	6			
	2	10	0.6	0.1	1.2			
	1	10	7.5	0.1	7.50			
	2	10	0.6	0.1	1.20			
				Total	15.9	cum	2970	17211
3.2.1 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
	1	10	1	0.4	4			
	1	10	7.5	0.12	9			
	7	7.5	1	0.15	7.88			
	2	10	0.2	0.6	2.40			
	1	10	1.2	0.5	6			
	1	10	6.5	0.12	7.8			
	6	7.5	1	0.15	6.75			
side railing	2	10	0.2	0.4	1.60			
	3	10	0.2	0.1	0.60			
	2	5	0.2	0.1	0.20			
				Total	46.23	cum	4163	192434.675
3.12 Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
6	3.12.1 Thermo-Mechanically treated bars FE 415				2311.3			
	50kg/cum				Total	2311.3	Kg	54.5
7	Providing and making 6mm thick cement plaster of mix:							
	In Cement mortar 1:4 (1 cement : 4 fine sand)							
	3	10		1	30			
	6	10		0.15	9			
	2	10		1.2	24			
	3	10		1	30			
	6	9.5		0.15	8.55			
	2	10		1.2	24			
				Total	63	sqm	87	5481

2.1 Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:									
2.1.1 Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below 9 plinth level.									
	2	10							
	6	10		1	20				
	4	10		0.15	9				
	2	10		0.6	24				
	6	10		1.2	24				
	4	10		0.15	9				
				0.6	24				
				Total	110	sqm	139	15290	
3.10 Extra for laying PCC/ RCC, in or under water or liquid mud including cost of pumping or bailing out of water and removing slush etc. complete									
		46.23			46.23	cum	261	12064.725	
10 Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in:									
Cement Mortar 1:6 (1 cement : 6 coarse sand)									
	2	10.50	0.20	1.20	5.04				
				Total	5.04	Cum	3350	16884	
11 15mm thick cement plaster on the rough side of single or half brick wall of mix:									
In Cement Mortar 1:6 (1 cement : 6 fine sand)									
	4	10		1.2	48				
	4	9		1	36				
				Total	84	Sqm	113	9492	
As per SOR Total Estimate Amount Rs.								463488.73	


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE

Work :- Construction Of C.C. Road from SLRM centre to Ayodhyapuri pond

16 Schedule of Rates Public Works Department [PWD BUILDING 01-01-2015]

ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
1 Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
	2	275	1.8		990			
	2	65	1.8		234			
				Total	1224	Sqm	7.2	8812.8
2 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), In all types of soil								
	2	275	1.5	0.35	288.75			
	2	65	1.5	0.35	68.25			
				Total	357	cum	185	66045
3 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
	2	275	1.5	0.1	82.5			
	2	65	1.5	0.1	19.5			
				Total	102	cum	371	37842
4 Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
1:3:6 (1 cement : 3coarse sand : 6graded stone aggregate 40mm nominal size).								
	2	275	1.5	0.1	82.5			
	2	65	1.5	0.1	19.5			
				Total	102	cum	2970.00	302940

	and fixing formwork, centering, shuttering, staging, propping bracing complete and including its							
		3	275		0.15	123.75		
		120	1.5		0.15	27		
		3	65		0.15	29.25		
		35	1.5		0.15	7.875		
					Total	187.88	Sqm	119.00
								26114.625
6	Providing and laying nominal mix Plain cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.							
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm)							
		2	275	1.5	0.2	165		
		2	65	1.5	0.2	39		
					Total	204	Cum	4073
								830892
8	1.26 Carriage by mechanical transport upto 5 km lead;							
	1.26.1 Earth	1.00	357.00		0.80	285.60	Cum	111.00
	1.19 Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.							
	Side shoulder (local Earth)	2.00	242.00	1.00	0.20	96.80		
		2.00	58.00	1.00	0.20	23.20		
						120.00	cum	242.00
								29040.00
	As per SOR Total Estimate Amount Rs.							1333388.03


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.) DETAILED ESTIMATE


Deeping of pond at Ayodhyapuri pond ward no. 46

Schedule of Rates Public Works Department [FWD BUILDING 01-01-2018]

ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
					750.00			
				Total	750.00	Sqm	7.20	5400.00
2 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
In all types of soil	4	50.00	2.50	0.40	200.00			
	4	30.00	2.50	0.40	120.00			
	4	50.00	2.50	0.40	200.00			
	4	30.00	2.50	0.40	120.00			
	4	50.00	2.50	0.40	200.00			
	1	50.00	50.00	0.40	1000.00			
				Total	1840.00	cum	185.00	340400.00
1.1 Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
1.1.2 In ordinary rocks.	2	50.00	2.50	0.25	62.50			
	2	30.00	2.50	0.25	37.50			
	2	50.00	2.50	0.25	62.50			
	2	30.00	2.50	0.25	37.50			
	1	50.00	40.00	0.25	500.00			
				Total	700.00	cum	267.00	186900.00

1.1 For lead for every 30 m free lead and 1.5 m port thereof and upto								
1.2 In ordinary rocks.					1840.00	cum	33.00	60720.00
1.7 Extra rate for quantity of work executed in or under water and/ or liquid mud including pumping out water.					700.00	cum	49.50	34650.00
	1840.00		0.80	1472.00	cum	51.00	75072.00	
As per SOR Total Estimate Amount Rs.								703142.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)