



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

दर्री जोन

फा.क्र./733,734,737 एवं 738/निर्माण (दर्री जोन)/2024/

कोरबा, दिनांक 20.09.2024

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 & PWD Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल निविदा वेबसाइट से डाउनलोड कर बंद लिफाफा के माध्यम से आमंत्रित की जाती है :-

- निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने की अंतिम तिथि - 07.10.2024 सायंकाल 3:00 बजे तक
- निविदा खुलने की अंतिम तिथि - 07.10.2024 सायंकाल 4:30 बजे

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यविधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
01	वार्ड क्र. 47 कुमगरी नीचेपारा में मुक्तिधाम निर्माण कार्य। (प्रभारी मंत्री मद 2024-25) (द्वितीय निविदा)	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	सक्षम श्रेणी	07.10.2024
02	वार्ड क्र. 48 नागिन भाठा स्वास्थ्य केन्द्र के बगल में सामुदायिक भवन निर्माण कार्य। (प्रभारी मंत्री मद 2024-25) (द्वितीय निविदा)	10,00,000/-	7,500 /-	750/-	Form-A	04 माह	सक्षम श्रेणी	07.10.2024
03	वार्ड क्र. 52 अंतर्गत नीलगिरी बस्ती में मेन रोड से दीपांकर चक्रवर्ती, विनोद घर से दिलीप सिंह एवं दिलीप सिंह से देवांगन घर तक आर.सी.सी. नाली का मरम्मत कार्य। (मरम्मत एवं संधारण मद) (द्वितीय निविदा)	3,93,000/-	4,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	07.10.2024
04	वार्ड क्र. 52 अंतर्गत नीलगिरी बस्ती में मेन रोड से कृष्णाकांत साहू के घर तक तथा विजय मल्लिक के घर से नवधा पण्डाल तक सी.सी. रोड का मरम्मत कार्य। (मरम्मत एवं संधारण मद) (द्वितीय निविदा)	3,94,000/-	4,000 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	07.10.2024

निविदा की शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से भेजना होगा अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, आई.टी.आई. चौक साकेत भवन, जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनोंक तक समस्त संशोधनों के साथ) आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा मुहरबंद लिफाफा में मान्य किया जावेगा जो निम्नानुसार होगा:-
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में

उल्लेखित अन्य दस्तावेज के साथ निर्धारित निविदा प्रपत्र शुल्क का डीडी, निविदाओं में निविदाकार को फिजिकल दस्तावेज के साथ निविदा सूचना प्रसारित होने के पश्चात् राशि रु. 100/- के स्टॉम्प पर निष्पादित शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्य की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।

- (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
 (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफे होंगे तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम, कोरबा के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम, कोरबा के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
 6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले 03 वित्तीय वर्षों का आय चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. (जीवित) पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधिसंगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना ठेकेदार के हस्ताक्षर सहित निविदा दस्तावेजों के साथ प्रस्तुत करना अनिवार्य होगा।
 7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
 8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
 9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिका स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
 10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
 11. ठेकेदार को अपनी दरें शब्दों एवं अंको में लिखना अनिवार्य होगा।
 12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
 13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
 14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध निविदा शर्तानुसार एवं मेयर इन काउंसिल के निर्णयों के अनुरूप कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
 15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
 16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत की दर से सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रकृति के कार्यों को छोड़कर शेष कार्यों के देयकों से 5 प्रतिशत की दर से पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्किरिटी के रूप में रोकी जायेगी। सुरक्षा राशि एवं परफार्मेंस गारंटी राशि वापसी हेतु समयावधि की गणना कार्य पूर्णता तिथि से किया जायेगा। उक्त समयावधि में निर्माण कार्य की भौतिक स्थिति सही होने तथा सक्षम प्राधिकारी के संतुष्टि के आधार पर भुगतान किया जायेगा।
 17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
 18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित राशि रु. 100/- नॉन ज्यूडिशियल स्टॉम्प पेपर पर निष्पादित शपथ पत्र निविदा दस्तावेजों के साथ संलग्न करना अनिवार्य होगा।
 19. ईट से संबंधित निर्माण कार्यों में फ्लाइंग एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
 20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
 21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त, नगर पालिक निगम कोरबा का निर्णय अंतिम एवं सर्वमान्य होगा।
 22. निविदा में सफल निविदाकार को ऐसे कार्य जिसकी अनुबंध राशि 10.00 लाख या उससे अधिक है, उनको प्रत्येक कार्यों हेतु पृथक से छ.ग. भवन और सन्निर्माण कर्मचार मण्डल का पंजीयन प्रमाण पत्र प्रस्तुत करना अनिवार्य होगा अन्यथा देयक भुगतान किया जाना संभव नहीं होगा।
 23. कार्य क्रियान्वयन से संबंधित गुणवत्ता परीक्षण संबंधी रिपोर्ट पर होने वाले व्यय का वहन संबंधित ठेकेदार द्वारा किया जावेगा।
 24. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गए प्रावधानों का पालन करना अनिवार्य होगा।
 25. ठेकेदार द्वारा संपादित किये गए कार्यों के देयको का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जाएगा।
 26. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।

//03//

27. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

प्रतिलिपि :- प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नया रायपुर (छ.ग.) को Uad.cg.gov.in में अपलोड किये जाने हेतु प्रेषित।

(ढेकेदार के हस्ताक्षर)

नाम

पूर्ण पता


मोबाईल नं.-


कार्यपालन अभियंता
नगर पालिक निगम
कोरवा (छ.ग.)

ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
Foundations, footings, base of columns lintel beam in any shape and size.									
		10x4	1.4		0.2	11.2			
		10x2	0.35		0.9	6.3			
		10x2	0.35		0.9	6.3			
		2	28		0.3	16.8			
					Total	40.6	Sqm	139.00	5643.40
b	Columns, Pillars, Piers and likes- rectangular or square in shape								
		10x4	0.35		3.9	54.6			
		4x4	0.2		1.2	3.84			
					Total	58.44	Sqm	297.00	17356.68
c	Beams, lintels, cantilevers & walls								
	top beam	1	28		0.4	11.2			
		1	28		0.35	9.8			
		2	6		0.5	6			
		2	6		0.35	4.2			
					Total	31.2	Sqm	202.00	6302.40
d	2.1.7 Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
		1	9	7		63	Sqm	235.00	14805.00
7	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal								
		10	1.4	1.4	0.35	6.86			
		10	0.35	0.35	5.2	6.37			
		1	28	0.2	0.3	1.68			
	slab beam	1	28	0.35	0.4	3.92			
		2	5	0.35	0.5	1.75			
	slab	1	9	7	0.12	7.56			
					Total	28.14	Cum	4163.00	117146.82
8	Providing and laying nominal Plain cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		4	9	1.5	0.15	8.1	cum	4073.00	32991.30

ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
9	Binding and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire								
	Thermo-Mechanically treated bars					110 kg/cum		3100.00	
					Total	3100.00	Kg	54.50	168950.00 ✓
10	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in:								
	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
		1	28	0.3	0.8	6.72			
					Total	6.72	Cum	3350.00	22512.00 ✓
11	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
		1	8	6	0.35	16.8			
					Total	16.8	cum	65.00	1092.00 ✓
12	12mm thick cement plaster of mix:								
	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
		10X4	0.35		4.9	68			
		2	28	1	0.6	33.6			
					Total	101.6	Sqm	96.50	9804.40 ✓
13	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	14.15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm	10X4	0.35		5.2	72.8			
		1	10	10.3		103			
					Total	175.8	sqm	56.00	9844.80 ✓

ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
14	49 25 mm thick KOTA stone slab over 20mm (Average) thick base cement mortar 1:4 laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including grinding rubbing and polishing etc. complete (Area of slab to be over 0.20 sqm and upto 0.50 sqm) sqm 897.00	1	8	6		48.00	Sqm	897.00	43056.00
15	Providing filling and compacting local earth (from approved source pit) in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.[ITEM NO. 1.19]	1	8	6	0.3	14.40	cum	242.00	3484.80
16	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					175.8			
		10X4	0.35		5.2	72.8			
		1	10	9		90			
					Total	162.80	sqm	94.50	15384.60
As per SOR Total Estimate Amount Rs.									499910.72
Part B- Boundarywall Around muktidham Rs.									499948.18
Total Estimate Amount									999858.90
Say Amount Rs.									1000000.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE**


Work :- Construction Of Boundary wall Muktidham At ward no.47
per Sor :- Schedule of Rates Public Works Department (PWD BUILDING 01-01-2015)


Sno.	ITEM DESCRIPTION	N	L	B	H/D	Qty	Unit	Rate	Amount
1	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).								
		1	120	1.2		150			
					Total	175	Sqm	18	3150
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.								
	In all types of soil	42	1.2	1.2	1.2	72.576			
		1	112	0.4	0.4	17.92			
					Total	90.496	cum	185	16741.76
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.								
		42	1.2	1.2	0.05	3.024			
		1	112	0.4	0.05	2.24			
					Total	5.264	cum	371	1952.944
4	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.								
5	1:3:6 (1 cement : 3coarse sand : 6graded stone aggregate 40mm nominal size).								
		42	1.2	1.2	0.08	4.8384			
		1	112	0.4	0.08	3.584			

ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
		1	15	2.5	0.08	3			
					Total	11.4224	cum	2970.00	33924.522
6	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:								
7	Foundations, footings, base of columns and plinth beam in any shape and size.								
		42x4	1		0.2	33.6			
		42x2	0.2		0.9	15.12			
		42x3	0.3		0.9	22.68			
		2	112		0.25	56			
					Total	127.4	Sqm	139.00	17702.5
8	Columns, Pillars, Piers and likes-rectangular or square in shape								
		42x2	0.2		1.3	21.84			
		42x2	0.3		1.3	32.76			
					Total	54.6	Sqm	297	16215.2
9	Beams, lintels, cantilevers & walls								
	top beam	2	120		0.2	48			
					Total	48	Sqm	202	9696
10	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		42	1	1	0.2	8.4			
		42	0.2	0.3	2.6	6.552			
		1	120	0.2	0.3	7.2			
	top beam	1	120	0.2	0.2	4.8			
					Total	26.952	Cum	4163	112201.18
11	Providing and laying nominal Plain cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.								
a	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).								
		1	25	2.5	0.15	9.375	cum	4073	38184.375

ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
11	Providing and placing in position reinforcement for R.C.C. work including strapping, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:								
	Thermo-Mechanically treated bars					55kg/cum			
						1500.00			
					Total	1500.00	Kg	54.5	81750
12	Brick work with modular fly-ash lime bricks (FALG Bricks) conforming to IS:12894-2002 of class designation 40 in foundation and plinth in:								
	Cement Mortar 1:6 (1 cement : 6 coarse sand)								
		1	120	0.2	1.2	28.8			
					Total	28.8	Cum	3350	96480
13	Extra for brick work in superstructure:								
	Above plinth and upto floor five level.					26			
					Total	26	Cum	121	3146
14	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
		1	120	0.3	0.25	9			
					Total	27	cum	65	1755
15	15mm thick cement plaster on the rough side of single or half brick wall of mix:								
	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
		1	120		1.4	168			
					Total	168	Sqm	113	18984
16	12mm thick cement plaster of mix:								
	In Cement Mortar 1:6 (1 cement : 6 fine sand)								
		1	120	1	1.4	168			
		1	100	0.2		20			
					Total	188	Sqm	96.5	18142
17	Painting on new work (two or more coats) to give an even shade with:								
		2	3.6		2.1	15.12			

ITEM DESCRIPTION		N	L	B	H/D	Qty	Unit	Rate	Amount
					Total	15.12	Sqm	55	831.6
18	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.								
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1				151			
					Total	151	kg	68.00	10268
19	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								
	14.15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm	2	120		1.4	336			
					Total	336	sqm	56.00	18816
As per SOR Total Estimate Amount Rs.									499948.18
Say Amount Rs.									500000.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asst. Engineer
 Municipal Corporation
 Korba (C.G.)