



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

टी.पी. नगर जोन

फा.क्र./251, 252, 254, 255/निर्माण (टी.पी. नगर)/2024/

कोरबा, दिनांक 22.07.2024

## निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों के क्र. 01 के भाग-अ, क्र. 02, 03 हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित PWD Building SOR 01.01.2015 एवं कार्य क्र. 01 के भाग-ब हेतु PWD Electrical SOR 01.06.2020 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर श्रेड्युल अनुसार आयटम दरों पर निविदा प्रपत्र Form-A में तथा क्र. 04 हेतु आयटम दर पर निविदा प्रपत्र Form-B निम्नलिखित निर्माण कार्य हेतु मैन्युअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

| क्र. | कार्य का नाम  | प्राक्कलन राशि में | घरोहर राशि रु में | निविदा प्रपत्र का मूल्य | निविदा प्रपत्र | कार्यावधि | ठेकेदार का वर्ग | निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि | निविदा खुलने की अंतिम तिथि |
|------|---|--------------------|-------------------|-------------------------|----------------|-----------|-----------------|--|----------------------------|
| 1.   | इंडियन कॉफी हाउस के पास कामर्शियल काम्प्लेक्स में रूम एवं टायलेट का मरम्मत एवं रेनोवशन कार्य (मरम्मत एवं संधारण मद, प्रथम निविदा)         | 2,12,000/-         | 2,150/-           | 750/-                   | Form-A         | 02 माह    | सक्षम श्रेणी    | 13.08.2024   | 14.08.2024                 |
| 2.   | वार्ड क्र. 15 ढोढीपारा अंतर्गत संजय किराना घर से सरिता जैन घर तक सी.सी. रोड एवं नाली का मरम्मत कार्य (मरम्मत एवं संधारण मद, प्रथम निविदा) | 3,92,000/-         | 3,950/-           | 750/-                   | Form-A         | 03 माह    | सक्षम श्रेणी    | 13.08.2024   | 14.08.2024                 |
| 3.   | वार्ड क्र. 13 अंतर्गत सामुदायिक मंच महावीर चौक के पास अतिरिक्त सुविधा का विस्तार/प्रदाय कार्य भाग-अ (पार्षद मद 2023-24, प्रथम निविदा)     | 4,70,000/-         | 4,700/-           | 750/-                   | Form-A         | 03 माह    | सक्षम श्रेणी    | 13.08.2024   | 14.08.2024                 |
| 4.   | टी.पी. नगर कोरबा अंतर्गत राजीव गांधी ऑडिटोरियम में 200 के.व्ही.ए. डी.जी. सेट का मरम्मत कार्य। (मरम्मत एवं संधारण कार्य, प्रथम निविदा)     | 1,98,939/-         | 2,000/-           | 750/-                   | Form-B         | 02 माह    | सक्षम श्रेणी    | 13.08.2024   | 14.08.2024                 |

### निविदा की शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा के दस्तावेज हाथों-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
- निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र Form - A/B/ABC (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-  
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं निविदाओं में निविदाकार को फिजिकल दस्तोवज के साथ निविदा सूचना जारी होने के पश्चात दिनांक का शपथ पत्र जिसमें संबंधित कार्य का नाम एवं कार्ड की निविदा क्रमांक अंकित हो प्रेषित करना अनिवार्य होगा एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोश में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।  
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।  
(स) तृतीय लिफाफा में उपरोक्त दोनों लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, शपथ पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना कर्मांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।

8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वभाव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्कुरिटी के रूप में रोकी जावेगी। मरम्मत कार्य हेतु मात्र सुरक्षा राशि की कटौती की जावेगी।
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथ पत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में प्लाई ऐश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा प्रपत्र From-A के क्लाज नंबर-11 अनुसार एस्केलेशन देय नहीं होगा।
23. ठेकेदार को निर्माण कार्य के दौरान "निर्माण एवं अपशिष्ट प्रबंधन नियम 2016" में किये गये प्रावधानों का पालन करना अनिवार्य होगा।
24. ठेकेदार द्वारा संपादित किये गये कार्यों के देयकों का भुगतान बजट आबंटन और राशि उपलब्ध होने पर किया जावेगा।
25. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
26. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

**नोट:-**

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

पृष्ठा.क्र./251, 252, 254, 255/निर्माण (टी.पी. नगर)/2024/  
प्रतिलिपि :-

कोरबा, दिनांक 22.07.2024

1. प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, मंत्रालय अटल नगर नया रायपुर (छ.ग.) को [uad.cg.gov.in](http://uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।

हस्ताक्षर \_\_\_\_\_  
फर्म का नाम \_\_\_\_\_  
पता \_\_\_\_\_  
मोबाईल नंबर \_\_\_\_\_

कार्यपात्र अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)**

**ABSTRACT**

**Name of Work :- Maintenance and Renovation Work of Room and Toilet At Professional Complex**

**As per Sor :- Schedule of Rates Public Works Department [ PWD BUILDING 01-01-2015]**


| S.No. | ITEM DESCRIPTION  | Qty    | Unit | Rate    | Amount   |
|-------|---|--------|------|---------|----------|
| 1     | Removing white or colour wash by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete.   |        |      |         |          |
|       |   | 266.63 | Sqm  | 4.30    | 1146.51  |
|       |   |        |      |         |          |
|       | Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :   |        |      |         |          |
|       | Thickness upto 15mm   |        |      |         |          |
|       |   | 139.82 | Sqm  | 132.00  | 18456.24 |
|       |   |        |      |         |          |
| 7     | Providing and applying 2mm thick ready mix exterior grade putty (manufactured with cow dung processing) on walls to make the surface smooth and even.   |        |      |         |          |
|       |   | 266.63 | Sqm  | 101.00  | 26929.63 |
|       |   |        |      |         |          |
| 8     | Painting exterior surface with SMOOTH exterior emulsion paint manufactured with the cow dung processing to give protective and decorative finish including cleaning washing of surface etc. complete with.  |        |      |         |          |
|       | On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over  | 103.88 | Sqm  | 79.00   | 8206.52  |
|       | Wall painting with premium emulsion (plastic) manufactured with the cow dung processing emulsion panit of required shade to give an even shade.   |        |      |         |          |
|       | On new work (Two or more coats)   |        |      |         |          |
|       |   | 162.75 | Sqm  | 69.00   | 11229.75 |
|       |   |        |      |         |          |
|       | 12.13 Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. |        |      |         |          |
|       | Size 600x600mm  |        |      |         |          |
|       |   | 38.62  | Sqm  | 1151.00 | 44451.62 |
|       |   |        |      |         |          |

| S.No | ITEM DESCRIPTION   | Qty    | Unit | Rate    | Amount     |
|------|--|--------|------|---------|------------|
|      | 12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.   |        |      |         |            |
|      | Size upto 200x300mm  |        |      |         |            |
|      |  | 12.30  | Sqm  | 587.00  | 7220.10 ✓  |
|      | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.   |        |      |         |            |
|      |  | 148.00 | Kg   | 75.00   | 11100.00 ✓ |
|      | 9.23 Providing and fixing frosted glass panes with steel glazing clips and special metal sash putty of approved make in steel doors, windows, ventilators:   |        |      |         |            |
|      | 5 mm thick   |        |      |         |            |
|      |  | 5.76   | sqm  | 717.00  | 4129.92 ✓  |
|      | 9.47 Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved shade according to IS: 1868, minimum anodic coating shall be of grade AC 15 |        |      |         |            |
|      | For fixed portion  |        |      |         |            |
|      |  | 60.00  | Kg   | 331.00  | 19860.00 ✓ |
|      | For shutter of doors, windows & ventilators including providing and making provision for fixing of fitting wherever required including the cost of PVC/ neoprene gasket required (Fittings shall be paid for separately).  |        |      |         |            |
|      |  | 40.00  | Kg   | 338.00  | 13520.00 ✓ |
|      | 8.12 Providing and fixing flush door shutters, conforming to IS : 2202 (Part-I), decorative type core of block board construction with frame of first class hard wood and well matched teak ply veneering with vertical grains or cross bands and face veneers on both faces of shutters excluding hinges.   |        |      |         |            |
|      | 35 mm. thick (single leaf)   |        |      |         |            |
|      |  | 2.52   | sqm  | 2005.00 | 5052.60 ✓  |

| S.No | ITEM DESCRIPTION  | Qty  | Unit | Rate    | Amount  |
|------|---|------|------|---------|---------|
|      | <p>Providing and fixing 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for styles and 15x15mm for top &amp; bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5mm thick heat moulded PVC 'C' channel of size 30mm thickness, 70mm width out of which 50mm shall be flat and 20mm shall be tapered in 45degree angle on either side forming styles; and 5mm thick, 95mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided either side of the panel. 10mm (5mm x 2 ) thick, 20mm wide cross PVC sheet be provided as gap insert for top rail &amp; bottom rail. paneling of 5mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles &amp; rails with 7mm (5mm+2mm) thick x 15mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5mm thick PVC strip of 20mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per Manufacturer's specification including 3 nos ISI marked stainless steel hinges of size 100x58x1.9 mm complete. (for W.C. and bathroom door shutter).</p> |      |      |         |         |
|      | PVC door shutter  | 1.89 | sqm  | 2318.00 | 4381.02 |
|      | Providing and fixing bright finished brass butt hinges with brass polished MS screws complete:  |      |      |         |         |
|      | 100x85x5.50 mm (Heavy Type)   | 6.00 | each | 195.00  | 1170.00 |
|      | 8.60 Providing and fixing bright finished brass sliding door bolt with nuts and brass polished MS screws complete:  |      |      |         |         |
|      | 250x16mm  | 2.00 | each | 344.00  | 688.00  |
|      | 8.62 Providing and fixing bright finished brass tower bolts (barrel type) with brass polished MS screws complete:   |      |      |         |         |
|      |   | 2.00 | each | 231.00  | 462.00  |
|      | 8.65 Providing and fixing bright finished brass door handles with brass polished MS screws complete:  |      |      |         |         |
|      | 125 mm  | 4.00 | each | 55.50   | 222.00  |

| S.No | ITEM DESCRIPTION  | Qty   | Unit  | Rate    | Amount  |
|------|---|-------|-------|---------|---------|
| 36   | Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.   |       |       |         |         |
|      | 110 mm dia pipe.  | 10.00 | metre | 267.00  | 2670.00 |
| 37   | Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.   |       |       |         |         |
|      | Tee/ Tee with door/ Bend 45°/ Bend 90°  |       |       |         |         |
|      | 110 mm  | 2.00  | each  | 154.00  | 308.00  |
|      | Vent cover  |       |       |         |         |
|      | 110 mm  | 1.00  | each  | 44.00   | 44.00   |
|      | Access door cap   |       |       |         |         |
|      | 110 mm  | 2.00  | each  | 59.00   | 118.00  |
|      | "P" trap 110mmx110mm long   | 2.00  | each  | 227.00  | 454.00  |
| 30   | 18.4 Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :  |       |       |         |         |
|      | White pedestal type   | 1.00  | each  | 2882.00 | 2882.00 |
| 31   | Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:   |       |       |         |         |
|      | Flat back half stall urinal of size 460x380x250mm   | 1.00  | each  | 1776.00 | 1776.00 |
| 33   | Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :  |       |       |         |         |
|      | White Size 550x450 mm   | 1.00  | each  | 1430.00 | 1430.00 |
| 38   | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. CONCEALED WORK including cutting chases and making good the walls etc. |       |       |         |         |
|      | 15 mm nominal outer dia .Pipes.   | 15.00 | metre | 133.00  | 1995.00 |
|      | 32 mm nominal outer dia .Pipes.   | 10.00 | metre | 284.00  | 2840.00 |
| 40   | Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:  |       |       |         |         |
|      | Bib cock (250 grams)  | 4.00  | each  | 185.00  | 740.00  |
|      | Stop cock (350 grams)   | 2.00  | each  | 237.00  | 474.00  |
| 41   | Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):   |       |       |         |         |
|      | 32 mm nominal bore.   | 1.00  | each  | 510.00  | 510.00  |

| S.No | ITEM DESCRIPTION   | Qty    | Unit  | Rate  | Amount           |
|------|--|--------|-------|---|------------------|
| 42   | Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank | 500.00 | litre | 7.30  | 3650.00          |
|      |  |        |       |   |                  |
|      |  |        |       | <b>Total Ammount</b>                                    | 198116.91        |
|      |  |        |       | <b>For Electrification Work (P.W.D. SOR 01.06.2020)</b> | 13872.00         |
|      |  |        |       |   | 211988.91        |
|      |  |        |       | <b>Say Amount Rs.</b>                                   | <b>212000.00</b> |

  
**Sub Engineer**  
**Municipal Corporation**  
**Korba (C.G.)**

  
**Asst. Engineer**  
**Municipal**  
**Corporation**