



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

बांकीमोंगरा एवं सर्वमंगला नगर जोन

फा.क्र./670 से 677/निर्माण (बांकीमोंगरा एवं सर्वमंगला नगर जोन)/2022/

कोरबा, दिनांक 26.05.2022

## निविदा आमंत्रण की सूचना

नगर पालिक निगम कोरबा द्वारा लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्यों हेतु मैनुअल निविदा वेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 17.06.2022 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 17.06.2022 सायंकाल 4:30 बजे से

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क. 62 में हनुमान मोहल्ला धरमपुर से बघेल गुरुजी से आखरी मकान तक सी.सी.रोड एवं नाली निर्माण कार्य। (पार्षद मद 2021-22)	7,00,000/-	5,300 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	17.06.2022
2	वार्ड क. 60 अंतर्गत मोंगरा भाटा मुख्य माग (चैन दास घर) से हेमंत दास घर तक नाली एवं रोड निर्माण कार्य। (पार्षद मद 2021-22)	6,98,000/-	5,300 /-	750/-	Form-A	03 माह	सक्षम श्रेणी	17.06.2022
3	वार्ड क. 59 अंतर्गत विकास नगर के समीप सांस्कृतिक मंच संधारण व अन्य सुविधा बाबत। (एल्डरमेन मद 2020-21)	6,00,000/-	5,000 /-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.06.2022
4	स्वच्छता सर्वेक्षण- 2022 के अंतर्गत वार्ड क. 67 में एस.एल.आर.एम.सेन्टर का उन्नयन एवं विकास कार्य। (मरम्मत संधारण मद)	3,91,241/-	4,000 /-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.06.2022
5	स्वच्छता सर्वेक्षण-2022 के अंतर्गत वार्ड क. 66 मैगजीनमाटा में एस.एल.आर.एम.सेन्टर का उन्नयन एवं विकास कार्य। (मरम्मत संधारण मद)	3,89,238/-	4,000 /-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.06.2022
6	वार्ड क. 56 अंतर्गत पंखादफाई 02 नं. दफाई बस्ती स्थित एस.एल.आर.एम.सेन्टर का पोताई एवं मरम्मत कार्य। (मरम्मत संधारण मद)	3,75,000/-	3,750 /-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.06.2022
7	वार्ड क. 59 अंतर्गत वैशाली नगर में एस.एल.आर.एम.सेन्टर का पोताई एवं मरम्मत कार्य। (मरम्मत संधारण मद)	3,62,000/-	3,650 /-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.06.2022
8	वार्ड क. 60 अंतर्गत बरपाली दशहरा मैदान के पास एस.एल.आर.एम.सेन्टर का पोताई एवं मरम्मत कार्य। (मरम्मत संधारण मद)	3,50,000/-	3,500 /-	750/-	Form-A	02 माह	सक्षम श्रेणी	17.06.2022

### निविदा की शर्तें:-

1. निविदा दरें प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।

2. निविदा के दस्तावेज हाथों-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाइट [www.korbamunicipal.in/uad.cg.gov.in](http://www.korbamunicipal.in/uad.cg.gov.in) डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
  - (अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी (निविदा आमंत्रण पत्र जारी दिनांक के पश्चात् का मान्य) एवं अमानत राशि का टी. डी.आर./एफ.डी.आर. जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
  - (ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
  - (स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा हेतु इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीडी) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय चुकता प्रमाण पत्र, पैन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क्र. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है, तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।
14. कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
15. सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ. डी.आर./टी.डी.आर. ऑफिस अथवा टाईम डिपॉजिट जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
16. सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयकों के साथ 01 वर्ष हेतु साथ ही मरम्मत एवं संधारण प्रवृत्ति के कार्यों को छोड़कर 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्क्यूरिटी के रूप में रोकी जावेगी। (मरम्मत संधारण मद के कार्यों को छोड़कर)
17. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदअंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
18. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र कंडिका क्र. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
19. ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
20. निविदा प्रपत्र अहस्तातरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार आयुक्त, नगर पालिक निगम के पास सुरक्षित रहेगा।
23. निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

प्रतिलिपि :- प्रोग्रामर संचालनालय, नगरीय प्रशासन एवं विकास विभाग, नवा रायपुर छ.ग. को [www.uad.cg.gov.in](http://www.uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।

(ठेकेदार के हस्ताक्षर)

नाम .....

पूर्ण पता .....

कार्यपालन अभियंता  
नगर पालिक निगम  
कोरबा (छ.ग.)

# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

## DETAILED ESTIMATE

Painting and Maintenance Work of SLRM Centre at Vaishali Nagar at Ward No. - 59

As per SOR: Schedule of rates public works department [PWD BUILDING - 01.01.2015] (PART A)

S. N.	SOR Ref.	ITEM DESCRIPTION	NO.	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.								
	2	1:3:6 or richer mix								
			2	3.85	2.80	0.05	1.078			
						Total=	1.078	Cum	549.00	591.82
2	17.1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :								
	1	Thickness upto 15mm								
			20	1.50		0.90	27.00			
			52	0.90		0.60	28.08			
			32	1.20		0.50	19.20			
			10	1.80		1.20	21.60			
			88	0.30		0.30	7.92			
						Total=	103.80	Sqm	132.00	13701.60
3	14.45	Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to scratches etc. complete.					600.08	Sqm	5.20	3120.42
4	14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.								
	1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)					384.80	Sqm	41.00	15776.80
5	14.9	Distemping with acrylic washable distemper to give an even shade.								
	1	On new work (Two or more coats)					215.28	Sqm	38.00	8180.64
6	14.18	Painting on new work (two or more coats) to give an even shade with:								
	1	Satin synthetic enamel paint					6.00	Sqm	55.00	330.00
7	14.23	Painting on old work (one or more coats) to give an even shade with:								
	1	Satin synthetic enamel paint					1764.24	Sqm	35.00	61748.40
8	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.					600.08	Sqm	94.50	56707.56



13	10.12	Supply and fixing of polymer pre-coated galvalume profile sheets (PPGL) of approved size, shape and pitch of corrugation, total coated thickness (TCT) 0.60 mm +/- 5%, epoxy primer on both side of the sheet and colour polyester top coat 18-20 microns and 6-7 microns on bottom. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.								
			1	6.60	4.80		31.68			
						TOTAL=	31.68	Sqm	693.00	21954.24
14	10.16	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws or with polymer coated J or L hooks, bolts and nuts and or G.I. seam bolts and nuts, G.I. plain and bitumen washers complete :								
		1 Ridges plain (500-600mm)								
						TOTAL=	27.80	Rmt	552.00	15345.60
		2 Gutter (600 mm over all Girth)								
						TOTAL=	54.40	Rmt	629.00	34217.60
15	18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.								
		For RAin Water Pipe For SLRM	2	6.00			12.00	rmt	267.00	3204.00
16	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.								
							82.85			
						TOTAL=	82.85	kg	75.00	6213.75

17	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan ),100mm sand cast Iron P or S trap,10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :								
	3	White Orissa pattern W.C. pan of size 580x440 mm								
			1	2.00			2.00	Nos	2899.00	5798.00
18	18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :	1	1.00			1.00	Nos	1203.00	1203.00
19	18.29	Providing and fixing 600x450 mm beveled edge 4mm mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	1	1.00			1.00	Nos	599.00	599.00
20	18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.								
	1	75 mm dia pipe.	1	9.00			9.00	RMT	182.00	1638.00
	2	100 mm dia pipe.	1	12.00			12.00	RMT	267.00	3204.00
21	18.4	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :								
	1	White pedestal type	1	1.00			1.00	Nos	2882.00	2882.00
22	19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
	1	Bib cock (250 grams)	1	4.00			4.00	Nos	185.00	740.00
	3	Stop cock (350 grams)	1	3.00			3.00	Nos	237.00	711.00

23	19.5	Providing and fixing Chlorinated polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. CONCEALED WORK including cutting chases and making good the walls etc.,								
	1	15 mm nominal outer dia .Pipes	1	6.00			6.00	RMT	133.00	798.00
	3	25 mm nominal outer dia .Pipes	1	12.00			12.00	RMT	213.00	2556.00
As per SOR:Schedule of rates public works departmen[PWD ELECTRICAL- 01.06.2020] (PART B)										
24	7.9	Providing and fixing metal clad, SP&N switch fuse unit (re-wirable), 230/250 volts, with porcelain re-wireble fuses including drilling holes on the board, connections, earthing the body etc. as per specification. (Thimbeling shall be paid separately).								
	1	32 amps	1	1.00			1.00	nos	978.00	978.00
25	6.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earthing etc. complete as required. P.F. should be greater than 0.9, with BEE Star rating from 3 star and above, IS: 374:2019 including all amendments.								
	4	1400 mm sweep	1	6.00			6.00	Each	1773.00	10638.00
26	6.58	Supplying, installation, testing and commissioning of Acrylic LED light (a) Specification of Acrylic 3 mm thick x 3 " width x 4 " depth *(imbose) (b) Specification of LED modules :- Each Moduel should have 6 Nos LED of 1 watt	1	5.80	3.60		20.88	Sqft	2312.00	48274.56
27	6.5	Supplying and fixing of wall/ cabin fan including connection etc. as per specification. P.F. should be greater than 0.9								
	1	300 mm sweep	1	2.00			2.00	nos	1387.00	2774.00
28	26.5	Supplying and fixing of following sizes 'B' class G I pipe with all necessary Tee's, bends, sockets in the suction/ delivery line including cutting and threading etc. as required.								
	4	50 mm dia.								
							24.00			
							TOTAL= 24.00	Metre	463.00	11112.00

23.19	Repair of submersible motor parts 100 mm dia meter opening /Rewinding and assembly with testing etc complete and reinstallation including etc								
3	Rewinding of motor upto 2 HP (single phase) waterproof copper winding wire								
		1	1.00			1.00			
					TOTAL=	1.00	Job	2179.00	2179.00
30	23.23	Repairing of control panel board with replacement of contactor kit set capacitors, boost up, condenser etc complete including wiring, fitting, and testing.							
	1	Single phasing preventer							
			1	1.00		1.00			
					TOTAL=	1.00	Job	715.00	715.00

Total= 362000.07

Say Rs.= 362000.00

Sub Engineer  
Municipal Corporation  
Korba (C.G.)

Asstt. Engineer  
Municipal Corporation  
Korba (C.G.)