

# कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क. 1376 / 2024

सिस्टम टेंडर नं. 153907

कोरबा दिनांक 09.03.2024

## ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्युरमेंट (E-Tendering) के माध्यम से निविदा प्रपत्र फार्म A में निविदा आमंत्रित की जाती है :-

क.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि (FDR/TDR)	कार्यावधि	निविदा प्रतिभागी शुल्क (DD)	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	कोसाबाड़ी जोन अंतर्गत वार्ड क 31 रुद्र नगर में सी.सी.रोड एवं नाली का निर्माण कार्य (15वें वित्त)	50.00	37500/-	5 माह	1500/-	वर्ग डी एवं प्रवर श्रेणी	02.04.2024 से .....

शर्तें:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी, विगत 3 वर्षों का आयकर चुकता प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि के FDR/TDR की प्रति ऑनलाईन अपलोड करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड, निविदा प्रतिभागी शुल्क का डिमाण्ड ड्राफ्ट एवं धरोहर राशि FDR/TDR, शपथपत्र का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
  - अमानत राशि का वैध FDR/TDR, निविदा प्रतिभागी शुल्क का DD एवं शपथ पत्र की मूल प्रति लिफाफा में कार्य का नाम एवं अन्य विवरण अंकित कर केवल स्पीड पोस्ट/रजिस्टर्ड डाक के माध्यम से निविदा खुलने की तिथि में दोपहर 3.00 बजे तक आयुक्त, नगर पालिक निगम, कोरबा साकेत भवन, आई.टी.आई.चौक रामपुर कोसाबाड़ी पिन- 495677 कोरबा को उपलब्ध कराना अनिवार्य होगा।
  - निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र (राशि रु. 100/- नॉनज्यूडिशियल स्टाम्प) निविदा आमंत्रण दिनांक के पश्चात का, निविदा क्रमांक एवं कार्य का नाम अंकित करना अनिवार्य होगा।
  - अमानत राशि का FDR/TDR एवं निविदा प्रतिभागी शुल्क का DD जो कि आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो प्रस्तुत करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईंट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा प्रपत्र फार्म -ए की कंडिका 11 अनुसार एस्कलेशन देय नहीं होगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यपालक अभियंता  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)

प्रतिलिपि-

प्रोग्रामर, संचालनालय, नगरीय प्रशासन एवं विकास विभाग, रायपुर को uad.cg.gov.in में अपलोड करने हेतु प्रेषित।

### Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		09.03.2024	15.00	09.03.2024	15.00	Release Tender
2		Bid Submission	09.03.2024	15.00	01.04.2024	17.30	
3		Physical Document Submission	09.03.2024	15.00	02.04.2024	15.00	
4	Tender Open		02.04.2024	16.00	--	--	

W/1  
EXECUTIVE ENGINEER  
KORBA (CG)  
For, Commissioner Korba (C.G.)

**TENDER/HIT HEADER DETAIL**

ORGANIZATION NAME	Urban Administration and Development Department (UADD)	PROCUREMENT CATEGORY	WORKS
TENDER NO.	153907	TENDER DEALING OFFICER	- MANOPANJAN SARYAR (EE)
NUMBER OF ITEMS ALREADY ATTACHED	1	MATCHING	NO
CURRENCY	INR - INDIAN RUPEE	TENDER CATEGORY	PERCENTAGE
NIT TYPE	RESTRICTED TENDER	OFFICE/DIVISION (PWD) NAME	COMMISSIONER, MUNICIPAL CORPORATION, KOREA
VENDOR CLASS	A, B, C, D	SECTION/CIRCLE (PWD) NAME	TENDER SECTION
PROBABLE AMOUNT OF CONTRACT (PAC) [INR]	4999425.00	DESCRIPTION	F.N/1365/Const./Kosabadi Zone/ 2024/YMC
DIVISION / DISTRICT NAME	MUNICIPAL CORPORATION, KOREA	DETAILED DESCRIPTION	Construction of CC Road & RCC Drain from Harki House to Dev Kumar House Rudra Nagar Kharmora Kosabadi Zone W.No. 31
IS AUCTION ENABLED?	N	BID PART NUMBER	1
NUMBER OF BID PART(S)	2		

**ATTRIBUTE(S)**

ATTRIBUTE NAME	ATTRIBUTE VALUE
BID VALIDITY PERIOD (in days)	120
Tender / Work Completion Time (in months)	04 (VALUE)
Required Past Technical Experience	As per tender document /NIT
Required Financial Turnover (in INR)	AS PER NIT
Required Bid Capacity (in INR)	AS PER NIT

**PAYMENT DETAILS**

DETAILS	
Tender/Processing/Bid Fees	N/A
EMD/Bid Security	37500.00 INR

**DATE-TIME DETAIL(S)**

BID SUBMISSION START DATE	Mar 9, 2024 07:30:00:PM	BID DUE DATE	Apr 1, 2024 05:30:40:PM
BID OPEN DATE (SCHEDULED)	Apr 2, 2024 04:00:06:PM	PHYSICAL DOC SUBMISSION END DATE	Apr 2, 2024 03:00:15:PM

**PRE-BID DISCUSSION DETAILS**

PRE-BID DISCUSSION NOT REQUIRED

**ALTERNATE BID DECRYPTOR(S)**

USER DETAILS
MR BUYER ADMIN (DPLT)
- MANOPANJAN SARYAR (DPLT)
- Mitresh Verma (DPLT)
- Ramkumar Maheshwari (DPLT)
- ARUN KUMAR SHARMA (DPLT)
- Bhushan Ram Oraon (DPLT)
- Vinod kumar Sandilya (DPLT)

**TERM AND CONDITION DETAIL(S) - SPECIAL TERM(S)**

SL. NO.	CATEGORY	DESCRIPTION
1	SPECIAL TERM(S)	SPECIAL TERM(S) As per tender document /NIT

**TENDER SPECIFIC REQUIRED ATTACHMENT(S)**

**Envelop B**

SL. NO.	SUPPORTING DOCUMENT NAME	MANDATORY	ALLOW EXEMPTION	GROUP
1	PARTNERSHIP DEED/MOA OF COMPANY (IF REQUIRED)	YES	NO	OTHER
2	DECLARATION FOR NOT BEING BLACK LISTED	YES	NO	OTHER
3	LIST OF TECHNICAL STAFF DETAIL	YES	NO	OTHER
4	GST CERTIFICATE FROM CHHATTISGARH	YES	NO	OTHER
5	DECLARATION FOR NOT ABOVE TOTAL WORK OF REGISTRATION CAPACITY	YES	NO	OTHER
7	REGISTRATION CERTIFICATE (ANY GOVT DEPT IN CHHATTISGARH)	YES	NO	OTHER

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA ( C.G.)**  
**ABSTRACT**

Name of Work **CONSTRUCTION OF CC ROAD & RCC DRAIN FROM NANKI HOUSE TO DEV KUMAR HOUSE RUDRA NAGAR KHARMORA KOSABADI ZONE WARD NO. 31**  
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.2	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	Cum.	1200.00	95.00	114,000.00
2	4.1	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401				
	A	Plant mix method (with Mechanically crushed stone only)				
	(a)	For Lower Sub-base with				
	(i)	Grading-III Material	Cum.	525.00	1423.00	747,075.00
3	4.10	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	Cum	525.00	1434.00	752,850.00
4	6.6	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads)				
	(i)	P.C.C. M-10	Cum	198.00	2789.00	552,222.00
	(iv)	P.C.C. M-30	Cum	297.00	4350.00	1,291,950.00
5	3.20	Construction of RCC open drain				
	(ii)	Construction of RCC open drain 0.60m x 0.60m inside dimension lined with 120 mm thick RCC M-20 walls, 120 mm thick CC M-20 foundation, over 100 mm thick (Av) leveling course in PCC M-15 including excavation , dressing of sides and bottom, provision of HYSD reinforcement consisting 8 mm dia horizontal bars @ 150 mm c/c and L-shaped 8 mm dia vertical bars @ 150 mm c/c (L= 800 mm) including cutting , bending and binding wire, placing in position , providing shuttering and concreting by using concrete mixer, compaction by vibration etc complete as per drawings and technical specifications.	Meter.	539.00	2592.00	1,397,088.00
6	9.2	Providing and laying Reinforced Cement Concrete pipe NP 4 / prestressed concrete pipe on first class bedding (Laying Reinforced cement concrete pipe NP4/prestressed concrete pipe for culverts on first class bedding of granular material including fixing collar with cement mortar 1:2 and bedding as per clause 2904 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets . )				
	D	1200 mm dia	Meter	16.00	9015.00	144,240.00

As per Estimate Amount Rs. **4999425.00**

*Syds 50.50 ladd*

**OFFICE OF THE MUNICIPAL CORPORATION, KORBA ( C.G.)**

**DETAILED ESTIMATE**

Name of Work : CONSTRUCTION OF CC ROAD & RCC DRAIN FROM NANKI HOUSE TO DEV KUMAR HOUSE RUDRA NAGAR KHARMORA KOSABADI ZONE WARD NO. 31

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
1	3.2	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	1	600.00	4.00	0.50	1200.00	Cum.	95.00	114000.00
2	4.1	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401								
	A	Plant mix method (with Mechanically crushed stone only)								
	(a)	For Lower Sub-base with								
	(i)	Grading-III Material	1	600.00	3.50	0.25	525.00	Cum.	1423.00	747075.00
3	4.10	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in	1	600.00	3.50	0.25	525.00	Cum	1434.00	752850.00

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)								
4	6.6	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads)								
	(i)	P.C.C. M-10	1	600.00	3.30	0.10	198.00	Cum	2789.00	552222.00
	(iv)	P.C.C. M-30	1	600.00	3.30	0.15	297.00	Cum	4350.00	1291950.00
5	3.20	Construction of RCC open drain								
	(ii)	Construction of RCC open drain 0.60m x 0.60m inside dimension lined with 120 mm thick RCC M-20 walls, 120 mm thick CC M-20 foundation, over 100 mm thick (Av) leveling course in PCC M-15 including excavation , dressing of sides and bottom, provision of HYSD reinforcement consisting 8 mm dia horizontal bars @ 150 mm c/c and L-shaped 8 mm dia vertical bars @ 150 mm c/c (L= 800 mm) including cutting , bending and binding wire, placing in position , providing shuttering and concreting by using concrete mixer, compaction by vibration etc complete as per drawings and technical specifications.	1	539.00			539.00	Meter.	2592.00	1397088.00
6	9.2	Providing and laying Reinforced Cement Concrete pipe NP 4 / prestressed concrete pipe on first class bedding (Laying								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		Reinforced cement concrete pipe NP4/prestressed concrete pipe for culverts on first class bedding of granular material including fixing collar with cement mortar 1:2 and bedding as per clause 2904 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets . )								
	D	1200 mm dia	1	16.00			16.00	Meter	9015.00	144240.00

As per Estimate Amount Rs. 4999425.00

Say Rs. 50.00 lakh

  
Sub Engineer  
Nagar Palik Nigam,  
Korba

Astt. Engineer  
Nagar Palik Nigam,  
Korba