



# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./988/विद्युत/2022

कोरबा, दिनांक 23.05.2022

## निविदा आमंत्रण सूचना

नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग, छ.रा.वि.मंडल, एवं छत्तीसगढ़ अनुज्ञापन मंडल (विद्युत) में उचित श्रेणी में विद्युतीकरण कार्य हेतु पंजीकृत/लाईसेंसि ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियंता लोक निर्माण विभाग (विद्युत) रायपुर द्वारा दिनांक 01.06.2020 से प्रभावशील दर अनुसूची पर, (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान प्रतिशत दरों पर मैन्युअल निविदा फार्म ए बेबसाइट से डाउनलोड कर त्रि-लिफाफा पद्धति के माध्यम से मुहरबंद निविदाएं आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि	धरोहर राशि	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा दस्तावेज (भाग-अ) खुलने की तिथि	निविदा दर (भाग-ब) खुलने की तिथि
1.	वार्ड क्र.64 घुड़देवा के हाईस्कूल फुटबॉल ग्राउण्ड में प्रकाश व्यवस्था कार्य। (निगम मद)	9,84,720/-	7,400/-	750/-	02 माह	वर्ग अ-श्रेणी	22.06.2022	24.06.2022

शर्त :-

- निविदा दरे प्रचलित एस.ओ. आर. से कम या अधिक प्रतिशत दरों पर दिया जावे एस. ओ. आर. के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र नगर पालिक निगम कोरबा के बेबसाइट : [www.korbamunicipal.in](http://www.korbamunicipal.in) एवं [www.uad.cg.gov.in](http://www.uad.cg.gov.in) से डाउनलोड किया जाकर निर्धारित निविदा प्रपत्र का शुल्क डी.डी. के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य ना किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र/पैन नम्बर पत्र एवं जी.एस.टी. का पंजीयन प्रमाण पत्र प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि प्रस्तुत करना होगा।
- निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा। प्रथम लिफाफे में वांछित दस्तावेज, अमानत राशि का टी.डी.आर./एफ.डी.आर एवं निविदा प्रपत्र के शुल्क का डी.डी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा। द्वितीय लिफाफे में ठेकेदार द्वारा भरा निविदा प्रपत्र होगा। तृतीय लिफाफा में उपरोक्त दोनों लिफाफे होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
- निविदा प्रपत्र उन्ही ठेकेदारों को दिया जायेगा जिन्हें इस प्रकार के कार्यों का अनुभव हो।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 3.00 बजे तक प्राप्त की जा सकती है और उसी दिन 4.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेंगे।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं राज्य कर्मचारी बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर प्रमाण पत्र प्रस्तुत करना होगा। अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
- सम्पूर्ण किए गए कार्यों के प्रत्येक चल देयको में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 05 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में प्रत्येक चल देयको में से 03 वर्ष रोकी जावेगी।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में शपथ पत्र प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- सफल निविदादाता से अनुबंध के पूर्व अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जब कि निविदा की दरों में कॉफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- शासन के विभिन्न विभागों जैसे- खनिज विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
- निर्धारित निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाये जाने पर ही निविदा दर संबंधित लिफाफा खोला जावेगा, अन्यथा निविदा निरस्त मानी जावेगी।
- उक्त कार्य में लगे श्रमिकों को आवश्यक विद्युत सुरक्षा उपकरण उपलब्ध कराना अनिवार्य होगा, एवं कार्य के दौरान किसी प्रकार के दुर्घटना होने पर सम्पूर्ण जवाबदारी ठेकेदार की होगी।

//2//

17. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएं स्वयमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
  18. कार्य हेतु लिफाफे पर कार्य का नाम, निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
  19. ठेकेदारों को उपरोक्त कार्य हेतु लगे श्रमिकों का भुगतान बैंक के माध्यम से किया जाना अनिवार्य होगा।
  20. निविदा प्रपत्र अहस्तांतरणीय होगा। एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
  21. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
  22. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- नोट:-
1. घरोहर राशि के रूप में एफ.डी.आर./टी.डी.आर. पृथक से लिफाफे में स्वीकार किए जावेंगे, जो आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
  2. उपरोक्त तिथियों में कोई तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

प्रतिलिपि :- प्रोग्रामर, संचानालय नगरीय प्रशासन एवं विकास विभाग नवा रायपुर (छ.ग.) को [Uad.cg.gov.in](http://Uad.cg.gov.in) में अपलोड किये जाने हेतु प्रेषित।

कार्यपालन अभियन्ता  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)

ठेकेदार के हस्ताक्षर  
नाम -.....  
पूर्णपता -.....  
.....  
मोबाईल नं. ....



# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

## Abstract

**Sub :- Lighting Arrangement at Football Ground of High School  
Ghuddeva Under W. No. 64**

PWD (Elec. 01.06.2020)

S. No	Ref.	Item of Work	Unit	Rate	Qty	Amount
1	19.3	Supply of swaged steel tubular pole as per IS 2713 with base plate of size 300x300x6mm welded at bottom, necessary hole for cable entry and earthing stud welded at specified height including painting with one coat of red oxide zinc chromate primer.				
	19.3.11	Designation 410 SP-32 height 9.00 metre	Each	11825.00	4	47300.00
2	19.10	Erection of STEEL TUBULAR or "H" BEAM/ ISMB pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation and cement concrete collar of size 0.4 metre dia and 0.50 metre height from ground level including excavation and refilling etc. as per specification of length:				
	19.10.4	7 metre to 10 metre	Each	2610.00	12	31320.00
3	15.1	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).				
	15.1.12	3.5 x 35 sq. mm.	Metre	316.00	600	189600.00
4	15.3	Supplying and laying following sizes one number FRLS PVC insulated /XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade in existing RCC/ HUME/ STONEWARE/ METAL/ HDPE pipe as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).				
	15.3.12	3.5 x 35 sq. mm.	Metre	134.00	22	2948.00
5	15.4	Supplying and laying following sizes one number FRLS PVC insulated /XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade in existing masonry open duct as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).				
	15.4.12	3.5 x 35 sq. mm.	Metre	126.00	10	1260.00
6	14.5	Supplying and fixing G.I. pipe along with wall or pole/ support with 2 Nos MS clamps for protection of under ground cable in approved manner including bolts and nuts or metal dash fasteners complete as per specification				
		50 mm dia	Metre	403.00	22	8866.00
7	19.17	Supplying and fixing PVC water tight terminal box of approved make and brand with detachable gland plate in bottom, hinged front openable cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 25x3mm GI flat with 2 No GI nuts bolts complete as per Specification				


Ref.	Item of Work	Unit	Rate	Qty	Amount
	300x200x125 mm for 3 phase	Each	989.00	12	11868.00
8	3.11 Supplying and drawing following sizes of FRLS PVC insulated copper conductor, Multi Strand Wire in the existing surface/ concealed FRLS PVC, conduit/ PVC casing capping as Specification and IS :694 (2010)				
	3.11.13 3 x 2.5 sq. mm	Metre	57.00	120	6840.00
9	15.28 Supplying, fixing and cramping suitable size and all type aluminium ferule/ lugs to following size 1.1 KV grade power cable core / lead, pressed with high pressure cramping tool including connection to switch gear/ MCCB etc as Specification				
	15.28.5 35 sq. mm	Each	20.00	100	2000.00
10	20.7 Supplying and erection of channel iron 75x40x4.8 mm (7.14kg/m) cross arm for overhead line complete with clamps, bolts and nuts including drilling of holes for insulator pins, bolts and nuts etc as per specification.				
	20.7.2 For 4 wire overhead line (1.15m long)	Set	619.00	24	14856.00
11	6.29 Supplying of following 230/250 volts LED Flood light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Seperate housing for driver etc complete as per specification and P.A. should be greater than 0.9. LED chip efficacy ratio ≥ 120 lumens /watt.				
	6.29.11 300 watt	Each	17225.00	36	620100.00
12	12.19 Providing maintenance free earthing with following size GI pipe including making bore pit of minimum 150mm dia, providing and laying approved 12.19 make Earthing Electrode of Pipe-in-Pipe technology as per IS 3043(R 2016) -1987 made of corrosion free G.I. Pipes having outer pipe of 80mm dia and inner pipe of 50mm dia and filling with specified qty highly conductive compound around pipe and above that with soft soil in bore pit complete and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. as per specification				
	With 3 metre long GI Pipes and 50 kg back filling compound.	Each	10955.00	2	21910.00
13	12.18 Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing along with existing surface/ concealed conduit/ submain wiring/ cable as per specification.	Metre	19.00	600	11400.00
14	31.12 Painting of following height steel tubular poles with two coat of aluminium paint of approved brand including cleaning the surface as Specification				
	Above 6 metre and upto 8 metre	Each	193.00	12	2316.00
15	7.10 Providing and fixing metal clad, TP&N switch fuse unit (re-wirable), 415/500 volts, with porcelain re-wireble fuses including drilling holes on the board, connections, earthing the body etc. as per specification. (Thimbeling shall be paid separately).				
	7.10.3 100 amps	Each	3493.00	1	3493.00



Ref.	Item of Work	Unit	Rate	Qty	Amount	
16	7.19	Fabrication, supply, installation, testing and commissioning of cubicle type compartmentalized wall/ floor mounted power cum control panel board of specified size and following depth made out of not less than 2 mm thick CRCA MS powder coated sheet with suitable size compartments for bus bars, switchgears and necessary cutouts for voltmeters, ammeters etc as per specifications including powder coating painting but without busbars, switchgears and other accessories etc complete as per specification. (Only face area is to be measured)				
	7.19.1	Upto 300 mm deep	Sqm	3818.00	0.36	1374.48
17	10.17	Providing and fixing panel mounting 230 volt LED type indicating lamp in existing cubical panel including, connections, testing and commissioning etc. as per Specification	Each	94.00	2	188.00
18	10.22	Providing and fixing following Time switch (timer) in existing panel including connection, testing and commissioning as per Specification				
	10.22.2	Analoge type	Each	2525.00	2	5050.00
19	9.10	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as per specification.				
	9.10.1	6 amps to 32 amps	Each	151.00	3	453.00
20	10.12	Providing and fixing 2 pole, 230/250 volts following rating power contactor in existing starter/ cubical panel including, connections, testing and commissioning etc. as per specification.				
	10.12.2	32 amps	Each	526.00	3	1578.00
		Total Rs			984720.48	
		Say Rs			984720.00	

  
**Sub Engineer**  
**Municipal Corporation,**  
**Korba (C.G.)**

  
**Assitt. Engineer**  
**Municipal Corporation,**  
**Korba (C.G.)**

  
**Executive Engineer**  
**Municipal Corporation,**  
**Korba (C.G.)**