



कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क./485, 486, 488/निर्माण (कोसा.)/2019

कोरबा, दिनांक 28.02.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रनावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्रमांक 29 पोड़ीबहार में मंच, शेड एवं सामुदायिक भवन का मरम्मत एवं पेंटिंग का कार्य । (पार्षद मद 2018-19)	4,50,000/-	4500/-	750/-	03 माह	सक्षम श्रेणी	13.03.2019	15.03.2019	23.03.2019
2	वार्ड क्रमांक 17 गुलापी हॉटल से नायक घर तक आर.सी.सी. नाली एवं सी.सी. रोड एवं मरम्मत कार्य । (मरम्मत एवं संधारण मद)	3,96,813/-	4000/-	750/-	03 माह	सक्षम श्रेणी	13.03.2019	15.03.2019	23.03.2019
3	वार्ड क्रमांक 32 रिसदी श्रीवास्तव गोहल्ला में आर.सी.सी. गंच का निर्माण कार्य । (विधायक मद 2018-19)	3,50,000/-	3500/-	750/-	03 माह	सक्षम श्रेणी	13.03.2019	15.03.2019	23.03.2019

उपरोक्त कार्यों की निविदा की सामान्य शर्तें, धरोहर राशि, विस्तृत निविदा विज्ञप्ति, निविदा दस्तावेज व अन्य जानकारी कार्यालयीन अवधि में कार्यालय से प्राप्त की जा सकती है साथ ही यह जानकारी विभागीय वेबसाइट Website : www.korbamunicipal.in एवं www.uad.cg.gov.in में देखा एवं डाउनलोड किया जा सकता है। उक्त निविदा में किसी भी प्रकार का संशोधन किया जाता है तो विभागीय वेबसाइट पर देखा जा सकता है।


कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

॥ स्वच्छ भारत निर्माण में योगदान दें ॥


OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
ABSTRACT


Name of Work **MAINTENANCE & PAINTING WORK OF MUNCH, SHED AND SAMUDAYIK BHAWAN OF PODIBAHAR WARD NO. 29**
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ROAD-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	17.1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :				
	1.2	Thickness more than 15mm and upto 20mm	sqm	120.00	148.00	17,760.00
2	14.9	Distempering with acrylic washable distemper to give an even shade.				
	9.2	On old work (one or more coats)	sqm	3000	17.50	52,500.00
3	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	1830	94.50	172,935.00
4	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.2	On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	sqm	1830.00	37.00	67,710.00
5	14.23	Painting on old work (one or more coats) to give an even shade with:				
	23.1	Satin synthetic enamel paint	sqm	308.60	35.00	10,731.00
6	12.13	Providing and laying vitrified floor tiles with double charge/ multi charge printing with water absorption less than 0.5% and conforming to IS : 15622 of approved make in all colours and shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.				
	13.1	Size 600x600mm	sqm	60.00	1151.00	69,060.00
7	14.44	Removing white or colour wash by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete.	sqm	3000.00	4.30	12,900.00
8	14.45	Removing dry or oil bound distemper by scraping sand papering and preparing the surfaces smooth including necessary repair to scratches etc. complete.	sqm	1830.00	5.20	9,516.00
9	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	9.00	4073.00	36,657.00

As per Estimate Amount Rs. **449769.00**

Say Rs. 450,000/-


Sub Engineer


Asst. Engineer