

# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2019/497

सिस्टम टेन्डर नं. 58141

कोरबा, दिनांक 31/10/2019


## द्वितीय ई-निविदा आमंत्रण सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015, सड़क दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 09 में भिलाई खुर्द कमांक 03 से कचन्दी नाला रोड तक सीमेंट कांकीट सड़क एवं आर. सी.सी. कलवर्ट का निर्माण कार्य	40.18	30200/-	07 माह	वर्ग डी एवं प्रवर श्रेणी	19.11.2019 से .....


शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड ) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोक़ी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

  
 कार्यपालन अभियन्ता  
 नगर पालिक निगम  
 कोरबा (छत्तीसगढ़)

**Date-Time Detail(s)**

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		31.10.19	10.30	31.10.19	10.30	Release Tender
2		Bid Submission	31.10.19	10.30	18.11.19	17.30	
3	Tender Open		19.11.19	10.30	--	--	

  
**EXECUTIVE ENGINEER**  
**KORBA (CG)**  
For, Commissioner Korba (C.G.)

# OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

## DETAILED ESTIMATE (PART A)

Construction of Cement Concrete Road from Bhalai Khurd Kramank 3 to Kachandi  
alla at Ward No. 9

Schedule of rates public works department [PWD <sup>ROAD</sup> BUILDING-01-01-2015]

S. N.	SOR Ref.	DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
1	2.1	Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable material with all lifts and up to a lead of 1000 mtrs and earth filling in the depression/pit and as per relevant clauses of section-200 for :-								
	i)	Girth from 300 mm to 600 mm	72				72.00	Each	197.00	14184.00
	ii)	Girth beyond 600 mm to 900 mm	42				42.00	Each	353.00	14826.00
	ii)	Girth beyond 900 mm to 1800 mm	12				12.00	Each	684.00	8208.00
2	3.2	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.								
			1	640.00	3.50	0.20	448.00			
			1	60.00	12.00	1.50	1080.00			
			1	60.00	9.60	0.60	345.60			
			1	30.00	6.80	0.30	61.20			
						Total=	1934.80	Cum	95.00	183806.00
3	3.15	Compacting Original Ground supporting sub-grade Loosening of the ground upto a level of 500 mm below the subgrade level ,watered, graded and compacted in layers to meet requirement of table 300-2 for sub grade construction								
	(i)		1	490.00	3.50	0.20	343.00			
			1	150.00	6.50	0.20	195.00			
							Total=	538.00	Cum	50.00
4	6.6	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. ( For Village roads)								
	1	P.C.C. M-10	1	640.00	3.50	0.10	224.00			
							Total=	224.00	Cum	2789.00
5	6.7	Providing and laying unreinforced cement concrete without dowel bar including form work and expansion, contraction and longitudinal joint as per design or as per IRC- 62-2014 over a prepared base as per approved mix design and finishing to lines and grade as per Drawings for pavement thickness less than 200mm in low volume Roads.								
	(i)	Plain Cement Concrete Grade M-30 and minimum Cement Content @375 kg/cum	1	640.00	3.50	0.20	448.00			


Total=	448.00	Cum	4391.00	1967168.00
--------	--------	-----	---------	------------


TOTAL =	2839828.00
---------	------------

Location of R.C.C. Culvert Between Shatal Khurd Kramank 3 to Kachh...

at Ward No. 9


Sl. No.	DESCRIPTION	NO	UNIT	QTY	AMT	Cum	Total
1	Excavation for all types and sizes of foundations, trenches and drains of all sizes other depths including removal of concrete, stuff upto 1.5 m and less than 30m radius far away from the proposed work including retaining wall having 10% slope	1	m <sup>3</sup>	1.50	150.00		150.00
		2	m <sup>3</sup>	2.50	250.00		400.00
		3	m <sup>3</sup>	80.00	80.00		480.00
				Total	150.00	Cum	150.00
2	Providing and laying formwork including casting, anchoring, stacking, aligning, propping, bracing etc. complete and including its removal at all levels for Foundations, columns, base of columns and depth below in any shape and size	1	m <sup>2</sup>	2.50	250.00		250.00
		2	m <sup>2</sup>	1.50	150.00		400.00
		3	m <sup>2</sup>	1.00	100.00		500.00
				Total	5.00	Cum	500.00
3	Supply of all materials including finished products, labour etc. in super structure	1	m <sup>3</sup>	1.50	150.00		150.00
		2	m <sup>3</sup>	0.50	50.00		200.00
				Total	2.00	Cum	200.00
4	Providing and laying concrete for concrete with 1:1:2 ratio with aggregate with concrete, masonry, foundation, pile and at ground level excluding cost of form work	1	m <sup>3</sup>	1.50	150.00		150.00
		2	m <sup>3</sup>	2.50	250.00		400.00
				Total	4.00	Cum	400.00
5	1:1:2 cement, 1:2 coarse sand, 3 grades coarse aggregate 20mm nominal size	1	m <sup>3</sup>	1.50	150.00		150.00
		2	m <sup>3</sup>	2.50	250.00		400.00
		3	m <sup>3</sup>	80.00	80.00		480.00
				Total	105.00	Cum	105.00


  
 Asstt. Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)



		1	7.50	5.50	0.30	12.38				
		3	5.50	0.60	1.80	17.82				
		1	7.50	5.50	0.30	12.38				
		4	2.80	0.80	0.20	1.79				
		4	2.80	0.30	1.80	6.05				
		2	5.50	2.20	0.30	7.26				
		2	60.00	0.80	0.20	19.20				
		2	60.00	0.30	1.20	43.20				
						Total=	120.07	Cum	4163.00	
5	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:								
		1	Thermo-Mechanically treated bars FE 415				Total=	9605.60	Kg	54.50
6	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.								
							155.36	Cum	65.00	
									TOTAL =	1178167.11

  
 Asstt. Engineer  
 Municipal Corporation  
 Korba (C.G.)

  
 Sub Engineer  
 Municipal Corporation  
 Korba (C.G.)