



नगर पालिक निगम, कोरबा (छत्तीसगढ़)

कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

फ़ोन : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

फा.क./05, 06/निर्माण (कोसा.)/2019

कोरबा, दिनांक 20.06.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने आवेदन की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	वार्ड क्रमांक 20 काशीनगर में सामुदायिक मंच का निर्माण कार्य । (पार्षद मद 2017-18)	4,82,000/-	5000/-	750/-	02 माह	सक्षम श्रेणी	04.07.2019	08.07.2019	15.07.2019
2	वार्ड क्रमांक 17 अंतर्गत पथरीपारा में सामुदायिक भवन के समीप भोग पण्डाल का निर्माण कार्य । (पार्षद मद 2018-19)	3,00,000/-	3000/-	750/-	02 माह	सक्षम श्रेणी	04.07.2019	08.07.2019	15.07.2019

शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्यों हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखि तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा मंगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जायेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशिप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन का प्रमाण पत्र एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र धरोहर राशि निविदा प्रपत्र प्राप्त करने के अंतिम तिथि के 3.00 बजे सायं तक अधोहस्ताक्षरकर्ता के समक्ष आवेदन प्रस्तुत करना अनिवार्य होगा।
- निविदा प्रपत्र उन्हीं ठेकेदारों को दिया जायेगा , जिन्हें इस प्रकार के कार्य का अनुभव होगा ।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके समक्ष खोले जावेंगे।
- सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं मरम्मत एवं संधारण मद के कार्य को छोड़कर 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्यूरिटी के रूप में रोकी जावेगी।



कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फ़ैक्स : 07759-221929, पो. बॉक्स नं. - 12 पिन कोड - 495677

Website : www.korbamunicipal.in, Email : kosabadizone3@gmail.com

9. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
10. ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।
11. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथपत्र देना अनिवार्य होगा।
12. ईट से संबंधित निर्माण कार्यों में प्लाई एंड ब्रिक का उपयोग किया जाना अनिवार्य होगा।
13. निविदा दसों असामान्य कमी प्रतीत होने पर सफल निविदा दारा से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईन डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव गिरस्त मानी जावेगी।
14. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
15. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
16. निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
17. निविदा प्रपत्र क्व कर अथवा वेबसाईट से सीधे डाउनलोड कर निविदा प्रपत्र हेतु निर्धारित राशि की अतिरिक्त डिमॉंड ड्राफ्ट सहित अपनी भरी हुई निविदा नगर पालिक निगम में रजिस्टर्ड/स्पीड पोस्ट द्वारा अमानत राशि के साथ प्रस्तुत करें।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

कार्यपालक अभियन्ता

नगर पालिक निगम

कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

ABSTRACT


Name of Work : **CONSTRUCTION OF COMMUNITY MUNCH AT KASHI NAGAR W.N 20**


As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.				
	3.3	In cement mortar.	cum	19.2	263.00	5,049.60
2	16.42	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	cum	2.64	768.00	2,027.52
3	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	3.2	1:3:6 or richer mix	cum	30.03	549.00	16,486.47
4	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	42.55	185.00	7,871.75
5	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	28.01	371.00	10,391.71
6	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	5.13	2659.00	13,640.67
7	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	18.39	4163.00	76,557.57
8	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	2.2	Thermo-Mechanically treated bars FE 500D	kg	1800	54.50	98,100.00
9	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	66.6	139.00	9,257.40
	1.6	Columns, beams & walls- circular or any other geometrical shape other than square and rectangular in all sizes	sqm	25.68	356.00	9,142.08
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	1.53	235.00	359.55
	1.8	Beams, lintels, cantilevers & walls	sqm	11.2	202.00	2,262.40
10	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	25.48	3263.00	83,141.24
11 1.1	Providing and making 6mm thick cement plaster of mix:				
1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	12.25	87.00	1,065.75
12 11.2	Providing and making 12mm thick cement plaster of mix:				
2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	105.4	91.50	9,644.10
13 11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	132.4	107.00	14,166.80
14 12.3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.				
3.3	75 mm thick	sqm	69	345.00	23,805.00
15 7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	22	121.00	2,662.00
16 9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	200	68.00	13,600.00
17 9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	200	75.00	15,000.00
18 14.9	Distempering with acrylic washable distemper to give an even shade.				
9.1	On new work (Two or more coats)	sqm	118	38.00	4,484.00
19 14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Altek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	251	94.50	23,719.50
20 14.14	Finishing walls with water proofing cement paint of required shade to give an even shade.				
4.1	On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	132.4	41.00	5,428.40
21 1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	32	65.00	2,080.00
22 1.26	Carriage by mechanical transport upto 5 km lead:				
6.1	Earth	cum	42.55	111.00	4,723.05
6.3	Dismantled Building debris (Mulba)	cum	51.87	91.50	4,746.10

As per Estimate Amount Rs. 459,412.66
 electrification Add Above 5 % 22,654.75
Total Estimate Amount Rs. 482,067.41
Say Rs.


 Sub Engineer


 Asst Engineer