

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

का.क./निर्माण /2019 /67

सिस्टम टेन्डर नं. 54188
ई-निविदा आमंत्रण सूचना

कोरबा, दिनांक 05/078/2019

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 33 रामपुर बस्ती में सामुदायिक भवन के समीप अतिरिक्त कार्य एवं मुन्नालय का निर्माण कार्य। (हदापार निधि)	7.50	5700/-	03 माह	वर्ग डी एवं प्रवर श्रेणी	27.08.2019 से



शर्त:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फलाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		05.08.19	10.30	05.08.19	10.30	Release Tender
2		Bid Submission	05.08.19	10.30	26.08.19	17.30	
3	Tender Open		27.08.19	10.30	--	--	


**EXECUTIVE ENGINEER
KORBA (CG)**
For,  Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
ABSTRACT

Name of Work CONSTRUCTION OF ADDITIONAL WORKS LIKE URINAL ROOM AT NEAR SAMUDAYIK BHAWAN OF RAMPUR BASTI
WARD NO. 33

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	39.15	185.00	7,242.75
2	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	25.38	65.00	1,649.70
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	7.26	371.00	2,693.46
4	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	57.66	139.00	8,014.74
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	30.78	297.00	9,141.66
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	50.24	235.00	11,806.40
	1.8	Beams, lintels, cantilevers & walls	sqm	48	202.00	9,696.00
5	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	8.36	2659.00	22,229.24
6	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	25.44	4163.00	105,906.72
7	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	1653.60	54.50	90,121.20
8	3.13	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	cum	0.35	4237.00	1,482.95
9	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				

ITEM DESCRIPTION		UNIT	QTY	RATE	AMOUNT
10	5.4 Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	41.74	3263.00	136,197.62
	7.6 Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	31.38	121.00	3,796.98
11	9.6 Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	6.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	240.00	68.00	16,320.00
12	9.13 Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	547.80	75.00	41,085.00
13	9.14 Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	kg	208.67	79.50	16,589.26
14	9.15 Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	kg	220.00	67.50	14,850.00
15	11.1 Providing and making 6mm thick cement plaster of mix:				
	1.2 In Cement mortar 1:4 (1 cement : 4 fine sand)				
16	11.2 Providing and making 12mm thick cement plaster of mix:	sqm	48.52	87.00	4,221.24
	2.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)				
17	11.3 Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:	sqm	351.00	91.50	32,116.50
	3.4 In Cement Mortar 1:6 (1 cement : 6 fine sand)				
18	12.7 Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.2 Size above 200x300mm	sqm	36.00	646.00	23,256.00
19	12.9 Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	9.2 Size above 300x300mm	sqm	45.00	728.00	32,760.00
20	14.13 Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	sqm	400	94.50	37,800.00
21	14.14 Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1 On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	270.00	41.00	11,070.00
22	14.15 Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:				
	15.1 On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	400.00	56.00	22,400.00

SN	QTY	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
23	14.22	Painting on new work (two or more coats) to give an even shade with:				
	22.1	synthetic enamel paint	sqm	36.96	55.00	2,032.80
24	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm and cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	1.3	White Orissa pattern W.C. pan of size 580x440 mm	each	2.00	2899.00	5,798.00
25	18.4	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	4.1	White pedestal type	each	2.00	2882.00	5,764.00
26	18.13	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:				
	13.1	Flat back half stall urinal of size 460x380x250mm	each	3.00	1776.00	5,328.00
	13.2	Flat back type urinal of size 460x380x250mm	each	2.00	1529.00	3,058.00
27	18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				
	17.1	White Size 550x450 mm	each	4.00	1430.00	5,720.00
28	18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete.				
	76.1	75 mm dia pipe.	metre	29.58	182.00	5,383.56
29	18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion.				
	77.1	Tee/ Tee with door/ Bend 45° / Bend 90°				
	77.1.1	75 mm	each	14.00	113.00	1,582.00
	77.2	Double 'Y' with or without door				
	77.2.1	75 mm	each	7.00	129.00	903.00
	77.3	Vent cover				
	77.3.1	75 mm	each	7.00	34.00	238.00
	77.5	'P' trap 110mmx110mm long	each	8.00	227.00	1,816.00
30	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. INTERNAL WORK - EXPOSED ON WALL				
	4.1	15 mm nominal outer dia .Pipes.	metre	15.00	110.00	1,650.00
	4.3	25 mm nominal outer dia .Pipes.	metre	20.00	199.00	3,980.00
31	19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of				

SN	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		approved quality:				
	13.1	Bit (250 grams)	each	16.00	185.00	2,960.00
	13.3	Stop (350 grams)	each	15.00	237.00	3,555.00
32	19.15	Providing and fixing stainless steel drain jali of approved make/quality.	each	14.00	51.00	714.00
33	19.16	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):				
	16.1	25 mm nominal bore	each	2.00	436.00	872.00
34	19.42	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	LTR	1000.00	7.30	7,300.00

As per Estimate Amount Rs. 749991.78


Sub Engineer
Nagar Palik Nigam,
Korba

Astt. Engineer
Nagar Palik Nigam,
Korba