

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क. /निर्माण /2020/586

सिस्टम टेन्डर नं. 67658
ई-निविदा आमंत्रण सूचना


कोरबा, दिनांक 10.09.2020

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत स्लम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (मवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरो पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि लाख में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 02.03 अंतर्गत पावर हाउस रोड से डी. डी.एम. स्कूल तक आर.सी.सी. नाला का निर्माण	198.17	149000.00	08 माह	वर्ग सी एवं प्रवर श्रेणी	06.10.2020 से


शर्तें:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हे निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं मरम्मत एवं संधारण मद को छोड़कर शेष कार्यों में 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो वे निविदाकार ही निविदा हेतु पात्र होंगे।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
10. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
11. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
12. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
13. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
14. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किया जा सकते हैं।


अधीक्षक अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		09.09.20	15.30	10.09.20	12.30	Release Tender
2		Bid Submission	10.09.20	12.30	05.10.20	17.30	
3	Tender Open		06.10.20	10.30	--	--	


SUPERITENDING ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)

DETAILED ESTIMATE

Work:- Construction of R.C.C. Nala from power house road to ddm school
 ward 02&03 at t.p.nagar zone

Rate of rates public works department [PWD BUILDING-01-01-2015]


DESCRIPTION	NO	L	B	D/H	QTY	UNIT	RATE	AMOUNT
Demolishing cement concrete including disposal of material within 50 metre lead.	2	820	0.6	0.10	98.4			
				Total=	98.40	Cum	549.00	54021.6
Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	2	820	0.2	0.60	196.80			
				Total=	196.80	Cum	768.00	151142.4
Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), in all types of soil	1	830.00	2.80	2.60	6042.40			
DUCT					196.80			
					98.40			
				Total=	6140.80	Cum	185.00	1136048.00
Extra for every additional lift of 1.5 m or part thereof.								
1.5.1 All types of soils	1	830	2.8	1.10	2556.40	CUM	26.50	67744.60
Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 10cm in depth consolidating each deposited layer by ramming and watering, including dressing etc.	1	830.00	2.80	0.15	348.60			
				Total=	348.600	Cum	371.00	129330.6
Providing and fixing formwork including centering, shuttering, leading, staging, propping bracing etc complete and including its foundations, footings, base of columns and plinth beam in any	2	830.00		0.20	332.00			
				Total=	332.00	Sqm	139.00	46148.0
of any thickness including arched pilasters, buttresses etc.	4	830.00		1.80	5976.00			

STU-20

6	3.1	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level				
	3	1:4:8 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm)				
			Cum	398.400	2659.00	1059345.6
7	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth				
	1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).				
				1629.664		
			Cum	1629.66	4163.00	6784291.232
8	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in				
	1	Thermo-Mechanically treated bars FE 415	Kg	69673.76	54.50	3797219.92
			Kg	55776.00	54.50	3039792.00
	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
			CUM	149.40	4073.00	608506.20
9	1.9	Extra rate for lead for every 50m lead or part thereof and upto 150 m beyond 50 m free lead and 1.5 m free lift by manual means only.				
	1	For Soils(Extra lead 150 m)	Cum	1228.160	111.00	136325.8
		1.26.3 Dismantled Building debris		295.200	91.50	27010.8
10	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead	Cum	4912.640	65.00	319321.60
	1.10	Pumping out water caused by springs tidal or river seepage, broken water main or drains and like during Excavation or during Excavation and laying of base concrete (volume to be calculated taking height from water level to bottom of pit and to be measured and paid)				
				1731.5		
			Cum	1731.45	146.00	252791.7

11	1.10	Pumping out water caused by springs tidal or river seepage, broken water main or drains and like during Excavation or during Excavation and filling of base concrete (volume to be calculated taking height from water level to bottom of pit and to be measured and paid)								
			1	824.5	2.1	1.00	1731.5			
						Total=	1731.45	Cum	146.00	252791.7
12	NS	Removing of sludge/ garbage from drain saptic and desposal at suitable places of any lead and lift as per direction of Engineer incharge								
			1	850.00	1.80	0.90	1377.00			
						TOTAL=	1377.00	CUM	263.00	362151.00
									TOTAL =	19817443.01

Say Rs.= 19817000.00



कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)



Asstt. Engineer
Municipal Corporation
Korba (C.G.)



Sub Engineer
Municipal Corporation
Korba (C.G.)