



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय - साकेत भवन, आई.टी.आई. टॉक, कोरबा (छ.ग.)

कोरबा जोन

फा.क्र./78/निर्माण (कोरबा जोन)/2022/

कोरबा, दिनांक 29.04.2022

“ द्वितीय निविदा आमंत्रण सूचना”

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा प्रचलित **PWD Building SOR 01.01.2015** से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैनुअल निविदा वेबसाईट से डाउनलोड कर त्रि-लिफाफा पद्धति के माध्यम से आमंत्रित की जाती है :-

1. निर्धारित प्रारूप में निविदा प्रपत्र प्राप्त होने अंतिम तिथि - 16.05.2022 सायंकाल 3:00 बजे तक
2. निविदा खुलने की अंतिम तिथि - 16.05.2022 सायंकाल 4:30 बजे तक

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	निविदा प्रपत्र	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क्रमांक 04 में सामुदायिक भवन निर्माण कार्य। (विधायक मद)	15,00,000/-	11,300/-	750/-	Form-A	04 माह	सक्षम श्रेणी	16.05.2022

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. निविदा के दस्तावेज हाथो-हाथ न लिया जाकर रजिस्टर्ड पोस्ट अथवा स्पीड पोस्ट से प्राप्त किया जावेगा। अन्य माध्यमों यथा कोरियर सर्विस, साधारण डाक इत्यादि से प्राप्त अथवा समयावधि के पश्चात् प्राप्त निविदाओं पर विचार नहीं किया जावेगा। निविदा आयुक्त, नगर पालिक निगम, कोरबा आई.टी.आई. कॉलोनी रामपुर, कोसाबाड़ी जिला-कोरबा (छ.ग.) पिन नं.-495677 के पते पर भेजना होगा। निर्धारित तिथि को सायं 3:00 के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं किए जावेंगे।
3. निविदा प्रपत्र नगर पालिक निगम, कोरबा के वेबसाईट www.korbamunicipal.in/uad.cg.gov.in डाउनलोड किया जाकर नवीन निविदा प्रपत्र **Form - A/B/ABC** (जारी दिनांक तक समस्त संशोधनों के साथ) निर्धारित शुल्क की डीडी के साथ संबंधित कार्य का नाम पूर्ण विवरण सहित भरकर भेजना होगा।
4. निविदा प्रपत्र त्रि-लिफाफा पद्धति से मान्य किया जावेगा जो निम्नानुसार होगा:-
(अ) प्रथम लिफाफा में ठेकेदार का जीवित पंजीयन प्रमाण पत्र, आयकर चुकता प्रमाण पत्र, निविदा सूचना आमंत्रण में उल्लेखित अन्य दस्तावेज के साथ निर्धारित प्रपत्र शुल्क का डीडी एवं अमानत राशि का टी.डी.आर./एफ.डी.आर. नगद निगम कोष में जमा कर जो कि आयुक्त, नगर पालिक निगम कोरबा के नाम पर देय होगा प्रस्तुत करना होगा।
(ब) द्वितीय लिफाफा में ठेकेदार द्वारा भरा हुआ निविदा प्रपत्र होगा।
(स) तृतीय लिफाफा में उपरोक्त दोनो लिफाफाएँ होगी तथा आवश्यकता पड़ने पर मूल अभिलेख प्रस्तुत करना होगा।
5. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
6. निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आयकर चुकता प्रमाण पत्र, पेन नम्बर, जी.एस.टी. पंजीयन एवं प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, शपथ पत्र, कर्मचारी भविष्य निधि संगठन, कर्मचारी, राज्य बीमा निगम रायपुर से पंजीयन एवं विस्तृत निविदा आमंत्रण सूचना (एनआईटी) हस्ताक्षरयुक्त एवं निर्धारित प्रारूप में निविदा आमंत्रण सूचना के कंडिका क. 04 के लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
7. कार्य हेतु लिफाफे पर कार्य का नाम निविदा आमंत्रण सूचना क्रमांक, निविदा खुलने की तिथि स्पष्ट रूप से लिखकर भेजना होगा।
8. निविदाकार का यह दायित्व है कि वे निविदा भरने के पूर्व स्थल का स्वयं निरीक्षण कर लें ताकि प्रारंभ करने में किसी प्रकार की कठिनाई न हो। निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
9. निर्धारित निविदा प्रपत्र में उल्लेखित कंडिकाएँ स्वमेव लागू मानी जावेगी एवं निविदा आमंत्रण सूचना निविदा का ही भाग माना जावेगा।
10. निर्धारित प्रारूप में निविदा प्रपत्र, निविदा प्रपत्र शुल्क, अमानत राशि, निविदा आमंत्रण सूचना पत्र में उल्लेखित दस्तावेज सही पाए जाने पर ही निविदा दर संबंधी लिफाफा खोला जावेगा अन्यथा निविदा निरस्त कर दी जावेगी।
11. ठेकेदार को अपनी दरें शब्दों एवं अंकों में लिखना अनिवार्य होगा।
12. शासन के विभिन्न विभागों जैसे:- खजिन विभाग, श्रम विभाग, समाज कल्याण विभाग इत्यादि विभागों द्वारा समय-समय पर जारी निर्देशों/आदेशों के पालन की समस्त जिम्मेदारी संबंधित ठेकेदार की होगी।
13. ठेकेदार यदि कार्य को अपूर्ण स्थिति में छोड़ता है तो निविदा प्रपत्र में उल्लेख अनुसार इस संबंध में प्रावधान के अंतर्गत कार्यवाही की जावेगी।

कमश'.....2/ /

- 14 कार्य प्रारंभ नहीं करने अथवा अपूर्ण स्थिति में छोड़ने पर निगम द्वारा ठेकेदार के विरुद्ध तत् समय में एम.आई.सी. द्वारा स्वीकृत प्रस्ताव के अधीन कार्यवाही की जावेगी जिसकी संपूर्ण जवाबदारी ठेकेदार की होगी।
- 15 सफल निविदा दाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी जबकि निविदा की दरों में काफी कमी हो जैसे निविदादाता को निविदा दर एवं अनुमानित लागत से 10 प्रतिशत से अधिक निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर./टी.डी.आर. ऑफिस टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम कोरबा के नाम से देय होगा, जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि को जमा न करने की दशा में निविदा निरस्त कर दी जावेगी।
- 16 सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि रनिंग देयको के साथ 01 वर्ष एवं 5 प्रतिशत पृथक से 03 वर्ष की गारंटी के लिये परफार्मेंस सिक्क्यूरिटी के रूप में रोकी जावेगी। मेंटनेंस कार्य हेतु मात्र सुरक्षा राशि काटी जावेगी।
- 17 निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- 18 निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में वैध शपथ पत्र कंडिका क. 04 के प्रथम लिफाफा (अ) में प्रस्तुत करना अनिवार्य होगा।
- 19 ईंट से संबंधित निर्माण कार्यों में पलाई ऐश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
- 20 निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- 21 निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधीनस्थ अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
- 22 निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- 23 निविदा खुलने की तिथि में अवकाश होने पर आगामी तिथि (कार्य दिवस) को निविदा संबंधी कार्यवाही मानी जावेगी।

नोट:-


1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।

हस्ताक्षर -
 फर्म का नाम -
 पता -

पृष्ठा.क./78/निर्माण(कोरबा जौन)/2022

प्रतिलिपि :-

- 1 प्रोग्रामर,नगरीय प्रशासन एवं विकास विभाग,नया रायपुर (छ.ग) को Uad.C.g.gov.in में अप लोड किये जाने हेतु।


 कार्यपालन अभियंता
 नगर पालिक निगम
 कोरबा (छ.ग.)
 कोरबा, दिनांक 29.04.2022

कार्यपालन अभियंता
 नगर पालिक निगम
 कोरबा (छ.ग.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)
DETAILED ESTIMATE

Name of work:- Construction of Samudayik Bhawan in Ward no. 04.

As per SOR: Schedule of rates public works department [PWD BUILDING-01-01-2015]

S.no.	Particulars of item	No.	Length	Bread	Ht./Deptl	Quantity	Unit	Rate	Amount
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff up to 1.5 m lift and lead upto 50 m (atleast 5 m away from the excavated area) including dressing and levelling of pits in all types of soils item no. 1.1.1 page 9								
	column	23	1.50	1.50	1.50	77.63			
					Total:	77.63	cum	185.00	14361.55
2	Providing and filling in plinth with sand / crushed dust and hard moorum under floor in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering including dressing etc. complete. item 1-18, p -11								
	verandah	1	9.37	2.44	0.30	6.86			
	stairs	1	3.71	2.44	0.30	2.72			
	hall	1	9.37	12.19	0.30	34.27			
	kitchen	1	5.49	3.05	0.30	5.02			
	gents toilet	1	3.35	2.90	0.30	2.91			
	ladies toilet	1	2.70	2.90	0.30	2.35			
					Total:	54.13	cum	371.00	20081.30
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work 1:4:8 40 mm nominal size Item no. 3.1.2 page 23								
	column	23	1.50	1.50	0.10	5.18			
					Total:	5.18	cum	2659.00	13773.62
4	Brick work with modular fly ash lime (FALG bricks) conforming to IS 12894-2002 of class designation 40 in foundation and plinth in cement Mortar 1:6 (1 Cement : 6 sand) item no. 7.5.4 page 45								
	foundation of wall	1	88.23	0.23	0.45	9.13			
					total	9.13	cum	3263.00	29797.08

5	Brick work with modular fly ash lime (FALG bricks) confirming to IS 12894- 2002 of class designation 40 in superstructure cement Mortar 1:6 (1 Cement : 6 sand) item no.7.6 page 45													
	main wall	1	76.42	0.23	3.00	52.73								
	half brick wall	1	10.24	0.11	3.00	3.38								
					Total :	56.11	cum							
(-)	Deductions:													
	Doors: D0	-1	1.80	0.23	2.10	-0.87								
	D	-2	1.00	0.23	2.10	-0.97								
	D1	-5	0.90	0.23	2.10	-2.17								
	D2	-6	0.80	0.11	2.10	-1.11								
	Wind. W	-7	1.50	0.23	1.20	-2.90								
	WK	-2	1.20	0.23	0.90	-0.50								
	vent. V	-4	0.60	0.23	0.45	-0.25								
					Total :	-8.77								
					Net	Total :	47.34	cum	3384.00	160198.56				
6	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works up to floor five level excluding cost of reinforcement and formwork 1:1.5:3 with 20 mm nominal size Item no. 3.2.1 page -23													
	column footing	23	1.50	1.50	0.17	8.80								
	footing	23	0.90	0.90	0.45	8.38								
	column	23	0.23	0.30	4.55	7.22								
	tie beam	1	88.23	0.23	0.30	6.09								
	slab beam	1	123.66	0.23	0.30	8.53								
	lintel beam	1	76.42	0.23	0.15	2.64								
	lintel beam	1	10.24	0.11	0.15	0.17								
	slab	1	200.66		0.10	20.07								
	(-)deduct stairs	-1	3.71	2.44	0.10	-0.91								
	stair w/s	1	6.08	1.20	0.10	0.73								
	landing	1	2.44	1.20	0.10	0.29								
	chhajja	1	21.56	0.60	0.08	0.97								
					Total:	62.98	cum	4163.00	262185.74					
7	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawing including including cost of binding wire all complete. Thermo-Mechanically treated bars Item no. 3.12.2 page 24													
			1.00% of R.C.C work i.e.		6397.04	Kg	54.50	348638.68						

8 Providing wood work in frames of doors, windows, clearestory windows and frames wrought framed and fixed in position (b) Sal, bijasal, benteak, khair,haldu										
Item-8.1.2, pg-54										
Doors:	D0	1	6.00	0.120	0.075	0.05				
	D	2	5.20	0.120	0.075	0.09				
	D1	5	5.10	0.120	0.075	0.23				
	D2	6	5.00	0.120	0.075	0.27				
						Total:	0.65	cum	61051.00	39506.10
9 Providing and fixing 40 mm thick panelled or glazed shutter frames for doors excluding hinges and panelling.										
Teak wood										
item no.8.6.1 page 55										
Doors:	D0	1	11.68		2.04	23.83				
	D	2	0.88		2.04	3.59				
	D1	5	0.78		2.04	7.96				
	D2	6	0.68		2.04	8.32				
						Total;	43.70	sqm	2906	126992.20
10 Providing and fixing aluminium works for doors, windows, ventilators & partition made out of extruded aluminium standard section (main section with minimum 1.5mm thickness) confirming to IS:733,IS1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gaseket beveled edge beading, screws duly fixed in wall floor with fixing clips or hold fastner or bolts & nuts as required aluminium section shall be anodized transparent or dyed to approved shade according to IS1868 minimum anodic coating shall be of grade AC-15										
Glazing to be paid for sapretely:										
Item no. 9.47.2 page -85										
	Windows W	7	5.05			35.35				
	WK	2	3.67			7.34				
VENT.	V	4	1.83			7.32				
	0.874kg/m.wind. Frame									
						total:	50.01	Kg	331.00	16553.31
11 Providing and fixing aluminium works for doors, windows, ventilators & partition made out of extruded aluminium standard section (main section with minimum 1.5mm thickness) confirming to IS:733,IS1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gaseket										

Suspended floors, roofs, access plate-									
form, balconies (plain surfaces) and									
shelves(cast in situ)									
item no. 2.1.7 page 16.									
slab									
	verandah	1	9.37	2.44		22.86			
	hall	1	9.37	12.19		114.22			
	kitchen	1	5.49	3.05		16.74			
	gents toilet	1	3.35	2.90		9.72			
	ladies toilet	1	2.70	2.90		7.83			
	stair w/s	1	6.08	1.20		7.30			
	landing	1	2.44	1.20		2.93			
	chhajja	1	21.56	0.60		12.94			
					Total:	194.53			
					g.total:	194.53	sqm	235.00	45715.161
16	6 mm thick cement plaster to ceiling								
	(b) in cement mortar 1:3								
	item no.11.1.1page 103.								
	verandah	1	9.37	2.44		22.86			
	hall	1	9.37	12.19		114.22			
	kitchen	1	5.49	3.05		16.74			
	gents toilet	1	3.35	2.90		9.72			
	ladies toilet	1	2.70	2.90		7.83			
	stair w/s	1	6.08	1.20		7.30			
	landing	1	2.44	1.20		2.93			
	chhajja	1	21.56	0.60		12.94			
					Total:	194.53	sqm		
					total :	194.53	sqm	93.00	18091.53
17	12 mm thick cement plaster of cement mortar								
	(1:5)								
	verandah	1	23.62		3.20	75.58			
	hall	1	43.12		3.20	137.98			
	kitchen	1	17.08		3.20	54.66			
	gents toilet	1	12.50		3.20	40.00			
	ladies toilet	1	11.20		3.20	35.84			
					Total:	344.06	sqm		
					total :	344.06	sqm	96.50	33201.79
18	15mm thick cement plaster on rough								
	side of single or half wall in cement								
	mortar 1:6								
	Item no,-11.3.4 Page - 103								
	outer wall	1	67.43		3.90	262.98	sqm		
					Total:	262.98	sqm		
					Grand total	262.98	sqm	107.00	28138.54
19	Providing and laying nominal mix								
	cement concrete with crushed stone								
	aggregate using concrete mixer in foun-								
	dation, plinth and at ground level exclud-								

		square or round bars welded to steel							
		frame of windows etc.including applying							
		a priming coat of red oxide zinc chro-							
		mate primer .							
		Item no. 9.15 page 81							
	Wind.	W	7	1.50		1.20	12.60		
		Wk	2	1.20		0.90	2.16		
	Vent	V	4	0.60		0.45	1.08		
						Total	15.84 sqm		
						at 20 kg per sqm	316.80 kg	67.50	21384.00


SANITATION WORK

25	18.76	Providing and fixing on wall face UV							
	1	75 mm dia pipe.	1	20.00			20.00	metre	182.00 3640.00
	2	110 mm dia pipe.	1	25.00			25.00	metre	267.00 6675.00
26	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :					6	each	2899.00 17394.00
	3	White Orissa pattern W.C. pan of size 580x440 mm							
27	18.17	Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :					6	each	2899.00 17394.00
	1	White Size 550x450 mm							
28	18.77	Providing and fixing on wall face UV stabilized Unplasticised - PVC moulded fittings/ accessories having 3.2mm wall thickness for Rigid PVC pipes conforming to IS : 13592 (heavy) jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion							
	1	Tee/ Tee with door/ Bend 45°/ Bend 90°							
	1	75 mm					8.00	each	113.00 904.00
	2	110 mm					12.00	each	154.00 1848.00
	3	Vent covel							
	1	75 mm					6.00	each	34.00 204.00
	6	Nahani trap 110x75mm					10.00	each	90.50 905.00

29	19.4	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.								
	1	15 mm nominal outer dia .Pipes.				20.00	metre	110.00		2200.00
	3	25 mm nominal outer dia .Pipes.				30.00	metre	199.00		5970.00
	4	32 mm nominal outer dia .Pipes.				40.00	metre	271.00		10840.00
30	19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
	1	Bib cock (250 grams)				6.00	each	185.00		1110.00
31	19.14	Providing and fixing 15 mm nominal bore C.P. brass fittings of approved make and conforming to IS:8931 including C.P. brass extension if required:								
	6	Stop cock (concealed) (600 grams)				6.00	each	494.00		2964.00
	4	Pillar Cock (400 grams)				4.00	each	398.00		1592.00
32	19.13	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:								
	1	Bib cock (400 grams)				6.00	each	382.00		2292.00
	2	Long nose bib cock (500 grams)				2.00	each	455.00		910.00
33	19.15	Providing and fixing stainless steel drain jali of approved make/quality.				10.00	each	51.00		510.00
34	19.16	Providing and fixing brass/ gun metal gate valve with C.I. wheel of approved quality (screwed end):								
	1	25 mm nominal bore				8.00	each	436.00		3488.00
	2	32 mm nominal bore.				8.00	each	510.00		4080.00
35	18.14	Providing and fixing white vitreous china urinal basin as per IS : 2556 complete:								
	2	Flat back type urinal of size 460x380x250mm				4.00	each	872.00		3488.00

36	19.42	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.					500.00	litre	7.30	3650.00
----	-------	---	--	--	--	--	--------	-------	------	---------

Total:										1499999.98
Say Rs.										1500000.00


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Ast Engineer
 Municipal Corporation
 Korba (C.G.)