

# कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./444/निर्माण/2018

सिस्टम टेन्डर नं. 47690  
ई-निविदा आमंत्रण सूचना


कोरबा, दिनांक 01.01.2019

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 12 शारदा विहार श्री राधाकृष्णा के पास सामुदायिक भवन का निर्माण कार्य	15.00 लाख	11500.00	04 माह	वर्ग डी एवं प्रवर श्रेणी	18.01.2019 से .....

शर्तों:-

1. निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
2. जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
3. इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड ) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अगले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
4. सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
5. निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
6. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में निविदा जारी तिथि से 10 दिवस पूर्व का नोटरी सत्यापित शपथपत्र देना अनिवार्य होगा।
7. निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन ) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
8. ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
9. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
10. प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
11. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयवधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
12. निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
13. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
14. निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
15. उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये जा सकते हैं।

  
कार्यपालन अभियन्ता  
नगर पालिक निगम  
कोरबा (छत्तीसगढ़)

### Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		01.01.19	13.00	01.01.19	10.30	Release Tender
2		Bid Submission	01.01.19	10.30	17.01.19	17.30	
3	Tender Open		18.01.19	10.30	--	--	

  
EXECUTIVE ENGINEER  
KORBA (CG)  
For, Commissioner Korba (C.G.)



SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		all levels, for:								
1.1		Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.								
		-COLUMN FOOTING	14X4	1.20	0.20		13.44			
			14X4	0.40	0.30		6.72			
		-COLUMN	14X4	0.30	1.50		25.20			
		-P BEAM	2X4	12.30	0.20		19.68			
			2X4	8.70	0.30		20.88			
							Total	85.92	sqm	139.00
1.5		Columns, Pillars, Piers and likes- rectangular or square in shape								
		-COLUMN	14X4	0.30	3.60		60.48			
							2.14			
							Total	62.62	sqm	297.00
1.8		Beams, lintels, cantilevers & walls								
		-L BEAM	2X4	12.30	0.20		19.68			
			2X4	8.70	0.20		13.92			
		-CHUJJA	2	13.50	0.60		16.20			
			2	9.90	0.60		11.88			
			2	9.90	0.10		1.98			
		-S BEAM	2X4	12.30	0.20		19.68			
			2X4	8.70	0.20		13.92			
		-CENTER BEAM	3X2	8.10	0.40		19.44			
							Total	116.70	sqm	202.00
1.7		Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)								
			1	12.60	9.00		113.40			
			2	12.60	0.10		2.52			
			2	9.00	0.10		1.80			
							Total	117.72	sqm	235.00
7	3.2	Providing and laying nominal mix reinforced cement concrete with								



SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
			2X5	2.10	0.40	0.30	2.52			
			2X5	2.10	0.30	0.20	1.26			
			2X4	3.90	0.40	0.20	2.49			
			2X4	3.90	0.30	0.20	1.87			
		-S/S	2X5	2.10	0.20	2.40	10.08			
			2X2	3.90	0.20	2.40	7.48			
			2X5	2.10	0.20	1.20	5.04			
			2X2	3.90	0.20	1.20	3.74			
		Deduction--C G GATE	2	3.90	0.20	2.40	-3.74			
		Deduction--W	14	1.20	0.20	1.50	-5.04			
		Deduction--V	8	0.60	0.20	0.45	-0.43			
		-PARAPET WALL	1	40.80	0.20	0.60	4.89			
		-TOILET	2	3.00	0.20	3.00	3.60			
			2	1.50	0.20	3.00	1.80			
		-S/T	2	3.00	0.30	3.00	5.40			
			2	1.50	0.30	3.00	2.70			
							Total	43.66	cum	3263.00
10	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:								142462.58
			2X5	2.10	0.20	2.40	10.08			
			2X4	3.90	0.20	2.40	14.97			
			2X5	2.10	0.20	1.20	5.04			
			2X4	3.90	0.20	1.20	7.48			
		Deduction--C G GATE	2	3.90	0.20	2.40	-3.74			
		Deduction--W	14	1.50	0.20	1.20	-5.04			
		Deduction--V	8	0.60	0.20	0.45	-0.43			
		-PARAPET WALL	1	40.80	0.20	0.60	4.89			
							Total	33.25	cum	121.00
11	4.22	Providing Water proofing treatment over Roof, Wall, Chhajjas, Balcony with Diamond Shield and Sealer coat or equivalent at leakage/ seepage area consisting of the operation: (i) Surface preparation roughening of surface, opening of cracks in 'V' groove in size of 5mm x 10m (WxD), filling of cracks with putty of Diamond shield with laying fiber glass mesh, Cleaning of surface by scrubbing with steel wire/ Nylon brush. Removing all								4023.25









SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		10mm), laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.								
	13.1	Size 600x600mm								
			1	11.70	8.10		94.77			
			2	11.70	0.60		14.04			
			2	8.10	0.60		9.72			
			1	3.50	3.60		12.60			
			1	3.60	1.50		5.40			
						Total	136.53	sqm	1151.00	157146.03
19	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.								
	7.1	Size upto 200x300mm								
		-TOILET	2	3.00	2.10		12.60			
			2	2.00	2.10		8.40			
						Total	21.00	sqm	587.00	12327.00
20	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.								
	9.1	Size 300x300mm								
		-TOILET FLOOR	1	3.00	2.00		6.00			
						Total	6.00	sqm	692.00	4152.00



SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
21	18.1	Providing and fixing water closet squatting pan (Indian type W.C. pan ), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :								
	1.3	White Orissa pattern W.C. pan of size 580x440 mm								
			1				1.00			
						Total	1.00	each	2899.00	2899.00
22	18.13	Providing and fixing white vitreous china urinal basin with waste fitting as per IS : 2556, and other couplings in C.P. brass complete:								
	13.1	Flat back half stall urinal of size 460x380x250mm								
			2				2.00			
						Total	2.00	each	1776.00	3552.00
23	18.15	Providing and fixing one piece construction white vitreous china squatting plate urinal with an integral rim longitudinal flushing pipe, standard size G.I. flush pipe for back and front flush, C.P. brass coupling complete including cutting and making good the walls and floors etc. wherever required :								
			1				1.00			
						Total	1.00	each	2014.00	2014.00
24	18.76	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC								



SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		approved quality (screwed end):								
	16.2	32 mm nominal bore.								
			2				2.00			
							Total	2.00	each	510.00
31	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.								1020.00
								175.05		
								154.56		
								117.36		
							Total	446.97	sqm	94.50
32	14.9	Distempering with acrylic washable distemper to give an even shade.								42238.66
	9.1	On new work (Two or more coats)								
								175.05		
								154.56		
							Total	329.61	sqm	38.00
33	14.16	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:								12525.18
	18.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)								
								117.36		


SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
						Total	117.36	sqm	74.50	8743.32
34	14.22	Painting on new work (two or more coats) to give an even shade with:								
	22.1	Satin synthetic enamel paint								
		-C G GATE	2	3.90	2.40		18.72			
		-W	14X2	1.50	1.20		50.40			
		-V	8X2	0.60	0.45		4.32			
						Total	73.44	sqm	55.00	4039.20
35	21.17	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)								
			1				1.00			
						Total	1.00	point	1502.00	1502.00
36	21.1	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground								


SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		level.								
	1.1	All types of soil								
	1.1.2	125 mm dia.								
			1	24.90			24.90			
	1.2	Rocky strata including Boulders.				Total	24.90	metre	321.00	7992.90
	2.2	125 mm dia.								
			1	64.50			64.50			
						Total	64.50	metre	349.00	22510.50
37	21.3	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge.								
	3.2	125 mm nominal size dia.								
			1	30.00			30.00			
						Total	30.00	metre	474.00	14220.00
38	21.10	Development of tube well in accordance with IS : 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully developed, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples								



SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		& getting tested in approved laboratory, i/c disinfection of tube well, all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge.								
			1				1.00			
						Total	1.00	Hour	654.00	654.00
39/21.11		Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for bore well of:								
	11.2	125 mm dia								
			1				1.00			
						Total	1.00	each	200.00	200.00

As per Estimate Amount Rs. 1422988.36  
Say Rs.

  
Sub Engineer  
Nagar Palik Nigam  
Korba (C.G.)

  
Asstt Engineer  
Nagar Palik Nigam  
Korba (C.G.)

E.E. Engineer  
Nagar Palik Nigam  
Korba (C.G.)



SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		required.								
	8	Fan regulator (two module size) electronic stepped type moving all rounds								
			15				15.00			
						Total	15.00	Each	203.00	3045.00
4	8.1	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FR PVC insulated, copper conductor, single core cable, earthing etc. complete as required.								
	2	1200 mm sweep								
			15				15.00			
						Total	15.00	Each	1503.00	22545.00
5	8.6	Supplying, installation, testing and commissioning of following sizes heavy duty (continuous running) 1400 rpm exhaust fan in existing opening in wall including earthing etc. complete as required.								
	1	300 mm sweep								
			1				1.00			
						Total	1.00	Each	2558.00	2558.00
6	8.11	Supplying, installation, testing and commissioning of following T-5 fluorescent fitting (luminaries) complete with electronic ballast but without fluorescent lamp, on ceiling/ wall surface, earthing the fitting etc. as required.								
	1	Single box type with decorative end caps						Each	635.00	
7	8.18	Supplying, fixing, testing and commissioning of following CFL (Built in choke type) in existing								

SN	REF	ITEM DESCRIPTION	N	L	B	H/D	QTY	UNIT	RATE	AMOUNT
		lighting luminaries as required.								
	5	20 Watt								
			21				21.00			
						Total	21.00	Each	233.00	4893.00
8	11.3	Supplying and fixing on surface/ recess following way, 240 volts SP&N MCB distribution board consumer unit of sheet steel phosphatized and powder painted, complete with tinned copper busbar, neutral busbar, earth bar, din bar, detachable gland plate, including interconnections, earthing etc. as required. (But without MCB/RCCB/Isolator)								
	2	2 + 8 way								
			2				2.00			
						Total	2.00	Each	816.00	1632.00
9	11.10	Supplying and fixing SP MCB, 240 volts, 'B' curve, suitable for lighting and other loads in the existing MCB DB complete with connections, testing and commissioning etc. as required.								
	1	6 amps to 32 amps								
			1				1.00			
						Total	1.00	Each	154.00	154.00
10	14.2	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as required.								
			1				1.00			
						Total	1.00	Set	3454.00	3454.00

