

कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

फा.क./निर्माण /2019

सिस्टम टेन्डर नं. 53210
ई-निविदा आमंत्रण सूचना

कोरबा, दिनांक 16/07/2019

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्यों हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015ए (सड़क) दिनांक 01.01.2015 से प्रभावशील दर पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु ऑनलाईन ई-निविदा आमंत्रित की जाती है :-

क्र	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की अंतिम तिथि
1	वार्ड क 12 शारदा विहार में बाईपास सड़क के पास आर.सी.सी. नाली एवं आर.सी.सी. नाला एवं सीमेंट कांकीट सड़क का निर्माण कार्य	49.00	368000/-	06 माह	वर्ग डी एवं प्रवर श्रेणी	06.08.2019 से


शर्त:-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक र आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पेन नम्बर, जी.एस.टी. पंजीयन प्रमाण पत्र एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्कैन कापी ऑनलाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- जिन निविदाकारों द्वारा कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो निविदाकार ही निविदा हेतु पात्र होंगे।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाई एश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
- प्रयुक्त लोहा का बिल एवं टेस्ट रिपोर्ट तथा प्रयुक्त सीमेंट का बिल संलग्न करना अनिवार्य होगा।
- निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
- निविदा अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने अथवा निरस्त करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- उपरोक्त निविदा सूचना की विस्तृत प्रति नगर पालिक निगम, कोरबा के साकेत भवन स्थित निर्माण शाखा से प्राप्त किये सकते हैं।

कार्यपालन अभियन्ता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		16.07.19	20.30	16.07.19	12.30	Release Tender
2		Bid Submission	16.07.19	12.30	05.08.19	17.30	
3	Tender Open		06.08.19	10.30	--	--	


EXECUTIVE ENGINEER
KORBA (CG)
 For, Commissioner Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


Abstract


Name Of Work - Construction of R.C.C. Drain and R.C.C. Nala Near By Pass Road At Sharda Vihar ward no 12

Schedule of rates public works department [PWD BUILDING-01-01-2015]

S. N.	SOR Ref.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.				
	3.3	in cement mortar	Cum	41.60	263.00	10940.80
2	16.4	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.				
			Cum	17.60	768.00	13516.80
3	16.4	Demolishing cement concrete including disposal of material within 50 metre lead				
	43.2	1:3:6 or richer mix	Cum	10.80	549.00	5929.20
4	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1	In all types of soil				
			Cum	1096.75	185.00	202898.75
5	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.				
			Cum	82.25	371.00	30514.75
6	2.1	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1	Foundations, footings, base of columns and plinth beam in any shape and size.				
			Sqm	1982.00	139.00	275498.00
		Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in	Sqm	29.00	235.00	6815.00
7	3.1	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.				
	3	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).				
			Cum	98.25	2970.00	291802.50

	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).				
			Cum	311.30	4163.00	1295941.90
9	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	1	Thermo-Mechanically treated bars FE 415	Kg	21791.00	54.50	1187609.50
10	9.6	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.				
	9.6.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.				
			Kg	350.00	68.00	23800.00
11	3.9	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.				
			Cum	30.00	469.00	14070.00
12	1.26	Carriage by mechanical transport upto 5 km lead				
	26.1	Earth	Cum	768.47	111.00	85300.17
13	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	Cum	460.00	65.00	29900.00
TOTAL =						3474537.37


 Sub Engineer
 Municipal Corporation
 Korba (C.G.)


 Asstt. Engineer
 Municipal Corporation
 Korba (C.G.)

OFFICE OF THE MUNICIPAL CORPORATION, KORBA (C.G.)


Abstract


Name of work - Construction of Cement Concrete Road Near By Pass Road at Sharda Vihar Ward No.12

Schedule of rates public works department[PWD ROAD-01-01-2015]

S. N.	SOR Ref.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.1	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300..				
			CUM	301.20	140.00	42168.00
2	6.6	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads)				
	I	P.C.C. M-10	CUM	115.40	2789.00	321850.6
3	6.7	Providing and laying unreinforced cement concrete without dowel bar including form work and expansion, contraction and longitudinal joint as per design or as per IRC - 62-2014 over a prepared base as per approved mix design and finishing to lines and grade as per Drawings for pavement thickness less than 200 mm in low volume Roads				
	(I)	plain Cement concrete grade M-30 and minimum cement content @ 375 kg/cum.				
			CUM	230.80	4391.00	1013442.80

TOTAL 1377461.40


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asstt. Engineer
Municipal Corporation
Korba (C.G.)

NON SOR ITEM


1	Shifting of pipe line of any size including excavation ,cutting,threading,fixing all complete.				
		point	40.00	1200.00	48000.00
				total=	48000.00


PART A = 3474537.37

→ B = 1377461.40

4899998.77

say = 4900,000.00


Sub Engineer
Municipal Corporation
Korba (C.G.)


Asstt. Engineer
Municipal Corporation
Korba (C.G.)