

कार्यालय, नगर पालिक निगम, कोरबा (छत्तीसगढ़)

फा.क./ निर्माण/2019/8365

सिस्टम टेंडर नं. 53502

कोरबा दिनांक 22.07.2019

ई-निविदा आमंत्रण सूचना

कार्यालय नगर पालिक निगम, कोरबा द्वारा लोक निर्माण विभाग एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से प्रमुख अभियंता लोक निर्माण विभाग, रायपुर द्वारा भवन कार्य हेतु दिनांक 01.01.2015 एवं सड़क कार्य हेतु दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ शेड्यूल अनुसार प्रतिशत दर पर ई-प्रोक्चुरमेंट (E-Tendering) के माध्यम से निविदाएं आमंत्रित की जाती है :-


क्र.	कार्य का नाम	प्राक्कलन राशि (लाख में)	धरोहर राशि	कार्यावधि	ठेकेदार का वर्ग	निविदा खुलने की तिथि
1	वार्ड क 16 अंतर्गत मेन रोड से भवानी मंदिर तक डामरीकृत सड़क का चौड़ीकरण एवं रिटेनिंगवाल का निर्माण कार्य	34.25	25700/-	03 माह (वर्षा ऋतु छोड़कर)	वर्ग डी एवं प्रवर श्रेणी	13.08.2019 से

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जाये सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- इच्छुक ठेकेदारों को उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पाटर्नरशीप डीड) की सत्य प्रतिलिपि, पूर्व में इस प्रकार के किये गये कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी, आयकर प्रमाण पत्र/पैन नम्बर, **जी.एस.टी. पंजीयन प्रमाण पत्र** एवं अमानत राशि ऑनलाईन जमा करना अनिवार्य होगा, प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र, कर्मचारी भविष्य निधि रायपुर से पंजीकरण का कोड एवं धरोहर राशि का स्केन कापी ऑन लाईन सिस्टम पर अपलोड करना अनिवार्य होगा।
- सम्पूर्ण किये गये कार्यों के लिए प्रत्येक चल देयकों में से 5 प्रतिशत सुरक्षा राशि 01 वर्ष के लिए एवं 5 प्रतिशत परफार्मेंस सिक्यूरिटी की गारंटी के रूप में से 03 वर्ष के लिए रोकी जावेगी।
- निविदा उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम, रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रदाय नहीं किया जावेगा।
- निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में उनके द्वारा किये जा रहे कार्यों का विवरण राशि सहित मूलप्रति में वैध शपथपत्र देना अनिवार्य होगा।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तदंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का **1 प्रतिशत उपकर** के रूप में प्रत्येक देयक से कटौती की जावेगी।
- ईट से संबंधित निर्माण कार्यों में फ्लाइ एश ब्रिक्स का उपयोग किया जाना अनिवार्य होगा।
- सशर्त निविदा स्वीकार नहीं की जावेगी। निविदा उन्हीं ठेकेदारों को दी जाएगी जिन्हें इस प्रकार के कार्य का अनुभव हो।
- निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त का निर्णय अंतिम एवं सर्वमान्य होगा।
- निविदा स्वीकृत करने अथवा अस्वीकृत करने का अधिकार नगर पालिक निगम के पास सुरक्षित रहेगा।
- अन्य सूचनाएं नगर पालिक निगम, साकेत भवन रामपुर कोरबा कार्यालय में प्राप्त की जा सकती है।
- बिना कारण बताये निविदा स्वीकृत/अस्वीकृत या पूर्ण रूप से अमान्य करने का अधिकार सक्षम अधिकारी/प्राधिकारी को रहेगा।
- डामरीकरण कार्य का निविदा प्रपत्र कय करते समय ठेकेदार को स्वयं के स्वामित्व के आटोमेटिक ड्रम मिक्स प्लांट, रोलर एवं अन्य मशीनरी, हॉट मिक्स प्लांट, पेवर फिनिशर एवं रोड रोलर आदि मशीनों के प्रमाण पत्र आवेदन के साथ संलग्न करना आवश्यक होगा तथा निविदाकार का 60 किमी. की परिधि में हॉल मिक्स प्लांट होना आवश्यक है।
- ठेकेदार द्वारा 60/70 ग्रेड का डामर IOC, BPCL, HPCI से ही कय कर लगाना होगा। ठेकेदार को तेल कंपनी को दी जाने वाली प्रदाय आदेश की प्रतिलिपि इस कार्यालय को देनी होगी।
- कार्य में प्रयुक्त डामर खरीदी के देयक (बिल) कार्यालय में प्रस्तुत करने पर ही भुगतान किया जायेगा।
- जब निविदा के दरों में असामान्य कमी प्रतीत हो तब सफल निविदादाता से अनुबंध के समय अतिरिक्त परफार्मेंस राशि जमा कराई जावेगी, जबकि निविदा की दरों में काफी कमी हो, जैसे निविदादाता को अनुमानित लागत से 10 प्रतिशत से कम निविदा दर होने पर सफल निविदादाता को निविदा दर एवं अनुमानित लागत के 90 प्रतिशत के अंतर की राशि के समतुल्य परफार्मेंस गारंटी के रूप में राष्ट्रीयकृत बैंक का एफ.डी.आर. पोस्ट ऑफिस टाईम डिपॉजिट, एन.एस.सी. जो कि संबंधित निकाय के आयुक्त /मुख्य नगर पालिका अधिकारी के नाम से देय होगा, जमा कराना अनिवार्य होगा उपरोक्त राशि को जमा न कराने की दशा में निविदा निरस्त कर दी जावेगी।

कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छत्तीसगढ़)

Date-Time Detail(s)

Seq. No.	Nagar Nigam Stage	Contractor Stage	Start		Expiry		Remarks
			Date	Time	Date	Time	
1	Release Tender		22.07.19	20.30	22.07.19	20.30	Release Tender
2		Bid Submission	22.07.19	20.30	12.08.19	17.30	
3	Tender Open		13.08.19	10.30	--	--	


**EXECUTIVE ENGINEER
KORBA (CG)
For, Commissioner Korba (C.G.)**



OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

ABSTRACT


Name of Work **CONSTRUCTION OF RETAINING WALL & WIDENING OF TAAR ROAD AT KOHADIYA, MAIN ROAD TO BHAWANI MANDIR
WARD NO -16 PART -A**

As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD ROAD-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	3.11	Scarifying existing bituminous surface to a depth of 50 mm (Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead up to 1000 meters) as per clause 305.4.3.	Sqm.	200	23.00	4,600.00
2	2.1	Cutting of trees , including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable material with all lifts and up to a lead of 1000 mtrs and earth filling in the depression/pit and as per relevant clauses of section-200 for :-				
	i)	Girth from 300 mm to 600 mm	Each.	17	197.00	3,349.00
	ii)	Girth beyond 600 mm to 900 mm	Each.	8	353.00	2,824.00
3	2.2	Clearing Grass and Removal of Rubbish (clearing grass and removal of rubbish up to a distance of 50 meters outside the periphery of the area) in thickness if required and as per relevant clauses of section- 200	Hectare.	0.24	13438.00	3,225.12
4	4.1	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401				
	A	Plant mix method (with Mechanically crushed stone only)				
	(a)	For Lower Sub-base with				
	(i)	Grading-III Material	Cum.	280.00	1423.00	398,440.00
5	4.10	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)	Cum	210.00	1434.00	301,140.00
6	9.2	Providing and laying Reinforced Cement Concrete pipe NP 4 / prestressed concrete pipe on first class bedding (Laying Reinforced cement concrete pipe NP4/prestressed concrete pipe for culverts on first class bedding of granular material including fixing collar with cement mortar 1:2 and bedding as per clause 2904 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets .)				
	B	900 mm dia	Meter	13	6147.00	79,911.00
7	5.2	Tack coat Providing and applying tack coat with bitumen emulsion (RS-1, grade confirming to IS:8887) using emulsion pressure distributor on the prepared bituminous/granular surface cleaned with mechanical broom and as per clause 503.				
	(i)	Bituminous surface @ 0.25 kg /Sqm	Sqm	6400.00	15.00	96,000.00
8	5.3	Bituminous Macadam (Providing and laying bituminous macadam as per clause 504 with mixed prepared in minimum 40-60 TPH capacity hot mix plant using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and				

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	rolled to achieve the desired compaction)				
B	With mechanical paver finisher				
(ii)	for Grading-II(19 mm nominal maximum size, bitumen content 3.40%)	Cum	140.00	6255.00	875,700.00
II.	With mechanical paver finisher				
A	With bitumen				
ii)	Type B (13.2 mm to 0.09 mm size aggregates)	Sqm	2800.00	146.00	408,800.00

As per Estimate Amount Rs. 2173989.12



 Sub Engineer
 Nagar Palik Nigam
 Korba(C.G.)

Asst. Engineer
 Nagar palik Nigam
 korba(C.G.)

OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)
ABSTRACT

Name of Work CONSTRUCTION OF RETAINING WALL & WIDENING OF TAAR ROAD AT KOHADIYA MAIN ROAD TO BHAWANI MANDIR
PART -B
As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	72.50	185.00	13,412.50
2	1.17	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	cum	767.50	65.00	49,887.50
3	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	10.87	371.00	4,032.77
4	1.26	Carriage by mechanical transport upto 5 km lead:				
	26.1	Earth	cum	767.50	111.00	85,192.50
5	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	788.00	139.00	109,532.00
6	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	10.87	2659.00	28,903.33
7	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	129.80	4163.00	540,357.40
8	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	7700.00	54.50	419,650.00
As per Estimate Amount Rs.						1250968.00


Sub Engineer
Nagar Palik Nigam
Korba(C.G.)

Asst. Engineer
Nagar palik Nigam
korba(C.G.)