



कार्यालय, नगर पालिक निगम, कोरबा (छ.ग.)

मुख्य कार्यालय – साकेत भवन, आई.टी.आई. चौक, कोरबा (छ.ग.)

मु.का. दूरभाष : 221288, 222672, फैक्स : 07759-221929, पो. बॉक्स नं.-12 पिन कोड – 495677

फा.क्र./8373/8383/8385/8386/8387/8392 से 8395/टी.पी. नगर जोन/ 2019/

कोरबा, दिनांक 23.07.2019

निविदा आमंत्रण की सूचना

लोक निर्माण विभाग से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु प्रमुख अभियन्ता लोक निर्माण विभाग, रायपुर द्वारा (भवन) दिनांक 01.01.2015 से प्रभावशील दर अनुसूची पर (निविदा खुलने के दिनांक तक समस्त संशोधनों के साथ) कम अधिक या समान दरों पर तथा शेड्यूल अनुसार आयटम दरों पर निम्नलिखित निर्माण कार्य हेतु मैन्युअल/ऑनलाईन निविदा वेबसाइट से डाउनलोड कर आमंत्रित की जाती है :-

क्र.	कार्य का नाम	प्राक्कलन राशि में	धरोहर राशि रु में	निविदा प्रपत्र का मूल्य	कार्यावधि	ठेकेदार का वर्ग	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा प्रपत्र प्राप्त करने की अंतिम तिथि	निविदा खुलने की अंतिम तिथि
1	परिवहन नगर जोन अंतर्गत आर.सी. सी. नाली का मरम्मत एवं प्रीकास्ट स्लेब डकने का कार्य। (मरम्मत संधारण मद)	4,00,000/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
2	वार्ड क्र. 15 के नैसखटाल बस्ती में सी.सी. रोड का मरम्मत कार्य। (मरम्मत संधारण मद)	3,94,300/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
3	वार्ड क्र. 15 के ढोडीपारा बस्ती में नाली का मरम्मत कार्य। (मरम्मत संधारण मद)	3,97,400/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
4	परिवहन नगर जोन अंतर्गत सी.एस. ई.बी चौक से शारदा विहार चौक तक रोड डिक्वाइंडर का मरम्मत कार्य। (मरम्मत संधारण मद)	3,99,400/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
5	वार्ड क्र. 15 अंतर्गत दुर्गा पंडाल के पास किचन कक्ष का मरम्मत कार्य। (मरम्मत संधारण मद)	3,06,300/-	3,100/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
6	वार्ड क्र. 03 राताखार गणेश चौक से सोसायटी तक सी.सी. रोड एवं नाली का मरम्मत कार्य। (मरम्मत संधारण मद)	4,00,000/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
7	वार्ड क्र. 03 राताखार अंतर्गत टॉयर चौक में सी.सी. रोड एवं नाली का मरम्मत कार्य। (मरम्मत संधारण मद)	4,00,000/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
8	वार्ड क्र. 02 परिवहन नगर में व्यावसायिक कामप्लेक्स का मरम्मत कार्य। (मरम्मत संधारण मद)	3,40,700/-	3,500/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019
9	निगम भवनों का मरम्मत कार्य। (मरम्मत संधारण मद)	3,98,000/-	4,000/-	750/-	03 माह	सक्षम श्रेणी	06.08.2019	09.08.2019	16.08.2019

शर्तें-

- निविदा दरे प्रचलित सी.एस.आर.से कम या अधिक प्रतिशत दरों पर दिया जावे सी.एस.आर.के अंतर्गत के आयटमों पर पृथक से आयटम दरों का उल्लेख करने पर निविदा निरस्त मानी जावेगी।
- निविदा प्रपत्र की प्रतियाँ नगर पालिक निगम, साकेत भवन रामपुर, कोरबा कार्यालय से उपरोक्त कार्यों हेतु नाम के सममुख अंकित राशि नगद जमा कर उपर लिखित तिथि तक सायं 5:00 बजे तक अवकाश के दिनों को छोड़कर प्राप्त की जा सकती है। यदि निविदा प्रपत्र डाक द्वारा संगाना हो तो रु. 50/- अधिक भेजने होंगे तथा निविदा समय पर मिलने या न मिलने की जिम्मेदारी इस कार्यालय की नहीं होगी।
- निविदा प्रपत्र स्पीड पोस्ट अथवा पंजीकृत डाक के माध्यम से ही स्वीकार किए जावेगे। निर्धारित तिथि को 3.00 बजे के पश्चात् प्राप्त निविदाएँ स्वीकार नहीं की जावेंगी।
- जिन ठेकेदारों द्वारा नगर पालिक निगम (साडा) के किसी ठेके के कार्य में अनुबंध के अनुरूप कार्य न किया गया हो अथवा नगर पालिक निगम (साडा) के हित के विरुद्ध कार्य किया गया हो उन्हें निविदा भरने की पात्रता नहीं होगी।
- निविदा प्रपत्र प्राप्त करने हेतु इच्छुक ठेकेदारों को आवेदन पत्र के साथ उचित वर्ग में पंजीयन की प्रमाणित प्रतिलिपि यदि साझेदारी फर्म हो तो उसका प्रमाण पत्र (पार्टनरशीप डीड)की सत्य प्रतिलिपि, पूर्व में इस प्रकार की किए गए कार्यों की प्रमाणित सूची, उपलब्ध तकनीकी अमले की जानकारी पिछले वित्तीय वर्ष का आय प्रमाण पत्र/पैन नम्बर पत्र एवं जी.एस.टी. पंजीयन प्रमाण पत्र प्रशिक्षित यंत्री नियुक्त करने संबंधी प्रमाण पत्र एवं धरोहर राशि सहित निविदा प्रपत्र प्राप्त करने के अंतिम तिथि को 5.30 बजे सायं तक आवेदन प्रस्तुत करना अनिवार्य होगा।
- पूर्ण रूप से भरी निविदा प्रपत्र उपरोक्त तिथि को 15.00 बजे तक प्राप्त की जा सकती है और उसी दिन 16.00 बजे ठेकेदारों एवं उनके प्रतिनिधि यदि वे उपस्थित होना चाहे तो उनके सम्क्ष खोले जावेंगे।
- सम्पूर्ण किये गये कार्यों के लिये 5 प्रतिशत सुरक्षा राशि देयको से 01 वर्ष की गारंटी के लिये रोकी जावेगी।
- निविदा में भाग लेने वाले ठेकेदारों को छ.ग. भवन और अन्य सन्निर्माण कर्मकार (नियोजन एवं सेवा शर्तों का विनियमन) अधिनियम 1996 एवं तद्अंतर्गत निर्धारित नियमों के तहत पंजीयन कराना आवश्यक होगा तथा निर्माण लागत का 1 प्रतिशत उपकर के रूप में प्रत्येक देयक से कटौती की जावेगी।

ठेके से संबंधित निविदा प्रपत्र उन्हीं ठेकेदारों को प्रदाय किये जावेंगे जो कि कर्मचारी भविष्य निधि संगठन एवं कर्मचारी राज्य बीमा निगम रायपुर से पंजीयन कराकर कोड प्राप्त कर लिया हो अन्यथा निविदा प्रपत्र प्रदाय नहीं किया जावेगा।

10. निविदाकार को प्रत्येक निविदा में पंजीयन क्षमता के अंतर्गत वर्तमान में नगर निगम या अन्य विभागों में किये जा रहे कार्यों का विवरण राशि सहित मूल प्रति में शपथ पत्र देना अनिवार्य होगा।
11. ईट से संबंधित निर्माण कार्यों में फ्लाई ऐश ब्रिक का उपयोग किया जाना अनिवार्य होगा।
12. कार्य में उपयोग हेतु 43 ग्रेड ओ.पी.सी. सीमेंट की खरीदी ठेकेदारों को स्वयं करनी होगी।
13. निविदा दरों असामान्य कमी प्रतीत होने पर सफल निविदा दाता से अनुबंध के पूर्व एस.ओ.आर. एवं निविदा दर की अंतर की राशि के समतुल्य परफारमेंस गारंटी के रूप में राष्ट्रीयकृत बैंक एफ.डी.आर., पोस्ट ऑफिस, टाईम डिपॉजिट अथवा एन.एस.सी. जो कि आयुक्त नगर पालिक निगम, कोरबा के नाम पर देय होगा जो मांग तिथि से 15 दिवस के भीतर जमा करना अनिवार्य होगा। उपरोक्त राशि समयावधि में जमा न करने की दशा में निविदा स्वमेव निरस्त मानी जावेगी।
14. निविदा प्रपत्र अहस्तांतरणीय होगा एवं सशर्त निविदाओं पर विचार नहीं किया जावेगा।
15. निविदा के संबंध में किसी प्रकार की विवाद होने की स्थिति में आयुक्त के द्वारा अधिनस्त अधिकारियों का निर्णय अंतिम एवं सर्वमान्य होगा।
16. निविदा प्रपत्र कय कर अथवा वेबसाईट से सीधे डाउनलोड कर निविदा प्रपत्र हेतु निर्धारित राशि की अतिरिक्त डिमॉंड ड्राफ्ट सहित अपनी भरी हुई निविदा नगर पालिक निगम में रजिस्टर्ड/स्पीड पोस्ट द्वारा अमानत राशि के साथ प्रस्तुत करें।

नोट:-

1. अमानत राशि के रूप में एफ.डी.आर./टी.डी.आर. अथवा नगद जमा रसीद पृथक से लिफाफे में स्वीकार किए जावेंगे आयुक्त, नगर पालिक निगम, कोरबा के नाम पर देय हो।
2. उपरोक्त तिथियों में किसी भी तिथि को शासकीय/स्थानीय अवकाश होने की स्थिति में अगले कार्य दिवस को निर्धारित तिथि समय एवं स्थान माना जावे।



कार्यपालन अभियंता
नगर पालिक निगम
कोरबा (छ.ग.)



OFFICE OF THE NAGAR PALIK NIGAM, KORBA (C.G.)

ABSTRACT

Name of Work **MAINTENANCE OF NIGAM BUILDING AT KORBA**


As per SOR : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]


S.N	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	17.1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :				
	1.1	Thickness upto 15mm	sqm	31	132.00	4,092.00
2	17.9	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 metres lead :				
3	9.1	Door chowkhats	each	2.00	441.00	882.00
	16.3	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead.				
	3.2	In lime mortar.	cum	7.06	187.00	1,320.22
4	16.43	Demolishing cement concrete including disposal of material within 50 metre lead.				
	43.2	1:3:6 or richer mix	cum	0.54	549.00	296.46
5	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.				
	1.1	In all types of soils.	cum	10.14	185.00	1,875.90
6	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	0.98	371.00	363.58
7	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:				
	1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	sqm	25.84	139.00	3,591.76
	1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	sqm	23	297.00	6,831.00
	1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	sqm	8.4	235.00	1,974.00
8	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	1.38	2659.00	3,669.42
	1.5	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	6.87	4073.00	27,981.51
9	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.				
	2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	cum	6.30	4163.00	26,226.90

S.	REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
10	12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:				
	12.1	Thermo-Mechanically treated bars FE 415	kg	390	54.50	21,255.00
11	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:				
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	23.78	3263.00	77,594.14
12	7.6	Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	cum	10.00	121.00	1,210.00
13	9.3	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer.				
	3.1	Electric resistance or induction butt welded tubes Grade-250	kg	165	88.50	14,602.50
14	9.13	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	kg	125	75.00	9,375.00
15	10.17	Providing asbestos cement 6mm thick corrugated or semi corrugated sheets roofing fixed with galvanized J or L hooks, bolts and nuts 8mm dia G.I. plain bitumen washers complete excluding the cost of purlins, rafters and trusses.	sqm	36.9	347.00	12,804.30
16	11.1	Providing and making 6mm thick cement plaster of mix:				
	1.2	In Cement mortar 1:4 (1 cement : 4 fine sand)	sqm	10.8	87.00	939.60
17	11.2	Providing and making 12mm thick cement plaster of mix:				
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	126.15	91.50	11,542.72
18	11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:				
	3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	126.15	107.00	13,498.05
19	12.3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.				
	3.2	50 mm thick	sqm	38	254.00	9,652.00
20	12.12	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	sqm	41.5	963.00	39,964.50
21	12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.				
	7.1	Size upto 200x300mm	sqm	29.4	587.00	17,257.80
22	12.9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.				
	9.1	Size 300x300mm	sqm	7.6	692.00	5,259.20
23	14.9	Distempering with acrylic washable distemper to give an even shade.				
	9.1	On new work (Two or more coats)	sqm	209.6	38.00	7,964.80
24	14.13	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI,	sqm	283.52	94.50	26,792.64

REF	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Nerolac, J.K. wall putty) on walls to make the surface smooth and even.				
25	14.1 Finishing walls with water proofing cement paint of required shade to give an even shade.				
	14.1 On new work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	323.8	41.00	13,275.80
26	14.22 Painting on new work (two or more coats) to give an even shade with:				
	22.1 Satin synthetic enamel paint	sqm	70.15	55.00	3,858.25
27	18.1 Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	1.1 White Long pattern W.C. pan of size 580 mm	each	1.00	2459.00	2,459.00
28	18.17 Providing and fixing vitreous china wash basin with C.I. brackets, 32 mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required :				
	17.1 White Size 550x450 mm	each	3.00	1430.00	4,290.00
29	18.4 Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required :				
	4.1 White pedestal type	each	1.00	2882.00	2,882.00
30	12.45 15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above)				
	45.2 Granite stone black	sqm	4.8	2646.00	12,700.80
31	19.13 Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality:				
	13.2 Bib cock (350 grams)	each	4.00	237.00	948.00
	13.3 Stop cock (350 grams)	each	4.00	237.00	948.00
32	19.17 Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete :				
	17.1 15 mm nominal bore	each	5.00	284.00	1,420.00
33	19.4 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. INTERNAL WORK - EXPOSED ON WALL				
	4.1 15 mm nominal outer dia. Pipes.	metre	50.00	110.00	5,500.00
34	9.51 Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete. (Cost of aluminium snap beading shall be paid in basic item):				
	51.1 With float glass panes of 4 mm thickness	sqm	1.5	611.00	916.50

As per Estimate Amount Rs. **398015.35**


Sub Engineer
Nagar Palik Nigam
Korba(C.G.)


Asst. Engineer
Nagar palik Nigam
korba(C.G.)